

Archosauriform footprints in the Lower Triassic of Western Alps and their role in understanding the effects of the Permian-Triassic hyperthermal (#51782)

1

First submission

Guidance from your Editor

Please submit by **24 Aug 2020** for the benefit of the authors (and your \$200 publishing discount) .



Structure and Criteria

Please read the 'Structure and Criteria' page for general guidance.



Custom checks

Make sure you include the custom checks shown below, in your review.



Raw data check

Review the raw data.



Image check

Check that figures and images have not been inappropriately manipulated.

Privacy reminder: If uploading an annotated PDF, remove identifiable information to remain anonymous.

Files

Download and review all files from the [materials page](#).

11 Figure file(s)

1 Video file(s)

! Custom checks

New species checks



Have you checked our [new species policies](#)?



Do you agree that it is a new species?



Is it correctly described e.g. meets ICZN standard?



Structure and Criteria

Structure your review

The review form is divided into 5 sections. Please consider these when composing your review:

1. BASIC REPORTING
2. EXPERIMENTAL DESIGN
3. VALIDITY OF THE FINDINGS
4. General comments
5. Confidential notes to the editor

 You can also annotate this PDF and upload it as part of your review

When ready [submit online](#).

Editorial Criteria

Use these criteria points to structure your review. The full detailed editorial criteria is on your [guidance page](#).

BASIC REPORTING

-  Clear, unambiguous, professional English language used throughout.
-  Intro & background to show context. Literature well referenced & relevant.
-  Structure conforms to [PeerJ standards](#), discipline norm, or improved for clarity.
-  Figures are relevant, high quality, well labelled & described.
-  Raw data supplied (see [PeerJ policy](#)).

EXPERIMENTAL DESIGN

-  Original primary research within [Scope of the journal](#).
-  Research question well defined, relevant & meaningful. It is stated how the research fills an identified knowledge gap.
-  Rigorous investigation performed to a high technical & ethical standard.
-  Methods described with sufficient detail & information to replicate.

VALIDITY OF THE FINDINGS

-  Impact and novelty not assessed. Negative/inconclusive results accepted. *Meaningful* replication encouraged where rationale & benefit to literature is clearly stated.
-  All underlying data have been provided; they are robust, statistically sound, & controlled.
-  Speculation is welcome, but should be identified as such.
-  Conclusions are well stated, linked to original research question & limited to supporting results.

Standout reviewing tips

3



The best reviewers use these techniques

Tip

Support criticisms with evidence from the text or from other sources

Example

Smith et al (J of Methodology, 2005, V3, pp 123) have shown that the analysis you use in Lines 241-250 is not the most appropriate for this situation. Please explain why you used this method.

Give specific suggestions on how to improve the manuscript

Your introduction needs more detail. I suggest that you improve the description at lines 57- 86 to provide more justification for your study (specifically, you should expand upon the knowledge gap being filled).

Comment on language and grammar issues

The English language should be improved to ensure that an international audience can clearly understand your text. Some examples where the language could be improved include lines 23, 77, 121, 128 – the current phrasing makes comprehension difficult.

Organize by importance of the issues, and number your points

1. Your most important issue
2. The next most important item
3. ...
4. The least important points

Please provide constructive criticism, and avoid personal opinions

I thank you for providing the raw data, however your supplemental files need more descriptive metadata identifiers to be useful to future readers. Although your results are compelling, the data analysis should be improved in the following ways: AA, BB, CC

Comment on strengths (as well as weaknesses) of the manuscript

I commend the authors for their extensive data set, compiled over many years of detailed fieldwork. In addition, the manuscript is clearly written in professional, unambiguous language. If there is a weakness, it is in the statistical analysis (as I have noted above) which should be improved upon before Acceptance.

Archosauriform footprints in the Lower Triassic of Western Alps and their role in understanding the effects of the Permian-Triassic hyperthermal

Fabio M. Petti¹, Heinz Furrer², Enrico Collo³, Edoardo Martinetto⁴, Massimo Bernardi¹, Massimo Delfino⁴, Marco Romano^{Corresp., 5}, Michele Piazza⁶

¹ MUSE – Museo delle Scienze, Trento, Trento, Italy

² Paläontologisches Institut und Museum, Universität Zürich, Zürich, Switzerland

³ Natura Occitana, Dronero (CN), Dronero (CN), Italy

⁴ Dipartimento di Scienze della Terra, Università degli Studi di Torino, Torino, Italy

⁵ Scienze della Terra, University of Roma "La Sapienza", Rome, Italy

⁶ Dipartimento di Scienze della Terra, dell'Ambiente e della Vita, Università di Genova, Genoa, Italy

Corresponding Author: Marco Romano

Email address: marco.romano@uniroma1.it

The most accepted killing model for the Permian-Triassic mass extinction (PTME) postulates that massive volcanic eruption (i.e. the Siberian Traps LIP) led to geologically rapid global warming, acid rain and ocean anoxia. On land, habitable zones were drastically reduced, due to the combined effects of heating, drought and acid rains. This hyperthermal had severe effects also on the paleobiogeography of several groups of organisms. Among those, the tetrapods, whose geographical distribution across the end-Permian mass extinction (EPME) was the subject of controversy of a number of recent papers. We here describe and interpret a new Early Triassic (?Olenekian) archosaur track assemblage from the Gardetta Plateau (Briançonnais, Western Alps, Italy) which, at the Permian-Triassic boundary, was placed at about 11° North. The tracks, both arranged in trackways and documented by single, well-preserved imprints, are assigned to *Isochirotherium gardettae* ichnosp. nov., and are here interpreted as produced by a non-archosaurian archosauriform (erytrosuchid?) trackmaker. This new discovery provides further evidence for the presence of archosauriformes at low latitudes during the Early Triassic epoch, supporting a model in which the PTME did not completely vacate low-latitude lands from tetrapods that therefore would have been able to cope with the extreme hot temperatures of Pangaea mainland.

Archosauriform footprints in the Lower Triassic of Western Alps and their role in understanding the effects of the Permian-Triassic hyperthermal

Fabio M. Petti¹, Heinz Furrer², Enrico Collo³,

Edoardo Martinetto⁴, Massimo Bernardi¹, Massimo Delfino⁴, Marco Romano^{5,*}

and Michele Piazza⁶

¹MUSE – Museo delle Scienze, Trento

²Paläontologisches Institut und Museum, Universität Zürich, Zürich

³Natura Occitana, Dronero (CN)

⁴Dipartimento di Scienze della Terra, Università degli Studi di Torino, Torino

⁵Dipartimento di Scienze della Terra, Sapienza Università di Roma, Roma

⁶Dipartimento di Scienze della Terra, dell'Ambiente e della Vita, Università di Genova, Genova

*Corresponding author e-mail: marco.romano@uniroma1.it

Key words: *Isochirotherium gardettae* n. ichnosp., climate warming, extinction, Lower Triassic, Italy.

23

24 ABSTRACT

25 The most accepted killing model for the Permian-Triassic mass extinction (PTME) postulates
 26 that massive volcanic eruption (i.e. the Siberian Traps LIP) led to geologically rapid global
 27 warming, acid rain and ocean anoxia. On land, habitable zones were drastically reduced, due to
 28 the combined effects of heating, drought and acid rains. This hyperthermal had severe effects
 29 also on the paleobiogeography of several groups of organisms. Among those, the tetrapods,
 30 whose geographical distribution across the end-Permian mass extinction (EPME) was the subject
 31 of controversy of a number of recent papers. We here describe and interpret a new Early Triassic
 32 (?Olenekian) archosaur track assemblage from the Gardetta Plateau (Briançonnais, Western
 33 Alps, Italy) which, at the Permian-Triassic boundary, was placed at about 11° North. The tracks,
 34 both arranged in trackways and documented by single, well-preserved imprints, are assigned to
 35 *Isochirotherium gardettae* ichnosp. nov., and are here interpreted as produced by a non-
 36 archosaurian archosauriform (erytrosuchid?) trackmaker. This new discovery provides further
 37 evidence for the presence of archosauriformes at low latitudes during the Early Triassic epoch,
 38 supporting a model in which the PTME did not completely vacate low-latitude lands from
 39 tetrapods that therefore would have been able to cope with the extreme hot temperatures of
 40 Pangaea mainland.

41

42

43 INTRODUCTION

44

The Permian-Triassic mass extinction (PTME) was the most severe biotic crisis of all times (Erwin, 1993), eliminating > 90% of marine and terrestrial species (Erwin, 1993; Song et al., 2013, 2015). After the mass extinction, totally new clades emerged, which include decapods and marine reptiles in the oceans and new tetrapods on land (Chen and Benton, 2012). In the last decade different physical environmental shocks have been identified as possible triggers for the huge crisis, which include increased atmospheric CO₂ concentrations, global warming, acid rain, ocean anoxia, ocean acidification and hypercapnia (Chen and Benton, 2012; Benton, 2018). The most accepted killing model (e.g. Benton & Twitchett, 2003; Chen & Benton, 2012; Benton & Newell, 2014; Shen et al., 2019) postulates an initial megascale eruption (more than 1,000 Gigatonnes of erupted lava, see Grasby et al., 2011), that released consistent amount of sulphate aerosols and methane from clathrate reservoirs (see Berner, 2002), which led to global warming and acid rain, causing a generalized plant die-offs and thus intensive erosion of the soil (Wignall, 2001; Benton, 2003, 2018; Benton & Twitchett, 2003; Sephton et al., 2005; Knoll et al., 2007). On land, habitable zones were drastically reduced, due to the combination of extreme heat, drought and acid rains, which caused progressive loss of soil and forests and had direct impact on lacustrine organisms and any land-dwelling animal (Benton & Newell, 2014).

According to several authors (Joachimski et al., 2012; Sun et al., 2012; Schobben et al., 2014; Song et al., 2015) the intense global warming started at the extinction horizon as testified in the Meishan section (South China), and then continued in the Early Triassic, very likely with the release of methane from deep ocean sediments and coals that triggered the process, and the release of additional greenhouse gasses by interactions of the Siberian traps with local permafrost soils, limestones, and other deposits rich in organic matter (e.g. Racki, 2003; Racki & Wignall, 2005; Retallack & Jahren, 2008; Grasby et al., 2011).



The hyperthermal had severe effects also on the paleobiogeographic patterns. In the last years the distribution of land tetrapods across the PTME was discussed by a number of studies which however suggested different scenarios. By compiling literature evidence on the main skeletal findings, Sun et al. (2012) suggested that, in the Early Triassic, terrestrial vertebrates totally vacated the equatorial belt, the so-called ‘vertebrate equatorial-gap’, as a consequence of the extreme hot temperatures. More recently, Bernardi et al. (2015, 2018) reviewed the Late Permian-Early Triassic terrestrial tetrapod record integrating skeletal and track data and concluded that tetrapod geographic distribution was much wider than previously suggested. In the Early Triassic it included also the low latitudes, though polarward dispersals were detected in the Early Triassic and possibly linked to the development of super-hot temperatures in the equatorial belt (Bernardi et al., 2018). Fossil track evidence, in particular, was key in denying the existence of an ‘equatorial gap’ (Bernardi et al., 2018).

Archosaur tracks and trackways are in fact well-known from Lower to Middle Triassic siliciclastic and carbonate sediments of the Upper Buntsandstein and Lower Muschelkalk (late Olenekian-early Anisian) of Germany (Haubold, 1971a, 1971b; Klein & Haubold, 2007), the Lower Triassic of the Holy Cross Mountains in Poland (Klein & Niedzwiedski, 2012), the Middle Triassic of Bourgogne (Gand, 1979), Massif Central (Demathieu, 1970) and Ardèche in France (Courel & Demathieu, 1976), the Iberian Range in Spain (Fortuny et al., 2011; Díaz-Martínez, et al., 2015) and Sardinia in Italy (Citton et al., 2020). Further sites, often with identical ichnotaxa and ichnoassemblages, are known from the Lower to Middle Triassic of Great Britain (King et al., 2005), North American southwest (Klein & Lucas, 2010), Argentina (Melchor & De Valais, 2006), Africa (Klein et al., 2011) and southern China (Xing et al., 2013). In the Alps, chirotherian footprints were described from the Lower to Middle Triassic of the

Dolomites, Piedmont and Ligurian Alps in Italy (Avanzini & Mietto, 2008; Petti et al., 2013; Santi et al., 2015), Aar Massif in eastern Switzerland (Feldmann et al., 2009; Klein et al., 2016) and the Aiguilles Rouges Massif (Western Alps), on the border between Switzerland and France (Demathieu & Weidmann, 1982; Avanzini & Cavin, 2009; Cavin et al., 2012; Klein et al., 2016).

We here describe and interpret a new archosaur track assemblage from the Gardetta Plateau (Western Alps, south-western Piedmont, Italy; Fig. 1) that was analyzed in two different field works, during the summer 2009 and in the autumn 2017-2018.

Tracks are preserved on two distinct track surfaces, belonging to the same stratigraphic horizon. Some of them are badly preserved but distinct trackways, up to 3 m long, can be recognized together with other exceptionally preserved isolated tracks showing clear morphological details of the trackmaker's autopodium.

This discovery provides reliable evidence of the presence of archosauriforms in the Briançonnais domain during the Early Triassic, adding further support to the occurrence of terrestrial tetrapods at low latitudes soon after the PTME (Bernardi et al., 2015; 2018) and well before a full land ecosystem recovery.

MATERIALS AND METHODS

All the specimens were identified in the same outcrop, located about 1 km SE of the Gardetta Plateau, close to Pianezza creek (44°24'5.75"N; 7° 1'45.29"E; Canosio Municipality, Cuneo Province, NW Italy; Fig. 1).

Most of the footprints are preserved as negative epichnia (concave epirelief) and were left *in situ* in the field. The footprints were discovered by EC and MP in summer 2008. A surface of about 10-15 m² was mapped a first time in 2009 by HF and then in 2017 by FP and HF. An exceptionally preserved trackway, consisting of three large pes and manus imprints, was then discovered during the 2017 and 2018 field works by EM and FP, about 10 m higher up on the same outcropping horizon. Tracks outlines were drawn on transparency acetate film and then digitized by a vector-based drawing software (Adobe Illustrator ©). Additional footprints were collected by the authors and hikers from loose sandstone slabs in the creek below the track surfaces. These isolated and usually fragmentary footprints are preserved both as concave epirelief and well-preserved convex epirelief, the latter being preserved in the basalmost level of the sandstone bed which overlies the track layer.

Close-range photogrammetry was used to document tracks and obtain three-dimensional model of the best-preserved ones (Petti et al., 2008; Remondino et al., 2010; Mallison & Wings, 2014). The data processing phase was performed using Agisoft PhotoScan ® Professional software, following the procedure indicated by Mallison & Wings (2014). In a second phase, the software Surfer®14 (GoldenSoftware, 2002), was used to convert elevation points to contour lines and to produce color coded maps of the studied material.

The obtained images are ideal for both precisely measure standard ichological parameters (Haubold, 1971b; Leonardi, 1987) and for recognizing anatomy related morphologies, therefore for the reconstruction of the trackmaker's autopodial osteology.

Trackmaker identification was carried out employing three different and integrated methodological approaches: i) Synapomorphy-based correlation (Olsen, 1995; Carrano & Wilson, 2001); ii) Phenetic correlation (Carrano & Wilson, 2001) and iii) Coincidence

correlation (Carrano & Wilson, 2001). The synapomorphy-based method focuses on the identification of osteologic-derived character states in the footprints that result from the impression of synapomorphic characters in the trackmaker autopodia (see Olsen et al., 1998; Carrano & Wilson, 2001; Wilson, 2005; Romano et al., 2015). The phenetic correlation is closely linked to ichnotaxonomy and derives from an accurate description of the footprint and the identification of the trackmaker through the recognition of an affinity between tracks and limbs osteology (Carrano & Wilson, 2001; Wilson, 2005). The coincidence correlation is usually adopted to refine trackmaker identification and is based on supplemental data including geological age, geographic provenance, local faunal composition and distributions, and abundances of skeletal taxa and ichnotaxa (Carrano & Wilson, 2001).

GEOLOGICAL FRAMEWORK

The Gardetta Plateau - Preit valley area is located in the southern part of the Western Alps (Fig. 1). It encompasses the Sautron, Rouchouze, Rocca Peroni tectonic units and the Gardetta deformation unit (*sensu* d'Atri et al., 2016) also known as “bande siliceuse de la Gardetta” (Gidon, 1972). These tectonic units pertain to the Briançonnais Domain (Gidon, 1958a, 1958b, 1972; Schmid et al., 2004, 2017) and in particular to the External Briançonnais Domain which is characterized by very low grade to anchizone metamorphism (d'Atri et al., 2016).

The upper Permian-Mesozoic sedimentary succession varies considerably within the Briançonnais Domain *s.l.* (Briançonnais Domain *s.s.* and Ligurian Briançonnais, Decarlis & Lualdi, 2009; Fig. 2) due to the slightly different paleogeographic positions of these sectors (see

Decarlis et al., 2013 for a review). The outcropping lithostratigraphic units, even if can be correlated across the distinct domains, display different thickness, vertical/lateral relationships and hiatuses. These differences led authors to adopt a multitude of official and unofficial names for the lithostratigraphic units. Despite these minor differences, the late Permian–Early Triassic sedimentation in the whole Briançonnais domain s.l. testifies to the evolution of a continental margin affected by extensional tectonics. The Briançonnais domain was positioned north of the westernmost sector of the Palaeotethys, in the western continental termination of the Meliata oceanic back-arc basin (Ziegler & Stampfli, 2001; Decarlis et al., 2013). Adopting the paleolatitude calculator developed by Van Hinsbergen et al. (2015) (model version 2.1) and using the Global Apparent Polar Wander Path of Torsvik et al. (2012) as paleomagnetic reference frame, the Early Triassic (250 Ma) palaeolatitude estimate for the Southern Briançonnais Domain is 11.8 N.

In the study area the volcano-sedimentary succession starts with upper Carboniferous - Permian volcanic rocks (andesitic lavas followed by rhyolites and rhyolitic ignimbrites) unconformably overlain by upper Permian-Lower Triassic siliciclastic continental-to-transitional deposits (the so called “*semelle silicieuse*” of French Authors). In particular these deposits are characterized by basal coarse grained conglomerates and quartz-conglomerates, named locally “Verrucano Brianzone” (Carraro et al., 1970; Cassinis et al., 2018) that evolve upward into quartz-arenites and quartz-siltites of the “Werfenian quartzites” (Fig. 2; Gidon, 1958b; Malaroda, 1970; Megard-Galli & Baud, 1977; Costamagna et al., 2002; Costamagna, 2013). The siliciclastic sequence indicate deposition in an alluvial environment characterized by sandy braided fluvial system fed by the residual Variscan relieves (Costamagna, 2013). In the southernmost part of the Briançonnais domain (External Ligurian Briançonnais Domain,

Vanossi, 1974; 1991; Bertok et al., 2012) these latter lithostratigraphic units are known as “Scytian quartzites” or “Ponte di Nava Quarzites” (Fig. 2; Decarlis et al., 2013, 2015). Similar to the siliciclastic sequence of the Briançonnais Domain s.s., the “Ponte di Nava Quarzites” originated from the dismantling and reworking of the Paleozoic igneous and metamorphic basement.

The quartz-arenites can be topped either by greenish pelites (known as “Case Valmarenca Pelites” in the Ligurian Briançonnais, Vanossi 1974; 1991), that have been interpreted as mudflat deposits, or by a thin and discontinuous interval of cavernous dolostones called “*Cargneules Inférieures*” representing the sedimentation in an arid environment as an evaporitic sabkha (Fig. 2). According to Lualdi & Seno (1984), in the Ligurian Briançonnais Zone the “Case Valmarenca Pelites” could be laterally equivalent to the “*Cargneules inférieures*”.

The continental succession and/or the evaporitic deposits are followed by Middle Triassic shallow water carbonates of the “*couverture carbonatée*” (Gidon, 1958b; Megard-Galli & Baud, 1977; Costamagna et al., 2002) comprising a lower calcareous complex (Costa Losera Fm, Lualdi and Bianchi, 1990, corresponding to the e St. Triphon Formation of the classic Briançonnais Domain) and an upper dolomitic complex (San Pietro dei Monti Fm, Vanossi, 1969). These carbonate deposits testify the sedimentation in a subsiding carbonate ramp.

The lower calcareous complex (Fig. 2) begins with a characteristic facies named “*Marbres Phylliteux*” by French Authors made of greyish and brownish fine-grained limestones, (lower to upper Anisian) with sericite, muscovite, chlorite laminated levels. Bedding can be locally masked by pervasive and intense bioturbation (“*Calcaires Vermiculés*” facies) assigned to the ichnogenus *Rhizocorallium*. The basal complex ends with varicolored pelites, interpreted as

cinerites (upper Anisian in age) by Caby & Galli (1964), recognizable throughout the whole Briançonnais Domain.

The upper dolomitic complex (Fig. 2) is constituted by massive to well-bedded dolostones followed by cyclically arranged carbonates (“*Calcaires rubanés*” – upper Anisian – upper Ladinian; Gidon, 1958b; Megard-Galli & Baud, 1977; Costamagna et al., 2002; Decarlis & Lualdi, 2009) characterized by subtidal crinoidal wackestones, intertidal oolitic limestones and supratidal dolomitic mudstones capped by reddish paleosols, that testify shallowing-upward cycles. The dolomitic succession includes dark limestones, dark fossiliferous and/or oolitic dolostones, meter-thick autoclastic breccias and gypsum–anhydrite pseudomorphs witnesses of major emersion events. These lithofacies, dated to the uppermost Ladinian, are known in the different Briançonnais domains as “*Dolomies blanches*” or “*Dolomies grises*” or “*Couches à C. goldfussi*” or “*Complexe schisto-dolomitique basal*”.



THE PIANEZZA STRATIGRAPHIC SUCCESSION

In the framework of the abovementioned stratigraphic setting the footprint-bearing level is located in the Pianezza area along the track connecting Colle del Preit (2100 m a.s.l.) to Grange Isoardi (Pianezza area, 2275 m a.s.l.) (Fig. 2). The outcrop is located along the SW flank of a narrow antiformal anticline belonging to the Sautron Tectonic Unit which overthrusts the Rouchouze Tectonic Unit. Here the volcano-stratigraphic succession begins by meta-andesites and andesitic schists pertaining to the upper Carboniferous-Permian volcanic complex. The sedimentary succession continues upward with a thin and discontinuous (up to 1 meter) level of

graphitic schists, deriving from the weathering of the volcanic basement (Lorenzoni & Zanettin, 1958) and is then followed by up to 100 meters of quartz-conglomerates (“Verrucano Brianzone” and by fine to very fine quartz-arenite and quartz-siltite with ripple marks and cross bedding (“Werfenian quartzites”). The track-bearing horizon occurs at the top of the latter clastic interval. The succession continues upward with 15 meters of gypsum/anhydrite deposits of the lower cargneule. In the Pianezza area the Middle Triassic “*couverture carbonatée*” is only represented in the north-eastern flank of Sautron Unit anticline.

CHRONOSTRATIGRAPHIC FRAMEWORK OF THE STUDY AREA

The sedimentary rocks belonging to the quartz-rich clastic succession does not allow precise dating because of the lack of biostratigraphic markers as commonly happen for these kind of deposits. They are here referred to the upper Permian-Lower Triassic on the base of their stratigraphic position in the Sautron Unit, similar to that of the well-comparable quartz-conglomerate and quartzarenite rocks occurring not only in the Briançonnais Domain, but also in the Southern Alps, Sardinia and Provence. For this reason, in order to constrain the age of the track-bearing horizon, some considerations are required: i) the coarse quartz-conglomerates (“Verrucano Brianzone”) are commonly referred to the late Permian-earliest Triassic (Gidon, 1958b; Carraro et al., 1970; Megard-Galli & Baud, 1977; Decarlis & Lualdi, 2009); ii) the Lower Triassic age can be hypothesized considering the occurrence of *Estheria minuta* Alberti and *Myacites fassaensis* Bittner within the “Ponte di Nava Quarzites” (Decarlis & Lualdi, 2009); iii) the “lower cargneule” unit and its lateral equivalent “Case Val Marenca Pelites” are generally

attributed to the late Early Triassic (Gidon, 1958b; Carraro et al., 1970; Megard-Galli & Baud, 1977; Decarlis & Lualdi, 2009); iv) the lower part of “*Marbres Phylliteux*” are considered early Anisian in age, on the basis of the occurrence of *Rhizocorallium*, that is regarded to be an early Anisian marker all over the Tethyan realm (Baud, 1976); v) an early Anisian age for the base of the lower calcareous complex (“*Marbres Phylliteux*” and Costa Losera Fm.) is also suggested by the occurrence of Dasycladacean algae and crinoidal remains (*Dadocrinus* sp.; Carraro et al., 1970); vi) In the northern Briançonnais of southwestern Switzerland a find of the ammonoid *Beyrichites cadoricus* in the upper part of the St-Triphon Formation indicate a middle Anisian age (Baud et al., 2016).

Additionally, it is worth mentioning that both in the Geological Map of the Argentera Massif (Malaroda, 1970; Carraro et al., 1970) and in the Geological Map of France at the scale 1: 50.000 (Sheet 896, Larche; Gidon, 1978) the studied outcrop was attributed to Lower Triassic. All the above reported data thus point to a probable attribution of the trampled horizon to the late Early Triassic.

SYSTEMATIC ICHNOLOGY

Most footprints are preserved as natural molds (concave epirelief) on top of a 3-4 cm thick bed of fine sandstone. The tracks are shallow, less than 2 cm deep, but most of them are cut by small-scale tectonic cracks/fissures and strongly weathered. Two possible trackways with lengths of 4–5 m were identified on a track surface. Only one isolated track was visible on the underlying sandstone bed, also preserved as concave epirelief. Three solitary small footprints,

preserved as convex epirelief of the directly overlying sandstone bed, were collected from loose slabs. The upper surface of this 1–2 cm thick sandstone bed is marked by symmetric wave ripples, exposed on a spectacular bedding plane (Fig. 3).

An exceptionally preserved trackway, made of three consecutive manus-pes sets was found on another surface, belonging to the same stratigraphic horizon, upstream of the previously described ones (Fig. 4). The general features of the herein studied ichnoassemblage are typical for chirotherian tracks (Haubold & Klein, 2002).

Ichnogenus *Chirotherium* Kaup, 1835

Type ichnospecies: *Chirotherium barthii* Kaup, 1835

Chirotherium isp.

(Figs 3, 7)

Referred specimens: two trackways preserved as concave epirelief (GT-1 and GT-2). GT-1 consists of four clear and two weakly impressed imprints, arranged in a 2.10 m-long trackway in the lower part of the outcrop, just 2 meters above the creek level (Fig. 3). Its direction on the steep bedding plane points upwards to southeast. Trackway GT-2 is 2.40-m-long, is preserved in the lower part of the same bedding plane, about 2 meters above the creek level, running from northwest to southeast.

Description: pentadactyl and semi-digitigrade pes imprint. Pes is longer than wide, (Foot Length [FL] = 13 to 16 cm; Foot Width [FW] = 8-10 cm; FL/FW = 1.6 to 2.0) with digit group

II-IV roughly asymmetrical. Pedal digit impressions gradually increase from I to IV, with II sub-equal or shorter than digit IV; digit III is the longest. In the best-preserved track (GT1-3; Figs 3, 7), digit I is pointed and placed posteriorly with respect to digit group II-IV. Digit V is oval and tapers distally; it is positioned posteriorly and laterally to digit I-IV and directed antero-laterally. No digital pad impressions can be observed on digit II-IV. Digit V shows a large rounded pad impression and a possible sub-triangular shaped claw mark. Manus tracks are absent or faintly preserved as small semi-circular imprints, placed in front of the pedal footprints. An isolated tetradactyl imprints, measuring 4.5 cm in length and 7 cm in width, and another isolated circular pentadactyl imprint 5.5 cm long are interpreted as possible manus imprints.

In the trackway the oblique pace varies between 26 and 41 cm, with a mean value of 36 cm. The pes pace angulation varies between 145° and 165°, with a mean value of 157°.

Discussion: the ichnogenus *Chirotherium* with its holotype *Chirotherium barthii*, was described by Kaup (1835) on trackways from the “Thüringischer Chirotheriensandstein” (Lower-Middle Triassic) of the Thuringia region (Germany). The here described material, even if not perfectly preserved, retains some diagnostic features of the ichnogenus *Chirotherium*, such as the oval morphology and the position of digit V (slightly behind digit group II-IV), and the relative digit length of group II-IV, with digit IV longer or sub-equal to digit II. Pes pace angulation is also similar to the values to date reported for the ichnogenus (160°-170°). *Chirotherium barthii* (Figs 7e, 7f) shows clear circular pads on digit group II-IV and digit impressions are broader than in the studied specimens. In *C. barthii*, as well as in *C. rex*, *C. moquinense* and *C. vorbachii* (Fig. 7h), digits I-IV are splayed whereas in the GT-1 and GT-2 trackways, pedal digits outlines are closely arranged with only digit I medially spread. Digits II-IV seems to be almost parallel to

each other and the digit pattern resemble that of the ichnospecies *C. sickleri* Kaup, 1835 (Figs 7i, 7l, 7m) with digit I forming a narrow group with digits II, III and IV. Nevertheless, digit IV, though slightly shorter than III, is not much longer than II as observed in most of the specimens assigned to *C. sickleri*. Unfortunately, the bad preservation of pes imprints in GT-1 and GT-2 trackways preclude any accurate ichnospecific assignment.

Ichnogenus *Isochirotherium* Haubold, 1971a (Figs 4, 5, 8)

Type ichnospecies: *Isochirotherium soergeli* (Haubold, 1967).

***Isochirotherium gardettae* ichnosp. nov.**

Derivatio nominis: from the Gardetta plateau, type locality of the ichnospecies.

Type-level: “Werfenian quartzites”, Lower Triassic.

Referred specimens: a trackway made of three well-preserved and consecutive manus-pes couples (GT-7; Fig. 4) not exceeding 2.20 m across. Another possible isolated track (GT-3) partially preserved in the lower track surface.

Diagnosis: chirotherian track with pentadactyl pes and small and tetradactyl manus imprint and pes digit IV noticeably shorter than II; pes digit group I-IV slightly longer than wide, pes digit V with large ovoid metatarsal pad and a reduced phalangeal portion. Pes length ranging



341 from 28 to 33 cm; cross axis equal to 90° . Trackway very narrow, pace angulation near 165° , and
 342 ratio of stride to pes length is 4.3.

343

344 **Description:** pentadactyl and semi-plantigrade pes imprint, longer than wide (FL = 33.4 cm;
 345 FW = 19.2 cm; FL/FW = 1.74). Digit III is the longest. It is slightly longer than II, whereas digit
 346 IV is shorter than II. Digit I is the shortest and is thinner than those of digit group II-IV. The total
 347 divarication I-IV is 22° ; the angle between digit I and II is 8° and is equal to that between II and
 348 III but larger than II-IV (6°). Cross axis is nearly equal to 90° . Digit impressions are robust and
 349 pointed showing large sub-triangular claw marks. Two phalangeal pad impressions are present
 350 on each digit of group I-IV. The metatarsal-phalangeal portion is proximally arched and could be
 351 separated from digit V by a gap, or joined with it through a convex area, running from the
 352 basalmost portion of digit I to the medial digit V. Digit V shows a large oval impression joined
 353 to a rounded phalangeal-ungual portion, laterally spread out. In GT-7-2 and GT-7-3, pes digit V
 354 has a sub-triangular shape with a wider inner margin, almost aligned with the medial margin of
 355 digit I. Length of pes digits are: I) 118 mm; II) 173 mm; III) 186 mm; IV) 136 mm; V) 167 mm.

356 The manus is small, tetradactyl and digitigrade, wider than long (FL = 8.04 cm; FW = 13 cm;
 357 FL/FW = 0.62) and is placed in front of the pes. Digits are short and pointed. Digits II and III
 358 have nearly equal length and are longer than digits I and IV; the latter is moderately spread
 359 outward. Digit IV is possibly the shortest. Length of manus digits are: I) 49 mm; II) 74 mm; III)
 360 68 mm; IV) 43 mm.

361 The trackway, made by three consecutive manus-pes sets, shows a clear narrow gait (pace
 362 angulation 164°). Oblique pace is 59 cm, whereas double pace is 119 cm across. Manus-pes
 363 couples turned slightly outward with respect to the midline (from 10° to 15° on average).

364

365 **Discussion:** the ichnogenus *Isochirotherium* was erected by Haubold (1971a); its type
 366 ichnospecies *I. soergeli* (Haubold, 1967) comes, as for *Chirotherium barthii*, from the
 367 “Thüringischer Chirotheriensandstein” (Lower-Middle Triassic) of the Thuringia region
 368 (Germany). The ichnogenus is reported also from the Middle Triassic of Great Britain (Tresise &
 369 Sarjeant, 1997; King et al., 2005), from the Lower–Middle Triassic of North American
 370 Southwest (Peabody, 1948; Klein & Lucas, 2010), the Aiguilles Rouges Massif (Western Alps)
 371 on the border between Switzerland and France (Avanzini & Cavin, 2009; Klein et al., 2016) and
 372 from the Middle Triassic of North-East Italy (Avanzini & Leonardi, 2002).

373 The main diagnostic features of this ichnogenus, retained by our specimens are: i) the relative
 374 digit length, with digit II longer than IV and shorter than III; ii) a marked heteropody; iii) the pes
 375 pace angulation around 165°; iv) the weakly impressed distal portion of digit V and v) pes-
 376 manus couples outward rotation of about 15°. However, the studied trackway shows clear
 377 difference to most of the ichnospecies known to date. For example, the type ichnospecies *I.*
 378 *soergeli* Haubold, 1967 (Fig. 8o), has smaller absolute dimensions, thinner pes digit marks and,
 379 most importantly, display five clear digit impressions in the manus contrary to GT-7, where only
 380 tetradactyl manus were observed. 

381 *Isochirotherium hessbergense* Haubold, 1971a (Fig. 8m) has also a pentadactyl manus and is
 382 clearly different from the material described in this paper for its digit group I-IV longer than
 383 wider and for the relative pes digit length, notably digit I is longer than IV.

384 *Isochirotherium demathieui* Haubold, 1971a (Fig. 8n) can be excluded for its pentadactyl
 385 manus and for the shorter distance between manus and pes.

Isochirotherium coltoni Peabody, 1948 (Fig. 8h) and *I. lomasi* Baird, 1954 (Fig. 8i) retain much slenderer digit impressions, especially in the pes imprint and most notably have manus tracks more internally placed than in the studied footprints. Interestingly *I. herculis* Egerton, 1839 (Fig. 8e) has similar dimensions (i.e. FL longer than 30 cm) but can also be excluded for i) the tridactyl manus; ii) the digit group I-IV slightly wider than longer and iii) the manus imprint position, very close to that of the pes.

Isochirotherium marshalli Peabody, 1948 (Fig. 8f) shows similar features such as: i) the pes digit relative length; ii) the interdigital angles values; iii) the digit group I-IV as longer as wider; iv) the arched metatarsal-phalangeal portion; v) the configuration of digit V whose phalangeal portion is significantly smaller than the ovoidal and possibly tarsal-metatarsal pad. Nevertheless, the assignment to this ichnospecies is precluded by its pentadactyl manus.

Isochirotherium inferni Avanzini & Leonardi, 2002 from the Illyrian (late Anisian, Middle Triassic; Fig. 8g) of the Adige Valley (Bolzano, NE Italy) closely resembles the Gardetta specimens for: i) the arched metatarsal-phalangeal portion; ii) the position of the base of pes digit V, placed along the axis of digit III; iii) pes digit relative length; iv) cross axis equal to 90° v) pes angulation of about 160°; vi) positive rotation of manus-pes couples respect to the midline (10°-15°). However, pes digits are stouter and the manus is described as pentadactyl (even if in the outline drawing only four digits are clearly appreciable). The tracks referred to *Isochirotherium delicatum* Courel & Demathieu, 1976 and found in the Anisian-Ladinian deposits of Argentièr (Ardèche, France; Courel & Demathieu, 1976; Courel et al., 1979; Demathieu, 1984; Gand, 1978) and Gampempass (Southern Alps, Italy; Avanzini & Lockley, 2002) show less-thick digit impressions and a markedly reduced digits IV and V; the latter is also much more backward positioned if compared with the studied specimens.

We therefore erect the new ichnospecies *Isochirotherium gardettae* to describe a new and well-preserved *Isochirotherium* trackway that differs from all the other ichnospecies for all the features listed above.

TRACKMAKER IDENTIFICATION

Grounding on previous studies and new observations Bernardi et al. (2015) showed that chirotherian footprints, such as *Protochirotherium*, *Chirotherium*, *Brachychirotherium* and *Isochirotherium*, can be confidently attributed to archosauriforms, based on the presence of a digit IV shorter or as long as digit III. Being metatarsal length directly proportionate to digit length, this assumes that metatarsal IV is shorter than or as long as metatarsal III, a synapomorphy of the archosauriforms (Nesbitt, 2011). Other characters useful to identify archosauriforms traces are: i) the presence of a compact digit group I-IV; ii) a posterolateral positioned and strongly reduced digit V; iii) a massive metatarsal-phalangeal region, shorter than or as long as digit I. However, the first character occurs in archosauriforms and non archosauromorphs diapsids (Haubold, 1971a, 1971b; Smith & Evans, 1996) whereas the second is present in archosauriforms, lepidosaurs and basal archosauromorphs (Haubold, 1971a, 1971b; Evans & Wang, 2005; Gottman-Quesada & Sander, 2009). Other features suggesting an archosaur affinity for chirotherian footprints (observed also in the here described traces), are narrow trackways linked to the disposition of limbs under the body, and the presence of small manus relative to the pes, which indicate a possible early tendency toward bipedal posture and gate (see Haubold, 1971a, 1971b, 1984, 2006; Klein et al., 2010).

To reconstruct the hind- and fore-limb autopodial bones, we assumed an arthral position for the joint articulations within digital pad impressions (Fig. 9a).

In our opinion, the sub-elliptical to pyriform impression behind group I-IV in *Isochirotherium* could be the result of the coalescence of the impression of the phalangeal-metatarsal portion of digit V and of a thick fleshy pad beneath the astragalus, the calcaneus and some of the tarsal bones. Overall, the trackmaker's pes may have had a semi-plantigrade posture, as evidenced by the gap between digit group I-IV and digit V, corresponding to the part of the foot held up during locomotion. The manus has a marked digitigrade posture and its tetradactyly might result by the fact that manual digit V likely held off the ground during the touch-down and weight bearing phases (*sensu* Manning, 2004).

The reconstructions thus obtained shows the following pes and manus phalangeal formulas: pes 2-3-4-4-1 and manus 1-2-3-3. They are compared with the anterior and posterior limbs of the main groups of archosauriforms known in the Triassic period (Huene, 1902; Broom, 1903; 1905; Romer, 1971; Welles, 1947; Young, 1964; Zhang, 1975; Peyer et al., 2008; Ezcurra et al., 2013; Sookias & Butler, 2013; Trotteyn et al., 2013).

The first considered non-archosaurian archosauriforms groups are Proterosuchidae (Ezcurra et al., 2013), Proterochampsidae (Trotteyn et al., 2013) and Euparkeriidae (Sookias & Butler, 2013). In all the three representatives *Proterosuchus fergusi* Broom, 1903 (South Africa, Induan-?early Olenekian; Fig. 9e), *Chanaresuchus bonapartei* Romer, 1971 (Argentina, Ladinian; Fig. 9i) and *Euparkeria capensis* Broom, 1913 (South Africa, Anisian; Fig. 9h), the IV metatarsal has a length similar or greater than that of the III but the digit II is much shorter than digit III and nearly equal to digit IV, in contrast to what we observe in specimens GT-7-1, GT-7-

2 and GT-3. No fore- or hind limb bones are known for the Doswelliidae, another clade of non-archosaurian archosauriforms (Middle-Late Triassic; Sues et al., 2013).

Diedrich (2015) recently attributed the *Isochirotherium* tracks to *Arizonasaurus* Welles, 1947, a member of Poposaurioidea (archosaurian archosauriforms) found in the Moenkopi Formation (Arizona, USA, Anisian,), from the same levels as *Isochirotherium* tracks. Unfortunately, no bones of the fore- and hind-limbs are known from *Arizonasaurus*, as well as from *Ctenosauriscus koeneni* (Huene, 1902) (Germany, latest Olenekian), the Lower Triassic poposaurid archosaur, and additionally findings are needed to test Diedrich's hypothesis.

The hind-limb bones are known in *Lotosaurus adentus* Zhang, 1975 (China, Ladinian; Fig. 9d), another member of Poposaurioidea with semi-plantigrade posture. If compared with the restored autopodium, it is characterized by larger fore-limbs, V digit positioned further forward, longer metatarsals of digit group I-IV and different digit proportions.

The pedal phalangeal relative length of the rauisuchid archosaur *Postosuchus alisonae* Peyer et al., 2008 (USA, Norian; Fig. 9c), is similar but all the five metatarsals are much longer, implying a digitigrade posture, as in the reconstruction proposed by Peyer et al. (2008).

Postosuchus kirkpatricki Chatterjee, 1985 (USA, Norian; Fig. 9b), is also characterized by very long metatarsals and thus excluded as a possible trackmaker. The smaller but complete skeleton of *Ticinosuchus ferox* Krebs, 1965 (see Lautenschlager & Desojo, 2011 for a review of the species) from the uppermost Anisian of Monte San Giorgio (southern Switzerland), shows long metatarsals and a digit IV longer than digit II and is commonly considered as the producer of *Chirotherium* trackway (Haubold, 1984, 1986).

By contrast, the hind limbs of the non-archosaurian archosauriform clade of Erythrosuchidae (Ezcurra et al., 2013) are characterized by relative digit length very similar to that outlined for

Isochirotherium gardettae and a pedal phalangeal formula that is approximately 2-3-4-5-3 (Young, 1964; Cruickshank, 1978; Gower, 1996).

Metatarsals II and III are sub-equal and slightly longer than IV in *Erythrosuchus africanus* Broom, 1905 (South Africa, lower Anisian; Fig. 9f. See also Cruickshank, 1978; Gower, 1996).

Metatarsals II and III are the longest in *Shansisuchus shansisuchus* Young, 1964 (Fig. 9g), another member of Erythrosuchidae found in upper Anisian deposits of China; *S. shansisuchus* also possesses a hook-shaped proximal end of metatarsal V and its relative digit proportion closely fits that of our individual, but as for *E. africanus* digit V seems to be too forwardly positioned. However, digit V impression in *I. gardettae* likely records only the distal metatarsal and phalangeal (ungual) portions. During locomotion the former was held off the ground whereas the latter was likely being retracted due to the presence of a thick fleshy pad beneath calcaneum and astragalus.

The morphology of the acetabulum and proximal end of the femur in erythrosuchids suggests a distinctly sprawling gait (Gower, 2003; Ezcurra et al., 2013), that clashes with the narrow trackway seen in *I. gardettae*. Nevertheless, the prominence of metatarsal II and III is evidenced only in non-archosaurian archosauriforms (Gower, 1996) and thus an individual belonging to this group, possibly a yet unknown taxon and with a more erect stance and characterized by a marked heteropody, is the most suitable producer (Fig. 10).

BIOCHRONOLOGY AND BIOGEOGRAPHY

The Gardetta ichnoassemblage represented by *Chirotherium* and *Isochirotherium* is typical for terrestrial deposits of the late Olenekian and early Anisian (Klein & Haubold, 2007) and the Gardetta chirotheriid tracks correlate with the international *Chirotherium barthii* Assemblage

Zone of Klein & Lucas (2010a). This biochron is characterized by the occurrence of *Chirotherium* and *Isochirotherium*, but also by two other ichnogenera not present at Gardetta, *Rotodactylus*, and *Synptychium*. The *Chirotherium barthii* Assemblage Zone ranges from the late Early to early Middle Triassic (late Olenekian – early Anisian), and independently confirms the Early Triassic (?Olenekian) age, derived by stratigraphic correlation with other sections in the Briançonnais of the Western Alps.

The Gardetta outcrop enlarges also the knowledge on biogeography of archosaurs in the Lower Triassic of Europe, so far based on archosaur ichnosites discovered in Italy (Val Marenc, Santi et al., 2015; Sardinia, Citton et al., 2020), Spain (Moncayo and Tagamanent, Díaz-Martínez & Pérez-García, 2012), Switzerland (Cascade d’Emaney and Vieux Emosson; Cavin et al., 2012), Austria (Drau Range; Krainer et al., 2012), Germany (Bundsandstein; Klein & Haubold, 2007) and Poland (Wióry, Holy Cross Mountains, Klein & Niedźwiedzki, 2012).

Early Triassic erythrosuchid skeletal fossils are known from the late Olenekian of Russia, South Africa, China and India (see Gower, 2003; Ezcurra et al., 2013, 2019, 2020; Gower et al., 2014; Ezcurra, 2016). The Gardetta ichnosite testifies the presence of erythrosuchids and more generally of Archosauriformes at low latitudes (11.8° N) also during the Early Triassic (Fig. 11).

This supports the conclusions of Bernardi et al. (2015, 2018) that Early Triassic ichnosites are mainly distributed along the tropics, contrasting the pattern described by skeletal findings and the hypothesis of a low-latitude vacancy of continental tetrapods during or soon after the PTME (Sun et al., 2012).

Discussion and conclusions

The Gardetta ichnosite is characterized by archosaur footprints assigned to *Chirotherium* isp. and to the new ichnospecies *Isochirotherium gardettae* ~~ichnosp. nov.~~. They represent the first record of terrestrial tetrapods in the Briançonnais domain of the Western Alps and expand the record of archosaur footprints in the Lower Triassic of Central Europe.

The morphological characters of the tracks assigned to *Isochirotherium gardettae* ~~ichnosp. nov.~~ suggest a non-archosaurian archosauriform (Erythrosuchidae?) as possible trackmaker candidate (even though the presence of crown-archosaurs cannot be excluded), thus providing crucial information about continental tetrapod occurrence in Europe in the Early Triassic. Based on a phylogenetic dataset made by 108 middle Permian–early Late Triassic species, Ezcurra & Butler (2015) investigate principal patterns of early archosauromorph biodiversity change across the Permo-Triassic mass extinction. The study, performed using phylogenetic diversity, morphological disparity, number of species and rates of phenotypic evolution across 35 million years of early archosauromorph evolution, indicates consistent phylogenetic diversification of the clade in the Olenekian. In particular, the basal diversification of main taxa, which include erythrosuchids, rhynchosaurs and tanystropheids, resulted in significantly high evolutionary rates, with a diversification interpreted by the authors as a radiative response to vacant ecological space, made available by the EPME (Ezcurra & Butler, 2015). If the trackmakers' attribution for the here described footprints is correct, the material from Gardetta could represent an evidence from Europe of such radiation, with an archosauromorph fauna composed at least by ?erythrosuchids (*Isochirotherium gardettae*) and pseudosuchids (*Chirotherium* isp.). Such clades as putative trackmaker for the Gardetta traces are well-compatible with an Early Triassic (likely late Early Triassic) age, considering that the early history of Archosauriformes is represented essentially by members of Proterosuchidae and Erythrosuchidae (Charig & Reig, 1970;

Cruickshank, 1972; Charig & Sues, 1976; Gower & Sennikov, 2000; Gower, 2003; Ezcurra et al., 2013).

Following the huge Permo-Triassic biotic crisis, unfavorable environmental conditions characterized much of the Early Triassic, testifying one of the slowest recoveries for ecosystems after an extinction in Earth history. A period between five and nine million years for a full recovery has been proposed in several contributions (Hallam, 1991; Erwin, 1992, 2001; Payne et al., 2004, 2011; Algeo et al., 2011; Whiteside & Ward, 2011), inferring a fully restored complex ecosystems only at the beginning of the Middle Triassic (see Chen & Benton, 2012). Such long recovery time led to a revolution on both marine and terrestrial ecosystems (Chen & Benton, 2012), with a major influence in the evolution of crucial vertebrates clades in the rest of Mesozoic and Cenozoic eras (Sepkoski, 1984; Benton, 2010). The recovery period led to the emergence of totally new groups, with a rapid diversification of several lineages of sauropsid both on sea and land (Nesbitt et al., 2010; Butler et al., 2011; Gower et al., 2014; Scheyer et al., 2014; Motani et al., 2015a, 2015b; Peacock et al., 2018). Avemetatarsalians (which include dinosaurs and pterosaurs) originated in this period (Brusatte et al., 2010; Nesbitt et al., 2010; Chen & Benton, 2012; Benton et al., 2014), along with the evolution of crucial modern group ancestors, including crocodiles, lizards, turtles, frogs and mammals. All these aspects highlight the crucial importance of the Early Triassic in the ecosystems restructuring after the Permo-Triassic mass extinction.

Retallack et al. (2011) propose that the long recovery from the mass extinction was strongly influenced by repeated greenhouse crises during the Early Triassic, with consistent negative excursions in carbon isotope ratios indicating at least five greenhouse crises in the 5 Myr following the EPME (Induan-Anisian) (see Kidder & Worsley, 2004; Retallack, 2005, 2009,

2013; Graisby et al., 2011; Retallack et al., 2011; Sun et al., 2012; Chen & Benton, 2012). In this regard, according to Sun et al. (2012) the entire Early Triassic was characterized by temperatures consistently in excess with respect to the modern equatorial annual sea surface temperatures (SSTs), thus exceeding a tolerable threshold for life in both oceans and land. Inferring SSTs approaching 40°C, according to Sun et al. (2012) the temperature on land very likely fluctuated to even higher levels, with terrestrial tetrapods generally absent between 30°N and 40°S in the Early Triassic.

In this framework, and although some uncertainties on the chronological attribution persists, the Gardetta ichnosite provides important evidence to the low latitude distribution of archosaurus during the Early Triassic period, soon after the PTME, confirming the pattern described by Bernardi et al. (2018). In particular, the new discovery provides further evidence for an early recovery terrestrial ecosystems and the presence at low latitudes of archosauriformes during the Early Triassic. Such evidences support a model in which the EPME did not completely vacate low-latitude lands from tetrapods that, therefore would, have been able to cope with the extreme hot temperatures of Pangaea mainland.

According to Botha and Smith (2006), Archosauromorpha (along with Procolophonomorpha) could be pre-adapted to extremely arid and hot environment conditions, considering that extant reptiles rarely drink water, excrete quite dry fecal pellets, and are characterized by solute-linked water reabsorption mechanisms, water-resistant integument and low ventilation rates (Withers, 1992; Pough et al., 1996). Such physiological aspects and water conserving mechanisms, probably suggest that the archosaurus response to the extreme hot condition of the Early Triassic (Benton, 2018) have probably been much more efficient and plastic than previously thought, and

did not necessarily imply massive dispersal towards higher latitudes as previously suggested (Sun et al., 2012).

Different anatomical features described above indicate a possible ?Erythrosuchids as the most probable trackmaker for the new described ichnospecies *Isochirotherium gardettae*. This attribution can also be supported by track parameters such a narrow trackway and high pace angulation, which indicate a more upright posture with respect to a classic plesiomorphic sprawling gait (see Kubo & Benton, 2007). In particular, according to Ezcurra et al. (2013), erythrosuchids were heavily built and characterized by a probably less sprawling gait, when compared to the condition observed in proterosuchids. The narrow trackway, along with consistently high pace angulation in the Gardetta material, also confirm the statement by Kubo & Benton (2009) that, even if proterosuchids and erythrosuchids are traditionally considered as sprawlers, ichnological evidences indicate that more derived erect-limbed archosaurian already evolved in the Early Triassic; the latter conclusion is also supported on the base of ghost ranges from cladograms (Sereno, 1991; Benton, 1999), and fragmentary materials from Russia (Gower & Sennikov, 2000).

To date, Erythrosuchids are totally unknown from North America and Europe, being described only from Russia, South Africa, China and India (see Gower, 2003; Ezcurra et al., 2013, 2019, 2020; Gower et al., 2014; Ezcurra, 2016). The material from the Lower Triassic deposits of Gardetta thus could represent the first occurrence of the clade in Europe, although, as already pointed out, the attribution is for the moment only tentative, and new studies are underway to better constrain the identity of the zoological trackmaker.

The planned future excavations in the Gardetta ichnosite will hopefully provide additional data to improve our knowledge of the evolutionary history of Archosauriformes in the aftermath of the EPME.

ELECTRONIC SUPPLEMENTARY MATERIAL

This article contains electronic supplementary material.

ACKNOWLEDGMENTS

We warmly thank the Associazione Escarton that generously supported by this research during the field campaigns held in 2009, 2017 and 2018. A special thanks to Giovanni Raggi for his valuable and constant support during the field works and the project organisation. We acknowledge insightful discussions with A. d’Atri (University of Torino). The authors wish also to thank Dr. Debora Rocchietti (Soprintendenza Archeologia Belle Arti e Paesaggio per le province di Alessandria, Asti e Cuneo) and Dr. Attilio Dalmaso (Museo dei fossili in San Rocco di Bernezzo) and Fabio Manucci for video production and artwork. Finally, a special thank is also due to Hanna Luginbühl for her help in mapping 2009 and to Cecilia Gomiero, Jacopo Valori and Nicolò Amoruso for their precious help during 2018 fieldwork.

This paper is part of the project ‘The end-Permian mass extinction in the Southern and Eastern Alps: extinction rates versus taphonomic biases in different depositional environments’ financed by the Euregio Science Fund (call 2014, IPN16) of the Europaregion Euregio.

REFERENCES

- Algeo TJ, Chen ZQ, Fraiser ML, Twitchett RJ. 2011. Terrestrial–marine teleconnections in the collapse and rebuilding of Early Triassic marine ecosystems. *Palaeogeography, Palaeoclimatology, Palaeoecology* **308**(1-2):1-11.
- Alroy J. 2003. Global databases will yield reliable measures of global biodiversity. *Paleobiology* **29**(1):26-29.
- Avanzini M, Cavin L. 2009. A new *Isochirotherium* trackway from the Triassic of Vieux Emosson, SW Switzerland: stratigraphic implications. *Swiss Journal of Geosciences* **102**:353-361.
- Avanzini M, Leonardi G. 2002. *Isochirotherium inferni* ichnosp. n. in the upper Anisian (Illyrian) of Adige Valley (bozen, Italy). *Bollettino della Società Paleontologica Italiana* **41**:41-50.
- Avanzini M, Lockley M. 2002. Middle Triassic archosaur population structure: interpretation based on *Isochirotherium delicatum* fossil footprints (Southern Alps, Italy). *Palaeogeography, Palaeoclimatology, Palaeoecology*, **185**(3-4): 391-402.
- Avanzini M, Mietto P. 2008. Lower and Middle Triassic footprint-based biochronology in the Italian Southern Alps. *Oryctos* **8**:3-13.
- Baird D. 1954. *Chirotherium lulli*, a pseudosuchian reptile from New Jersey. *Museum of Comparative Zoology Bulletin* **111**:165-192.
- Baud A. 1976. Les terriers de Crustacés décapodes et l’origine de certains facies du Trias carbonaté. *Eclogae Geologicae Helvetiae* **69**(2):415-424.
- Baud A, Plasencia P, Hirsch F, Richoz S. 2016. Revised middle Triassic stratigraphy of the Swiss Prealps based on conodonts and correlation to the Briançonnais (Western Alps). *Swiss Journal of Geosciences* **109**:365–377.

- Benton MJ. 1999.** *Scleromochlus taylori* and the origin of dinosaurs and pterosaurs.
Philosophical Transactions of the Royal Society of London. Series B: Biological Sciences
354(1388):1423-1446.
- Benton MJ. 2003.** When life nearly died: the greatest mass extinction of all time. Thames &
Hudson, London.
- Benton MJ. 2010.** The origins of modern biodiversity on land. *Philosophical Transactions of the*
Royal Society B: Biological Sciences **365(1558):**3667-3679.
- Benton MJ. 2018.** Hyperthermal-driven mass extinctions: killing models during the Permian–
Triassic mass extinction. *Philosophical Transactions of the Royal Society A* **376:**20170076.
- Benton M, Newell AJ. 2014.** Impacts of global warming on Permo-Triassic terrestrial
ecosystems. *Gondwana Research* **25:**1308–1337.
- Benton MJ, Twitchett RJ. 2003.** How to kill (almost) all life: the end–Permian extinction event.
Trends in Ecology & Evolution **18:**358–365.
- Benton MJ, Forth J, Langer MC. 2014.** Models for the rise of the dinosaurs. *Current Biology*
24:R87–R95.
- Bernardi M, Petti FM, Benton MJ. 2018.** Tetrapod distribution and temperature rise during the
Permian- Triassic mass extinction. *Proceedings of the Royal Society of London B*
285:20172331.
- Bernardi M, Klein H, Petti FM, Ezcurra MD. 2015.** The Origin and Early Radiation of
Archosauriforms: Integrating the Skeletal and Footprint Record. *PLoS ONE* **10(6):**e0128449.
- Berner RA. 2002.** Examination of hypotheses for the Permo–Triassic boundary extinction by
carbon cycle modeling. *Proceedings of the National Academy of Sciences, U.S.A.* **99:**4172–
4177.

- Bertok C, Martire L, Perotti E, d'Atri A, Piana F. 2012.** Kilometre-scale palaeoescarpments as evidence for Cretaceous synsedimentary tectonics in the External Briançonnais Domain (Ligurian Alps, Italy). *Sedimentary Geology* **251**:58-75.
- Botha J, Smith RMH. 2006.** Rapid vertebrate recuperation in the Karoo Basin of South Africa following the end-Permian extinction. *Journal of African Earth Sciences* **45**:502–514.
- Broom R. 1903.** On a new reptile (*Proterosuchus fergusi*) from the Karroo beds of Tarkastad, South Africa. *Annals of the South African Museum* **4**:159-164.
- Broom R. 1905.** Notice of some new reptiles from the Karoo Beds of South Africa. *Records of the Albany Museum* **1**:331-337.
- Broom R. 1913.** Note on *Mesosuchus browni*, Watson, and on a new South African Triassic pseudosuchian (*Euparkeria capensis*). *Records of the Albany Museum* **2**: 394-396.
- Brusatte SL, Benton MJ, Desojo JB, Langer MC. 2010.** The higher-level phylogeny of Archosauria (Tetrapoda: Diapsida). *Journal of Systematic Palaeontology* **8**(1):3-47.
- Butler RJ, Brusatte SL, Reich M, Nesbitt SJ, Schoch RR, Hornung JJ. 2011.** The sail-backed reptile *Ctenosauriscus* from the latest Early Triassic of Germany and the timing and biogeography of the early archosaur radiation. *PloS ONE* **6**(10):e25693.
- Caby R, Galli J. 1964.** Existence de cinérites et tufs volcaniques dans le Trias moyen de la zone briançonnaise. *Comptes Rendus de l'Académie des Sciences de Paris* **259**:417-420.
- Carrano MT, Wilson JA. 2001.** Taxon distributions and the tetrapod track record. *Paleobiology* **27**(3):564-582.
- Carraro F, Dal Piaz GV, Franceschetti B, Malaroda R, Sturani C, Zanella E. 1970.** Carta Geologica del massiccio dell'Argentera alla scala 1: 50.000 e Note Illustrative. *Memorie della Società Geologica Italiana* **9**:557-663.

- Cassinis G, Perotti C, Santi G. 2018.** Post-Variscan Verrucano-like deposits in Italy, and the onset of the alpine tectono-sedimentary cycle. *Earth-Science Reviews* **185**:476-497.
- Cavin L, Avanzini M, Bernardi M, Piuze A, Proz PA, Meister C, Boissonnas J, Meyer CA. 2012.** New vertebrate trackways from the autochthonous cover of the Aiguilles Rouges Massif and reevaluation of the dinosaur record in the Valais, SW Switzerland. *Swiss Journal of Palaeontology* **131**:317-324.
- Charig AJ, Reig OA. 1970.** The classification of the Proterosuchia. *Biological Journal of the Linnean Society* **2**(2):125-171.
- Charig AJ, Sues H-D. 1976.** Proterosuchia. In: Kuhn, O. (ed.) *Handbuch der Paläoherpetologie* 13. Gustav Fischer, Stuttgart, 11–39.
- Chatterjee S. 1985.** *Postosuchus*, a new thecodontian reptile from the Triassic of Texas and the origin of tyrannosaurs. *Philosophical Transactions of the Royal Society of London B* **309**:395-460.
- Chen ZQ, Benton MJ. 2012.** The timing and pattern of biotic recovery following the end-Permian mass extinction. *Nature Geoscience* **5**(6):375-383.
- Citton P, Ronchi A, Nicosia U, Sacchi E, Maganuco S, Cipriani A, Innamorati G, Zuccari C, Manucci F, Romano M. 2020.** Tetrapod tracks from the Middle Triassic of NW Sardinia (Nurra region, Italy). *Italian Journal of Geosciences* **139**(2):309-320.
- Costamagna LG. 2013.** Middle Triassic carbonate lithostratigraphy of the Southern Briançonnais (Cottian Alps, Italy) and comparison with the surrounding areas. *GeoActa* **12**:1-24.
- Costamagna LG, Barca S, Nervo R. 2002.** Analisi di facies della successione carbonatica mediotriassica del Dominio Brianzone fra le valli Stura e Maira (Alpi Occidentali, Cuneo,

Italia): La sezione del Vallone del Preit. In: Fioraso G., Malusà M., Mosca P. & Tallone S. (eds.) - 81^a Riunione estiva SGI, Riassunti delle Comunicazioni orali e dei poster: 110-111, Torino.

Courel L, Demathieu G. 1976. Une ichnofaune reptilienne remarquable dans les grès Triasique de Largentière (Ardèche, France). *Palaeontogr. A* **151**: 194–216.

Courel L, Demathieu G, Gall JC. 1979. Figures sédimentaires et traces d'origine biologique du Trias moyen de la bordure orientale du Massif Central. Signification sédimentologique et paleoécologique. *Geobios* **12**: 379-397.

Cruickshank ARI. 1972. The proterosuchian thecodonts. In: Joysey, K. A. & Kemp, T. S. (eds) *Studies in Vertebrate Evolution*. Oliver and Boyd, Edinburgh, 89–119.

Cruickshank ARI. 1978. The pes of *Eythrosuchus africanus* Broom. *Zoological Journal of the Linnean Society* **62**:161-177.

d'Atri A, Piana F, Barale L, Bertok C, Martire L. 2016. Geological setting of the southern termination of Western Alps. *International Journal of Earth Sciences* **105(6)**:1831-1858.

Decarlis A, Lualdi A. 2009. A sequence stratigraphic approach to a Middle Triassic shelf-slope complex of the Ligurian Alps (Ligurian Briançonnais, Monte Carmo-Rialto unit, Italy). *Facies* **55**:267-290.

Decarlis A, Dallagiovanna G, Lualdi A, Maino M, Seno S. 2013. Stratigraphic evolution in the Ligurian Alps between Variscan heritages and the Alpine Tethys opening: A review. *Earth-Science Reviews* **125**:43-68.

Decarlis A, Manatschal G, Hauptert I, Masini E 2015. The tectono-stratigraphic evolution of distal, hyper-extended magma-poor conjugate rifted margins: Examples from the Alpine Tethys and Newfoundland–Iberia. *Marine and Petroleum Geology* **68**:54-72.

- 747 **Demathieu G. 1970.** Les empreintes de pas de vertébrés du Trias de la bordure Nord-Est du
- 748 Massif Central. Cahiers de Paléontologie CRNS Paris, 211 p.
- 749 **Demathieu G. 1984.** Une ichnofaune du Trias moyen du bassin de Lodève (Hérault, France).
- 750 *Ann. Paleontol. (Vertebr.-Invertebr.)* **70**: 247-273.
- 751 **Demathieu G, Weidmann M. 1982.** Les empreintes de pas de reptiles dans le Trias du Vieux
- 752 Emosson (Finhaut, Valais, Suisse). *Eclogae Geologicae Helvetiae* **75**:721–757.
- 753 **Díaz-Martínez I, Pérez-García A. 2012.** Historical and comparative study of the first Spanish
- 754 vertebrate paleoichnological record and bibliographic review of the Spanish chirotheriid
- 755 footprints. *Ichnos*, **19(3)**: 141-149.
- 756 **Díaz-Martínez I, Castanera D, Gasca JM, Canudo JI. 2015.** A reappraisal of the Middle
- 757 Triassic chirotheriid *Chirotherium ibericus* Navas, 1906 (Iberian Range, NE Spain), with
- 758 comments on the Triassic tetrapod track biochronology of the Iberian Peninsula. *PeerJ*
- 759 **3**:1044.
- 760 **Diedrich C. 2015.** *Isochirotherium* trackways, their possible trackmakers (?*Arizonasaurus*):
- 761 intercontinental giant archosaur migrations in the Middle Triassic tsunami-influenced
- 762 carbonate intertidal mud flats of the European Germanic Basin. *Carbonates and Evaporites*
- 763 **30**:229-252.
- 764 **Egerton PG. 1839.** On two casts in sandstone of impression of the Hind Foot of a gigantic
- 765 *Cheirotherium*, from the New red sandstone of Cheshire. *The London and Edinburgh*
- 766 *Philosophical Magazine and Journal of Science, 3rd series* **14(75)**:151-158.
- 767 **Erwin DH. 1992.** A preliminary classification of evolutionary radiations. *Historical Biology*
- 768 **6**:133–147.

- 769 **Erwin DH. 1993.** The Great Paleozoic Crisis, Life and Death in the Permian. Colombia
- 770 University Press, New York, 327 pp.
- 771 **Erwin DH. 2001.** Lessons from the past: biotic recoveries from mass extinctions. *Proceedings of*
- 772 *the National Academy of Sciences* **98(10)**:5399-5403.
- 773 **Evans SE, Wang Y. 2005.** *Dalinghosaurus*, a lizard from the Early Cretaceous Jehol Biota of
- 774 north- east China. *Acta Paleontologica Polonica* **50**:725-742.
- 775 **Ezcurra MD. 2016.** The phylogenetic relationships of basal archosauromorphs, with an
- 776 emphasis on the systematics of proterosuchian archosauriforms. *PeerJ* **4**:e1778.
- 777 **Ezcurra MD, Butler RJ. 2015.** Taxonomy of the proterosuchid archosauriforms (Diapsida:
- 778 Archosauromorpha) from the earliest Triassic of South Africa, and implications for the early
- 779 archosauriform radiation. *Palaeontology* **58(1)**:141-170.
- 780 **Ezcurra MD, Butler RJ, Gower DJ. 2013.** ‘Proterosuchia’: the origin and early history of
- 781 Archosauriformes. *Geological Society, London, Special Publications* **379(1)**:9-33.
- 782 **Ezcurra MD, Gower DJ, Sennikov AG, Butler RJ. 2019.** The osteology of the holotype of the
- 783 early erythrosuchid *Garjainia prima* Ochev, 1958 (Diapsida: Archosauromorpha) from the
- 784 upper Lower Triassic of European Russia. *Zoological Journal of the Linnean Society*
- 785 **185**:717–783.
- 786 **Ezcurra MD, Jones AS, Gentil AR, Butler RJ. 2020.** Early Archosauromorphs: The Crocodile
- 787 and Dinosaur Precursors. Encyclopedia of Geology, 2nd edition.
- 788 **Ezcurra MD, Velozo P, Meneghel M, Piñeiro G. 2015.** Early archosauromorph remains from
- 789 the Permo-Triassic Buena Vista Formation of north-eastern Uruguay. *PeerJ* **3**:e776.
- 790 **Feldmann M, Furrer H, Glarus K. 2009.** Die Saurierspuren am Tödi und ihre geologische
- 791 Umgebung. *Mitteilungen der Naturforschenden Gesellschaft des Kantons Glarus* **18**:28-37.

- Fortuny J, Bolet A, Selles AG, Cartanya J, Galobart A. 2011. New insights on the Permian and Triassic vertebrates from the Iberian peninsula with emphasis on the Pyrenean and Catalanian basins. *Journal of Iberian Geology* **37**(1):65-86.
- Gand G. 1978. Interprétations paléontologique et paléoécologique d'un sixième assemblage à traces de reptiles des carrières triasiques de St.-Sernin-du Bois (Autunois, France). Conclusions générales à étude du gisement. *Bulletin de la Société d'Histoire Naturelle d'Autun* **87**: 9–29.
- Gand G. 1979. Description de deux nouvelles traces d'*Isochirotherium* observées dans les grès du Trias moyen de Bourgogne. *Bull. Soc. Hist. Nat. Creusot* **37**: 13–25.
- Gidon M. 1958a. Nouvelles observations sur la zone briançonnaise au delà de la frontière franco-italienne (Bassin de la Haute Maira, Province de Cuneo). *Trav. Lab. Géol. Univ. Grenoble* **34**:153-167.
- Gidon M. 1958b. La Zone Briançonnaise en Haute Ubaye (Basses-Alpes) et son prolongement au Sud-Est. PhD Thesis. Faculté des Sciences de l'Université de Grenoble, 272 pp.
- Gidon M. 1972. Les chainons briançonnais et subbriançonnais de la rive gauche de la Stura entre la Val de l'Arma (province de Cuneo-Italie). *Géologie Alpine* **48**(1):87-120.
- Gidon M. 1978. Carte géologique détaillée de la France à l'échelle 1/50.000, feuille Larche, 1^o édition. Bureau de Recherche Géologique et Minière, Orléans, with explanatory notes, pp. 1–28.
- Golden Software 2002. Surfer version 8.0: surface mapping system.
- Gottmann-Quesada A, Sander PM. 2009. A redescription of the early archosauromorph *Protorosaurus speneri* Meyer, 1832 and its phylogenetic relationships. *Palaeontographica Abteilung A* **287**:123-220.

- 815 **Gower DJ. 1996.** The tarsus of erythrosuchid archosaurs, and implications for early diapsid
816 phylogeny. *Zoological Journal of the Linnean Society* **116(4)**:347-375.
- 817 **Gower DJ. 2003.** Osteology of the early archosaurian reptile *Erythrosuchus africanus* Broom.
818 *Annals of the South African Museum* **110**:1-88.
- 819 **Gower DJ, Sennikov AG. 2000.** Early Archosaurs from Russia. In: Benton MJ, Shishkin MA,
820 Unwin DM, Kurochkin EN, editors. The Age of Dinosaurs in Russia and Mongolia.
821 Cambridge University Press, Cambridge. pp. 140–159.
- 822 **Gower DJ, Hancox PJ, Botha-Brink J, Sennikov AG, Butler RJ. 2014.** A new species of
823 *Garjainia* Ochev, 1958 (Diapsida: Archosauriformes: Erythrosuchidae) from the Early
824 Triassic of South Africa. *PLoS One* **9(11)**:e111154.
- 825 **Grasby SE, Sanei H, Beauchamp B. 2011.** Catastrophic dispersion of coal fly ash into oceans
826 during the latest Permian extinction. *Nature Geoscience* **4(2)**:104.
- 827 **Hallam A. 1991.** Why was there a delayed radiation after the end-Palaeozoic extinctions?.
828 *Historical Biology* **5(2-4)**:257-262.
- 829 **Haubold H, Klein H. 2002.** Chirotherien und Grallatoriden aus der Unteren bis Oberen Trias
830 Mitteleuropas und die Entstehung der Dinosauria. *Hallesches Jahrbuch für*
831 *Geowissenschaften B* **24**:1-22.
- 832 **Haubold H. 1967.** Eine Pseudosuchier- Fährtenfauna aus dem buntsandstein südthüringens.
833 *Hallesches Jahrbuch für Mitteldeutsche Erdgeschichte* **8**:12-48.
- 834 **Haubold H. 1984.** Saurierfährten. A. Ziemsen Verlag, Wittenberg, 232 pp.
- 835 **Haubold H. 1971a.** Die Tetrapodenfährten des Buntsandsteins. *Paläontologische Abhandlungen*
836 *A* **4(3)**:395-548.

- 837 **Haubold H. 1971b.** Ichnia Amphibiorum et Reptiliorum fossilium. Encyclopedia of
838 Paleoherpetology **18**:1-124.
- 839 **Haubold H. 1970.** Die Tetrapodenfährten des Germanischen Buntsandsteins und ihre
840 Äquivalente in der gesamten Trias. *Paläontologische Abhandlungen, Abteilung A,*
841 *Palaeozoologie*, **4**.
- 842 **Haubold H. 1984.** Saurierfährten. Wittenberg, Ziemsen, 231 p.
- 843 **Haubold H. 1986.** Archosaur footprints at the terrestrial Triassic–Jurassic transition. 190–201.
844 In Padian K. (ed.). The beginning of the Age of Dinosaurs: Faunal change across the Triassic–
845 Jurassic boundary. Cambridge University Press, Cambridge, 378 pp.
- 846 **Haubold H. 2006.** Die Saurierfährten *Chirotherium barthii* Kaup, 1835—das Typusmaterial aus
847 dem Buntsandstein bei Hildburghausen/Thüringen und das Chirotherium-Monument.
848 *Veröffentlichungen Naturhistorisches Museum Schleusingen* **21**:3–31.
- 849 **Huene F. von 1902.** Übersicht über die Reptilien der Trias. *Geologische und Paläontologische*
850 *Abhandlungen* **10**:1-84.
- 851 **Joachimski MM, Lai X, Shen S, Jiang H, Luo G, Chen B, Chen J, Sun Y. 2012.** Climate
852 warming in the latest Permian and the Permian–Triassic mass extinction. *Geology* **40**:195–
853 198.
- 854 **Kaup JJ. 1835.** Über Tierfährten bei Hildburghausen. *Neues Jahrbuch für Mineralogie,*
855 *Geologie und Paläontologie* 1835, 327–328.
- 856 **Kidder DL, Worsley TR. 2004.** Causes and consequences of extreme Permo–Triassic warming
857 to globally equable climate and relation to the Permo–Triassic extinction and recovery.
858 *Palaeogeography, Palaeoclimatology, Palaeoecology* **203(3–4)**:207–237.

- 859 **King MJ, Sarjeant WAS, Thompson DB, Tresise G. 2005.** A revised systematic
860 ichnotaxonomy and review of the vertebrate footprint ichnofamily Chirotheriidae from the
861 British Triassic. *Ichnos* **12**:241-299.
- 862 **Klein H, Lucas SG. 2010a.** Tetrapod footprints and their use in biostratigraphy and
863 biochronology of the Triassic. In Lucas, S.G. (ed.), The Triassic timescale. *Geological Society*
864 *of London Special Publications* **334**:419-446.
- 865 **Klein H, Niedźwiedzki G. 2012.** Revision of the Lower Triassic tetrapod ichnofauna from
866 Wióry, Holy Cross Mountains, Poland. *New Mexico Museum of Natural History and Science,*
867 *Bulletin* **56**:1-62.
- 868 **Klein H, Haubold H. 2007.** Archosaur footprints-potential for biochronology of Triassic
869 continental sequences. *New Mexico Museum of Natural History and Science Bulletin* **41**:120-
870 130.
- 871 **Klein H, Lucas SG. 2010.** Review of the tetrapod ichnofauna of the Moenkopi Formation/Group
872 (Early-Middle Triassic) of the American Southwest. *New Mexico Museum of Natural History*
873 *and Science Bulletin* **50**:1-67.
- 874 **Klein H, Voigt S, Hminna A, Saber H, Schneider J, Hmich D. 2010.** Early Triassic archosaur-
875 dominated footprint assemblage from the Argana Basin (western High Atlas, Morocco).
876 *Ichnos* **17(3)**:215-227.
- 877 **Klein H, Voigt S, Saber H, Schneider JW, Hminna A, Fischer J, Lagnaoui A, Brosig A.**
878 **2011.** First occurrence of a Middle Triassic tetrapod ichnofauna from the Argana Basin
879 (Western High Atlas, Morocco). *Palaeogeography, Palaeoclimatology, Palaeoecology*
880 **307**:218-231.

- 881 **Klein H, Wizevich MC, Thüring B, Marty D, Thüring S, Falkingham P, Meyer CA. 2016.**
- 882 Triassic chirotheriid footprints from the Swiss Alps: ichnotaxonomy and depositional
- 883 environment (Cantons Wallis & Glarus). *Swiss Journal of Palaeontology*, **135(2)**: 295-314.
- 884 **Knoll AH, Bambach RK, Payne JL, Pruss S, Fischer WW. 2007.** Paleophysiology and end–
- 885 Permian mass extinction. *Earth and Planetary Science Letters* **256(3–4)**:295–313.
- 886 **Krainer K, Lucas SG, Ronchi A. 2012.** Tetrapod footprints from the Alpine Buntsandstein
- 887 (Lower Triassic) of the Drau Range (Eastern Alps, Austria). *Jahrbuch der Geologischen*
- 888 *Bundesanstalt* **152**:205-212.
- 889 **Krebs B. 1965.** Die Triasfauna der Tessiner Kalkalpen, XIX. *Ticinosuchus ferox* nov. gen. nov.
- 890 sp. *Schweizerische Paläontologische Abhandlungen* **81**:1-140.
- 891 **Kubo T, Benton MJ. 2007.** Evolution of hindlimb posture in archosaurs: limb stresses in extinct
- 892 vertebrates. *Palaeontology* **50(6)**:1519-1529.
- 893 **Kubo T, Benton MJ. 2009.** Tetrapod postural shift estimated from Permian and Triassic
- 894 trackways. *Palaeontology* **52(5)**:1029-1037.
- 895 **Lautenschlager S, Desojo JB. 2011.** Reassessment of the Middle Triassic rauisuchian
- 896 archosaurs *Ticinosuchus ferox* and *Stagonosuchus nyassicus*. *Paläontologische Zeitschrift*
- 897 **85(4)**: 357-381.
- 898 **Leonardi G. 1987.** Glossary and manual of tetrapod footprint palaeoichnology. p.p. 117.
- 899 Brasilia: Ministerio das Minas e Energia Departamento Nacional da Producao Mineral.
- 900 **Lorenzoni S, Zanettin E. 1958.** Contributo alla conoscenza del giacimento uranifero di Preit
- 901 (Alpi Cozie). *Studi e Ricerche Divisione Geomineraria CNRN* **1(2)**:349-433.

- 902 **Lualdi A, Bianchi U. 1990.** La Formazione di Costa Losera: una nuova unità stratigrafica
903 dell'Anisico delle Alpi Liguri. *Atti Ticinensi di Scienze della Terra* **33**:33-62.
- 904 **Lualdi A, Seno S. 1984.** Osservazioni stratigrafiche e tettoniche nella zona dei Rio di Nava
905 (Brianzone Ligure Esterno, Unità di Ormea). *Memorie della Società Geologica Italiana*
906 **28**:493-503.
- 907 **Malaroda R. 1970.** Carta geologica del Massiccio dell'Argentera alla scala 1: 50.000. Allegato
908 al vol. **9** delle *Memorie della Società Geologica Italiana*.
- 909 **Mallison H, Wings O. 2014.** Photogrammetry in paleontology—a practical guide. *Journal of*
910 *Paleontological Techniques* **12**:1-31.
- 911 **Manning PL. 2004.** A new approach to the analysis and interpretation of tracks: examples from
912 the dinosauria. *Geological Society, London, Special Publications*, **228(1)**: 93-123.
- 913 **Megard-Galli J, Baud A. 1977.** Le Trias moyen et supérieur des Alpes nord-occidentales et
914 occidentales: données nouvelles et corrélations stratigraphiques. *Bulletin B.R.G.M.* **4(3)**:233-
915 250.
- 916 **Melchor RN, De Valais S. 2006.** A review of Triassic tetrapod track assemblages from
917 Argentina. *Palaeontology* **49(2)**:355-379.
- 918 **Motani R, Jiang DY, Chen GB, Tintori A, Rieppel O, Ji C, Huang JD. 2015a.** A basal
919 ichthyosauriform with a short snout from the Lower Triassic of China. *Nature* **517(7535)**:485-
920 488.
- 921 **Motani R, Jiang DY, Tintori A, Rieppel O, Chen GB, You H. 2015b.** Status of *Chaohusaurus*
922 *chaoxianensis* (Chen, 1985). *Journal of Vertebrate Paleontology* **35(1)**:e892011.
- 923 **Nesbitt SJ. 2011.** The early evolution of archosaurs: relationships and the origin of major clades.
924 *Bulletin of the American Museum of Natural History* **41(supp.)**:1-292.

- 925 **Nesbitt SJ, Liu J, Li C. 2010.** A sail-backed suchian from the Heshanggou Formation (Early
- 926 Triassic: Olenekian) of China. *Earth and Environmental Science Transactions of the Royal*
- 927 *Society of Edinburgh* **101**:271–284.
- 928 **Olsen PE. 1995.** A new approach for recognizing track makers. *Geological Society of America,*
- 929 *Abstracts with Programs* **27**:72.
- 930 **Olsen PE, Smith JB, McDonald NG. 1998.** Typematerial of the type species of the classic
- 931 theropod footprint genera Eubrontes, Anchisauripus and Grallator (Early Jurassic, Hartford
- 932 and Deerfield basins, Connecticut and Massachusetts, U.S.A.). *J. Vertebr. Paleontol.* **18**: 586–
- 933 601.
- 934 **Payne JL, Lehrmann DJ, Wei J, Orchard MJ, Schrag DP, Knoll AH. 2004.** Large
- 935 perturbations of the carbon cycle during recovery from the end-Permian extinction. *Science*
- 936 **305**:506-509.
- 937 **Payne JL, Summers M, Rego BL, Altiner D, Wei J, Yu M, Lehrmann DJ. 2011.** Early and
- 938 Middle Triassic trends in diversity, evenness, and size of foraminifers on a carbonate platform
- 939 in south China: implications for tempo and mode of biotic recovery from the end-Permian
- 940 mass extinction. *Paleobiology* **37**:409-425.
- 941 **Peabody FE. 1948.** Reptile and amphibian trackways from the Lower Triassic Moenkopi
- 942 formation of Arizona and Utah. *Bulletin of the Department of Geological sciences* **27**:295-
- 943 468.
- 944 **Peacock BR, Smith RM, Sidor CA. 2018.** A novel archosauromorph from Antarctica and an
- 945 updated review of a high-latitude vertebrate assemblage in the wake of the end-Permian mass
- 946 extinction. *Journal of Vertebrate Paleontology* **38(6)**:e1536664.

- Petti FM, Avanzini M, Belvedere M, De Gasperi M, Ferretti P, Girardi S, Remondino F, Tomasoni R. 2008.** Digital 3D modelling of dinosaur footprints by photogrammetry and laser scanning techniques: integrated approach at the Coste dell'Anglone tracksite (Lower Jurassic, Southern Alps, Northern Italy). *Studi Trentini di Scienze Naturali, Acta Geologica* **83**:303-315.
- Petti FM, Bernardi M, Kustatscher E, Renesto S, Avanzini M. 2013.** Diversity of continental tetrapods and plants in the Triassic of the Southern Alps: Ichnological, paleozoological and paleobotanical evidence. In Tanner, L.H., Spielmann, J.A. and Lucas, S.G. (eds.), The Triassic System. *New Mexico Museum of Natural History and Science, Bulletin* **61**:458-484.
- Peyer K, Carter JG, Sues H-D, Novak SE, Olsen PE. 2008.** A new suchian archosaur from the Upper Triassic of North Carolina. *Journal of Vertebrate Paleontology* **28**:363-381.
- Pough FH, Heiser JB, McFarland WN. 1996.** Vertebrate Life. Prentice Hall International, New Jersey.
- Racki G. 2003.** End-Permian mass extinction: oceanographic consequences of double catastrophic volcanism. *Lethaia* **35**:171-173.
- Racki G, Wignall PB. 2005.** Late Permian double-phased mass extinction and volcanism: an oceanographic perspective. In: Over, D.J., Morrow, J.R., Wignall, P.B. (Eds.), Understanding Late Devonian and Permian-Triassic Biotic and Climatic Events: Towards an Integrated Approach. Elsevier B.V., pp. 263-297.
- Remondino F, Rizzi A, Girardi S, Petti FM, Avanzini M. 2010.** 3D Ichnology—recovering digital 3D models of dinosaur footprints. *The Photogrammetric Record* **25(131)**:266-282.
- Retallack GJ. 2005.** Permian greenhouse crises. The nonmarine Permian. *New Mexico Museum of Natural History and Science Bulletin* **30**:256-269.

- Retallack GJ. 2009.** Greenhouse crises of the past 300 million years. *Geological Society of America Bulletin* **121(9-10)**:1441-1455.
- Retallack GJ. 2013.** Permian and Triassic greenhouse crises. *Gondwana Research* **24(1)**:90-103.
- Retallack GJ, Jahren AH. 2008.** Methane release from igneous intrusion of coal during Late Permian extinction events. *The Journal of Geology* **116**:1–20.
- Retallack GJ, Sheldon ND, Carr PF, Fanning M, Thompson CA, Williams ML, ... Hutton A. 2011.** Multiple Early Triassic greenhouse crises impeded recovery from Late Permian mass extinction. *Palaeogeography, Palaeoclimatology, Palaeoecology* **308(1–2)**:233–251.
- Romano M, Citton P, Nicosia U. 2015.** Corroborating trackmaker identification through footprint functional analysis: the case study of *Ichniotherium* and *Dimetropus*. *Lethaia* **49**:102-116.
- Romer AS. 1971.** The Chanares (Argentina) Triassic reptile fauna XI. Two new long-snouted thecodonts, *Chanaresuchus* and *Gualosuchus*. *Breviora* **379**:1-22.
- Santi G, Lualdi A, Decarlis A, Nicosia U, Ronchi A. 2015.** Chirotheriid footprints from the Lower-Middle Triassic of the Briançonnais Domain (Pelite di Case Valmarenca, Western Liguria, NW Italy). *Bollettino della Società Paleontologica Italiana* **54(2)**:82.
- Scheyer TM, Romano C, Jenks J, Bucher H. 2014.** Early Triassic marine biotic recovery: the predators’ perspective. *PLoS ONE* **9**:e88987.
- Sephton MA, Looy CV, Brinkhuis H, Wignall PB, de Leeuw JW, Visscher H. 2005.** Catastrophic soil erosion during the end–Permian biotic crisis. *Geology* **33**:941–944.
- Sereno PC. 1991.** Basal archosaurs: phylogenetic relationship and functional implications. *Journal of Vertebrate Paleontology* **11**:1–53.

- 992 **Shen J, Chen J, Algeo TJ, Yuan S, Feng Q, Yu J, ... Planavsky NJ. 2019.** Evidence for a
993 prolonged Permian–Triassic extinction interval from global marine mercury records. *Nature*
994 *communications* **10(1)**:1563.
- 995 **Schmid SM, Fügenschuh B, Kissling E, Schuster R. 2004.** Tectonic map and overall
996 architecture of the Alpine orogen. *Eclogae Geologicae Helvetiae* **97**:93-117.
- 997 **Schmid SM, Kissling E, Diehl T, van Hinsbergen DJJ, Molli G. 2017.** Ivrea mantle wedge,
998 arc of the Western Alps, and kinematic evolution of the Alps - Apennines orogenic system.
999 *Swiss Journal of Geosciences* **110**:581-612.
- 1000 **Schobben M, Joachimski MM, Korn D, Leda L, Korte C. 2014.** Palaeotethys seawater
1001 temperature rise and an intensified hydrological cycle following the end–Permian mass
1002 extinction. *Gondwana Research* **26**:675–683.
- 1003 **Sepkoski JJ Jr. 1984.** A kinetic model of Phanerozoic taxonomic diversity. III. Post–Paleozoic
1004 families and mass extinctions. *Paleobiology* **10**:246–267.
- 1005 **Smith RMH, Evans SE. 1996.** New material of *Youngina*: evidence of juvenile aggregation in
1006 Permian diapsid reptiles. *Palaeontology* **39**:289-303.
- 1007 **Song H, Wignall PB, Tong J, Yin H. 2013.** Two pulses of extinction during the Permian–
1008 Triassic crisis. *Nature Geoscience* **6(1)**:52.
- 1009 **Song H, Wignall PB, Tong J, Song H, Chen J, Chu D, ... Lai X. 2015.** Integrated Sr isotope
1010 variations and global environmental changes through the Late Permian to early Late Triassic.
1011 *Earth and Planetary Science Letters* **424**:140–147.
- 1012 **Sookias RB, Butler RJ. 2013.** Euparkeriidae. *Geological Society, London, Special Publications*
1013 **379**:35-48.
- 1014 **Sues HD, Desojo JB, Ezcurra MD. 2013.** Doswelliidae: a clade of unusual armoured

archosauriforms from the Middle and Late Triassic. *Geological Society, London, Special Publications* **379**:SP379-13.

Sun Y, Joachimski M, Wignall PB, Yan C, Chen Y, Jiang H, Wang L, Lai X. 2012. Lethally Hot Temperatures During the Early Triassic Greenhouse. *Science* **338**:1-35.

Torsvik TH, Van Der Voo R, Preeden U, Mac C, Steinberger B, Doubrovine PV, van Hinsbergen DJJ, Domeier M, Gaina C, Tohver E, Meert JG, McCausland PJA, Cocks LRM. 2012. Earth-Science Reviews Phanerozoic polar wander, palaeogeography and dynamics. *Earth Science Reviews* **114**(3–4):325-368.

Treasure G, Sarjeant WAS. 1997. The tracks of Triassic Vertebrates. Fossil Evidence from North-West England. The stationery Office, London, 204 pp.

Trotteyn MJ, Arcucci AB, Raugust T. 2013. Proterochampsia: an endemic archosauriform clade from South America. In: Anatomy, Phylogeny and Palaeobiology of Early Archosaurs and their Kin (eds Nesbitt S.J., Desojo J.B., Irmis R.B.), *Geological Society, London, Special Publications* **379**:59–90.

Van Hinsbergen DJJ, De Groot LV, Van Schaik SJ, Spakman W, Bijl PK, Sluijs A, Langereis CG, Brinkhuis H. 2015. A paleolatitude calculator for paleoclimate studies. *PLoS ONE* **10**(6):1-21.

Vanossi M. 1969. La serie brianzone di Salto del Lupo (Liguria Occ.): osservazioni sedimentologico-stratigrafiche. *Atti Ist. Geol. Univ. Pavia* **20**: 3-16.

Vanossi M. 1974. L'Unità di Ormea: una chiave per l'interpretazione del Brianzone ligure. Tipografia del libro.

Vanossi M. 1991. Guide Geologiche Regionali, 11 itinerari, Alpi Liguri (a cura della SGI), 296 pp. BE-MA Edit., Milano.

- 1038 **Welles SP. 1947.** Vertebrates from the Upper Moenkopi Formation of Northern Arizona.
1039 *University of California Publications in Geological Science* **27**:241-294.
- 1040 **Whiteside JH, Ward PD. 2011.** Ammonoid diversity and disparity track episodes of chaotic
1041 carbon cycling during the early Mesozoic. *Geology* **39**:99–102.
- 1042 **Wignall PR. 2001.** Large igneous provinces and mass extinctions. *Earth-Science Reviews* **53**:1–
1043 33.
- 1044 **Wilson JA 2005.** Integrating ichnofossil and body fossil records to estimate locomotor posture
1045 and spatiotemporal distribution of early sauropod dinosaurs: a stratocladistic approach.
1046 *Paleobiology* **31**(3): 400-423.
- 1047 **Withers PC. 1992.** Comparative Animal Physiology. Saunders College, New York.
- 1048 **Xing LD, Klein H, Lockley MG, Li J, Zhang J, Matsukawa M, Xiao J. 2013.** *Chirotherium*
1049 trackways from the Middle Triassic of Guizhou, China. *Ichnos* **20**:99–107.
- 1050 **Young CC. 1964.** The pseudosuchians in China. *Palaeontologia Sinica Series C* **19**:105-205.
- 1051 **Zhang F. 1975.** A new thecodont *Lotosaurus*, from Middle Triassic of Hunan. *Vertebrata*
1052 *Palasiatica* **13**:144-147.
- 1053 **Ziegler PA, Stampfli GM. 2001.** Late Palaeozoic–Early Mesozoic plate boundary
1054 reorganization: collapse of the Variscan orogen and opening of Neotethys. In: Cassinis G.
1055 (Ed.), Permian Continental Deposits of Europe and Other Areas. Regional Reports and
1056 Correlations. Annali Museo Civico Scienze Naturali, Brescia **25**:17–34.

Figure captions

Fig. 1 - Geologic map of the Pianezza area. In the upper row the location of Maira Valley and Gardetta-Pianezza area. For the geologic map: 1= volcanic complex and graphitic schist (upper Carboniferous - Permian); 2= conglomerate, 3= quartz-conglomerate, and 4= quartz-arenite and quartz-siltite of the quartzitic complex (upper Permian - early Lower Triassic); 5= lower carniole complex (late Lower Triassic); 6= lower calcareous complex (lower Anisian - early upper Ladinian); 7= upper dolomitic complex (upper Ladinian); 8= lakes and peat bog; 9= faults; 10= location of the footprint site; in white the detritic cover and moraines.

Fig. 2 - Correlation scheme among the Briançonnais s.s., the Ligurian Briançonnais, from De Carlis & Lualdi, 1990 redrawn and modified. PNQ: “Ponte di Nava Quartzites”, CVP: Case Val Marenca Pelites. The footprint silhouette marks the position of the track-bearing horizon.

Fig. 3 – a) Panoramic view of the track surface with the line-drawing of the chirotherian trackways. In pale yellow the above-lying bed characterized by symmetric wave ripples; b) Detailed view of the GT-1 and GT-2 trackways, highlighted with the black colour.

Fig. 4 – *Isochirotherium gardettae* ichnosp. nov. The GT-7 trackway, made of three consecutive manus-pes couples, is here highlighted by the red chalk and preserved in the upper track-bearing surface. Scale bar: 13 cm.

Fig. 5 – a) *Isochirotherium gardettae* ichnosp. nov. Colour-coded and contour line image of the GT-7 trackway; b) Interpretative drawing of the GT-7 trackway.

Fig. 6 – Reconstruction of the trackmaker’s fore- and hind limbs, based on the 3D model and its interpretative drawing. Dashed lines define the metatarsal of digit V held lifted off the ground during locomotion.

Fig. 7 – Pentadactyl tracks from the Lower and Middle Triassic, assigned to the ichnogenus *Chirotherium* and their comparison with the studied tracks of the Gardetta ichnosite: a) GT-1-3; b) GT-2-3; c) GT-2-8; d) GT-2-6; e), f) *Chirotherium barthiii* pes manus sets from type surface of the “Thüringischer Chirotheriensandstein”, Hildburghausen, Germany; g) *Chirotherium barthiii* pes manus set from the Holbrook Member of the Moenkopi Formation (Middle Triassic), southwest of Cameron, northern Arizona; h) *Chirotherium vorbachii* pes manus set from the Lower Triassic of Aura an der Saale, Germany; i), *Chirotherium sickleri* “Thüringischer Chirotheriensandstein”, Germany; l), m) *Chirotherium sickleri* pes manus sets from the Wupatki Member of the Moenkopi Formation (Lower Triassic), Meteor Crater, Arizona. Scale bar 10 cm.

Fig. 8 - Pentadactyl tracks from the Lower and Middle Triassic, assigned to the ichnogenus *Isochirotherium* and their comparison with the studied tracks of the Gardetta ichnosite: a), b), c), pes manus sets of the GT-7 trackway; d) GT-3 isolated pes imprints of the lower track surface; e) *Isochirotherium herculis* pes manus set from the “Thüringischer Chirotheriensandstein” (Lower Triassic), Germany; f) *Isochirotherium marshalli* pes manus set from the Holbrook Member of the Moenkopi Formation (Middle Triassic), Penzance, Northern Arizona; g) *Isochirotherium inferni* manus pes set from the Middle Triassic (late Anisian) of Adige Valley, Bolzano, Italy; h) *Isochirotherium coltoni* pes manus set from the Wupatki Member of the Moenkopi Formation (Lower Triassic), Meteor Crater, Arizona; i) *Isochirotherium lomasi* pes manus set from the Middle Triassic (Anisian) of Cheshire, Great Britain; l) *Isochirotherium coureli* pes manus set from the Middle Triassic (Anisian-Ladinian) of the Massif Central, France; m) *Isochirotherium hessbergense* pes manus set from the “Thüringischer Chirotheriensandstein” (Lower Triassic), Germany; n) *Isochirotherium*

1104 *demathieui* pes manus set from the Middle Triassic of Mont d'Or Lyonnais, France; o)
 1105 *Isochirotherium soergeli* pes manus set from the "Thüringischer Chirotheriensandstein"
 1106 (Lower Triassic), Germany. Scale bar 10 cm.

1107 **Fig. 9** – Fore- and hind-limb skeletons of Triassic archosauriforms and of the *Isochirotherium*
 1108 *gardettae* trackmaker. Reconstructed right pes and manus skeletons of a) the *Isochirotherium*
 1109 *gardettae* trackmaker in anterior/dorsal view; b) *Postosuchus kirkpatricki* CHATTERJEE 1985,
 1110 USA, Norian; c) *Postosuchus alisonae*, PEYER et al. 2008, USA, Norian; d) *Lotosaurus*
 1111 *adentus* ZHANG, 1975, China, Ladinian; e) *Proterosuchus fergusi* BROOM 1903, South Africa,
 1112 Induan–?early Olenekian f) *Erythrosuchus africanus* BROOM 1905, South Africa, early
 1113 Anisian; g) *Shansisuchus shansisuchus* YOUNG 1964, China, late Anisian; h) *Euparkeria*
 1114 *capensis* Broom, 1913, South Africa, Anisian; i) *Chanaresuchus bonapartei* ROMER, 1971,
 1115 Argentina, Ladinian. Scale bars: a), b), c), d), f) g) = 10 cm; e), h) and i) = 1 cm.

1116 **Fig. 10** – Life appearance of the non-archosaurian archosauriform (?Erythrosuchid) the most
 1117 suitable producer of *Isochirotherium gardettae*. Simplified reconstruction of fore and hind
 1118 autopodials in bottom (a) view. Complete life reconstruction in bottom (b), back (c), frontal
 1119 (d) and lateral view (e) of the trackmaker. The gait and fore- and hind limbs were
 1120 reconstructed according to the pattern and morphologies of GT-7 trackway (artwork by the
 1121 Italian artist Fabio Manucci). See the supplementary video to get a more complete view of the
 1122 reconstruction.

1123 **Fig. 11** – Paleogeographic distribution of Early Triassic archosauriform footprints (yellow stars)
 1124 and body fossil localities across Pangea. Black square = indeterminate archosauromorphs, red
 1125 circles = non-archosauriform archosauromorphs, blue stars = archosauriforms. The
 1126 palaeolatitude estimate for the southern Briançonnais domain is 11.8 N in the Olenekian (250

1127 Ma), confirming that archosauriforms were distributed also at low latitudes, in the tropical
 1128 humid climatic belt. ImagePaleomap for 250 Ma downloaded from Fossilworks using data
 1129 from the Paleobiology Database (Alroy, 2003). Redrawn and modified from Bernardi et al.,
 1130 2015 and Benton (2018).

1131

Figure 1

Geologic map of the Pianezza area

Fig. 1 - Geologic map of the Pianezza area. In the upper row the location of Maira Valley and Gardetta-Pianezza area. For the geologic map: (1) volcanic complex and graphitic schist (upper Carboniferous - Permian). (2) Conglomerate. (4) Quartz-conglomerate, and quartz-arenite and quartz-siltite of the quartzitic complex (upper Permian - early Lower Triassic). (5) Lower carnirole complex (late Lower Triassic). (6) Lower calcareous complex (lower Anisian - early upper Ladinian). (7) Upper dolomitic complex (upper Ladinian). (8) Lakes and peat bog. (9) Faults. (10) Location of the footprint site. In white the detritic cover and moraines.




Figure 2

Correlation scheme among the Briançonnais s.s., the Ligurian Briançonnais

Fig. 2 - Correlation scheme among the Briançonnais s.s., the Ligurian Briançonnais, from De Carlis & Lualdi, 1990 redrawn and modified. (PNQ) “Ponte di Nava Quartzites”. (CVP) Case Val Marenca Pelites. The footprint silhouette marks the position of the track-bearing horizon.

				Briançonnais s.s. Baud & Megard-Galli, 1977		Ligurian Briançonnais Lualdi & Seno, 1986	
Upper Triassic		Carnian		C. CLÔTE LA CIME			
Middle Triassic		Ladinian		Upper		"Complexe schisto-dolomitique basal"	
						"Dolomies grises"	
		Lower		Upper		"Couche a C. Goldfussi"	
						"Dolomies blanches"	
		Anisian		Upper		"Calcaire rubanés"	
		Middle		Upper		Cinerites	
						Cinerites	
		Lower		Upper		"Calcaire rubanés"	
						"Calcaire rubanés"	
				100-200 m		CHIAMPICELLA FM	
				150 m		ST. TRIPHON FM	
						40 m	
						COSTA LOSERA FM	
						175 m	
						SAN PIETRO DEI MONTI FM	
						CAPONOLI FM	
Lower Triassic		Pelites - "Cagneules Inférieures"		Pelites		Quartzites	
		"Werfenian quartzites"					
		"Verrucano Brianzonese"					

Figure 3

Panoramic view of the track surface with the line-drawing of the chirotherian trackways

Fig. 3 – (a) Panoramic view of the track surface with the line-drawing of the chirotherian trackways. In pale yellow the above-lying bed characterized by symmetric wave ripples. (b) Detailed view of the GT-1 and GT-2 trackways, highlighted with the black colour.





Figure 4

Isochirotherium gardettae ichnosp. nov

Fig. 4 - *Isochirotherium gardettae* ichnosp. nov. The GT-7 trackway, made of three consecutive manus-pes couples, is here highlighted by the red chalk and preserved in the upper track-bearing surface. Scale bar: 13 cm.



Figure 5

Isochirotherium gardettae ichnosp. nov. Colour-coded and contour line image of the GT-7 trackway

Fig. 5 – a) *Isochirotherium gardettae* ichnosp. nov. Colour-coded and contour line image of the GT-7 trackway; b) Interpretative drawing of the GT-7 trackway.




Figure 6

Reconstruction of the trackmaker's fore- and hind limbs, based on the 3D model and its interpretative drawing

Fig. 6 – Reconstruction of the trackmaker's fore- and hind limbs, based on the 3D model and its interpretative drawing. Dashed lines define the metatarsal of digit V held lifted off the ground during locomotion.




Figure 7

Pentadactyl tracks from the Lower and Middle Triassic, assigned to the ichnogenus *Chirotherium* and their comparison with the studied tracks of the Gardetta ichnosite

Fig. 7 – Pentadactyl tracks from the Lower and Middle Triassic, assigned to the ichnogenus *Chirotherium* and their comparison with the studied tracks of the Gardetta ichnosite. (a) GT-1-3. (b) GT-2-3. (c) GT-2-8. d) GT-2-6; (e) and (f) *Chirotherium barthiii* pes manus sets from type surface of the “Thüringischer Chirotheriensandstein”, Hildburghausen, Germany. (g) *Chirotherium barthiii* pes manus set from the Holbrook Member of the Moenkopi Formation (Middle Triassic), southwest of Cameron, northern Arizona. (h) *Chirotherium vorbachii* pes manus set from the Lower Triassic of Aura an der Saale, Germany (i), *Chirotherium sickleri* “Thüringischer Chirotheriensandstein”, Germany. (l) and (m) *Chirotherium sickleri* pes manus sets from the Wupatki Member of the Moenkopi Formation (Lower Triassic), Meteor Crater, Arizona. Scale bar 10 cm.




Figure 8

Pentadactyl tracks from the Lower and Middle Triassic, assigned to the ichnogenus *Isochirotherium* and their comparison with the studied tracks of the Gardetta ichnosite

Fig. 8 - Pentadactyl tracks from the Lower and Middle Triassic, assigned to the ichnogenus *Isochirotherium* and their comparison with the studied tracks of the Gardetta ichnosite (a), (b), (c) Pes manus sets of the GT-7 trackway. (d) GT-3 isolated pes imprints of the lower track surface. (e) *Isochirotherium herculis* pes manus set from the “Thüringischer Chirotheriensandstein” (Lower Triassic), Germany. (f) *Isochirotherium marshalli* pes manus set from the Holbrook Member of the Moenkopi Formation (Middle Triassic), Penzance, Northern Arizona. (g) *Isochirotherium inferni* manus pes set from the Middle Triassic (late Anisian) of Adige Valley, Bolzano, Italy. (h) *Isochirotherium coltoni* pes manus set from the Wupatki Member of the Moenkopi Formation (Lower Triassic), Meteor Crater, Arizona. (i) *Isochirotherium lomasi* pes manus set from the Middle Triassic (Anisian) of Cheshire, Great Britain. (l) *Isochirotherium coureli* pes manus set from the Middle Triassic (Anisian-Ladinian) of the Massif Central, France. (m) *Isochirotherium hessbergense* pes manus set from the “Thüringischer Chirotheriensandstein” (Lower Triassic), Germany. (n) *Isochirotherium demathieui* pes manus set from the Middle Triassic of Mont d’Or Lyonnais, France. (o) *Isochirotherium soergeli* pes manus set from the “Thüringischer Chirotheriensandstein” (Lower Triassic), Germany. Scale bar 10 cm.




Figure 9

Fore- and hind-limb skeletons of Triassic archosauriforms and of the *Isochirotherium gardettae* trackmaker

Fig. 9 – Fore- and hind-limb skeletons of Triassic archosauriforms and of the *Isochirotherium gardettae* trackmaker. Reconstructed right pes and manus skeletons of (a) The *Isochirotherium gardettae* trackmaker in anterior/dorsal view. (b) *Postosuchus kirkpatricki* Chatterjee 1985, USA, Norian. (c) *Postosuchus alisonae*, Peyer et al. 2008, USA, Norian. (d) *Lotosaurus adentus* Zhang, 1975, China, Ladinian. (e) *Proterosuchus fergusi* Broom 1903, South Africa, Induan–?early Olenekian. (f) *Erythrosuchus africanus* Broom 1905, South Africa, early Anisian. (g) *Shansisuchus shansisuchus* Young 1964, China, late Anisian. (h) *Euparkeria capensis* Broom, 1913, South Africa, Anisian. (i) *Chanaresuchus bonapartei* Romer, 1971, Argentina, Ladinian. Scale bars: a), b), c), d), f) g) = 10 cm; e), h) and i) = 1 cm.




Figure 10

Life appearance of the non-archosaurian archosauriform (?Erythrosuchid) the most suitable producer of *Isochirotherium gardettae*

Fig. 10 – Life appearance of the non-archosaurian archosauriform (?Erythrosuchid) the most suitable producer of *Isochirotherium gardettae*. Simplified reconstruction of fore and hind autopodials in bottom (a) view. Complete life reconstruction in bottom (b), back (c), frontal (d) and lateral view (e) of the trackmaker. The gait and fore- and hind limbs were reconstructed according to the pattern and morphologies of GT-7 trackway (artwork by the Italian artist Fabio Manucci). See the supplementary video to get a more complete view of the reconstruction.



Figure 11

Paleogeographic distribution of Early Triassic archosauriform footprints and body fossil localities across Pangea

Fig. 11 – Paleogeographic distribution of Early Triassic archosauriform footprints (yellow stars) and body fossil localities across Pangea. Black square = indeterminate archosauromorphs, red circles = non-archosauriform archosauromorphs, blue stars = archosauriforms. The palaeolatitude estimate for the southern Briançonnais domain is 11.8 N in the Olenekian (250 Ma), confirming that archosauriforms were distributed also at low latitudes, in the tropical humid climatic belt. ImagePaleomap for 250 Ma downloaded from Fossilworks using data from the Paleobiology Database (Alroy, 2003). Redrawn and modified from Bernardi et al., 2015 and Benton (2018).

