

Transformation of the pectoral girdle in pennaraptorans : critical steps in the formation of the modern avian shoulder joint (#91670)

1

First submission

Guidance from your Editor

Please submit by **23 Nov 2023** for the benefit of the authors (and your token reward) .



Literature Review article

This is a Literature Review article, so the review criteria are slightly different. Please write your review using the criteria outlined on the 'Structure and Criteria' page.



Image check

Check that figures and images have not been inappropriately manipulated.

If this article is published your review will be made public. You can choose whether to sign your review. If uploading a PDF please remove any identifiable information (if you want to remain anonymous).

Files

Download and review all files from the [materials page](#).

7 Figure file(s)

1 Table file(s)

1 Other file(s)

Structure and Criteria

2



Structure your review

The review form is divided into 5 sections. Please consider these when composing your review:

1. **BASIC REPORTING**
2. **STUDY DESIGN**
3. **VALIDITY OF THE FINDINGS**
4. General comments
5. Confidential notes to the editor

 You can also annotate this PDF and upload it as part of your review

When ready [submit online](#).

Editorial Criteria

Use these criteria points to structure your review. The full detailed editorial criteria is on your [guidance page](#).

BASIC REPORTING

-  Clear, unambiguous, professional English language used throughout.
-  Intro & background to show context. Literature well referenced & relevant.
-  Structure conforms to [Peerj standards](#), discipline norm, or improved for clarity.
-  Is the review of broad and cross-disciplinary interest and within the scope of the journal?
-  Has the field been reviewed recently? If so, is there a good reason for this review (different point of view, accessible to a different audience, etc.)?
-  Does the Introduction adequately introduce the subject and make it clear who the audience is/what the motivation is?

STUDY DESIGN

-  Article content is within the [Aims and Scope](#) of the journal.
-  Rigorous investigation performed to a high technical & ethical standard.
-  Methods described with sufficient detail & information to replicate.
-  Is the Survey Methodology consistent with a comprehensive, unbiased coverage of the subject? If not, what is missing?
-  Are sources adequately cited? Quoted or paraphrased as appropriate?
-  Is the review organized logically into coherent paragraphs/subsections?

VALIDITY OF THE FINDINGS

-  Impact and novelty not assessed. Meaningful replication encouraged where rationale & benefit to literature is clearly stated.
-  Conclusions are well stated, linked to original research question & limited to
-  Is there a well developed and supported argument that meets the goals set out in the Introduction?
-  Does the Conclusion identify unresolved questions / gaps / future directions?

Standout reviewing tips

3



The best reviewers use these techniques

Tip

Support criticisms with evidence from the text or from other sources

Give specific suggestions on how to improve the manuscript

Comment on language and grammar issues

Organize by importance of the issues, and number your points

Please provide constructive criticism, and avoid personal opinions

Comment on strengths (as well as weaknesses) of the manuscript

Example

Smith et al (J of Methodology, 2005, V3, pp 123) have shown that the analysis you use in Lines 241-250 is not the most appropriate for this situation. Please explain why you used this method.

Your introduction needs more detail. I suggest that you improve the description at lines 57- 86 to provide more justification for your study (specifically, you should expand upon the knowledge gap being filled).

The English language should be improved to ensure that an international audience can clearly understand your text. Some examples where the language could be improved include lines 23, 77, 121, 128 – the current phrasing makes comprehension difficult. I suggest you have a colleague who is proficient in English and familiar with the subject matter review your manuscript, or contact a professional editing service.

- 1. Your most important issue*
- 2. The next most important item*
- 3. ...*
- 4. The least important points*

I thank you for providing the raw data, however your supplemental files need more descriptive metadata identifiers to be useful to future readers. Although your results are compelling, the data analysis should be improved in the following ways: AA, BB, CC

I commend the authors for their extensive data set, compiled over many years of detailed fieldwork. In addition, the manuscript is clearly written in professional, unambiguous language. If there is a weakness, it is in the statistical analysis (as I have noted above) which should be

improved upon before Acceptance.

Transformation of the pectoral girdle in pennaraptorans : critical steps in the formation of the modern avian shoulder joint

Qian Wu^{Corresp., 1, 2, 3}, Jingmai K. O'Connor⁴, Shiyong Wang⁵, Zhonghe Zhou^{2, 3}

¹ University of Chinese Academy of Sciences, Beijing, China

² Key Laboratory of Vertebrate Evolution and Human Origins, Institute of Vertebrate Paleontology and Paleoanthropology, Chinese Academy of Sciences, Beijing, China

³ CAS Center for Excellence in Life and Paleoenvironment, Beijing, China

⁴ Negaunee Integrative Research Center, Field Museum of Natural History, Chicago, The United States of America

⁵ College of Paleontology, Shenyang Normal University, Shenyang, China

Corresponding Author: Qian Wu
Email address: wuqian@ivpp.ac.cn

Important transformations of the pectoral girdle are related to the appearance of flight capabilities in the Dinosauria. Previous studies on this topic focused mainly on paravians yet recent data suggests flight evolved in dinosaurs several times, including at least once among non-avian paravians. Thus, to fully explore the evolution of flight-related avian shoulder girdle characteristics, it is necessary to compare morphology more broadly. Here, we present information from pennaraptoran specimens preserving pectoral girdle elements, including all purportedly volant taxa, and extensively compare aspects of the shoulder joint. The results show that many pectoral girdle modifications appear during the evolution from basal pennaraptorans to paravians, including changes in the orientation of the coracoid body and the location of the articulation between the furcula and scapula. These modifications suggest a change in forelimb range of motion preceded the origin of flight in paravians. During the evolution of early avialans, additional flight adaptive transformations occur, such as the separation of the scapula and coracoid and reduction of the articular surface between these two bones, reduction in the angle between these two elements, and elongation of the coracoid. The diversity of coracoid morphologies and types of articulations joining the scapula-coracoid suggest that each early avialan lineage evolved these features in parallel as they independently evolved more refined flight capabilities. In early ornithothoracines, the orientation of the glenoid fossa and location of the acrocoracoid approaches the condition in extant birds, suggesting a greater range of motion in the flight stroke, which may represent the acquisition of improved powered flight capabilities, such as ground take-off. The formation of a new articulation between the coracoid and furcula in the Ornithuromorpha is the last step in the formation of an osseous

triosseal canal, which may indicate the complete acquisition of the modern flight apparatus and the ability to perform sustained flight over large distances. These morphological transitions equipped birds with a greater range of motion, increased and more efficient muscular output and while at the same time transmitting the increased pressure being generated by ever more powerful flapping movements in such a way as to protect the organs. The driving factors and functional adaptations of many of these transitional morphologies are as yet unclear although ontogenetic transitions in forelimb function observed in extant birds provide an excellent framework through which we can explore the behavior of Mesozoic pennaraptorans.

Transformation of the pectoral girdle in pennaraptorans: critical steps in the formation of the modern avian shoulder joint

Qian Wu ^{1,2,3}, Jingmai K. O'Connor ⁴, Shiyong Wang ⁵, Zhonghe Zhou ^{2,3}

¹ University of Chinese Academy of Sciences, Beijing, China

² Key Laboratory of Vertebrate Evolution and Human Origins, Institute of Vertebrate Paleontology and Paleoanthropology, Chinese Academy of Sciences, Beijing, China

³ CAS Center for Excellence in Life and Paleoenvironment, Beijing, China

⁴ Negaunee Integrative Research Center, Field Museum of Natural History, Chicago, IL, U.S.A.

⁵ Shenyang Normal university

Corresponding Author:

Qian Wu ¹

142 Xizhimenwai Dajie, Beijing, 100040, China

Email address: wuqian@ivpp.ac.cn

Abstract

Important transformations of the pectoral girdle are related to the appearance of flight capabilities in the Dinosauria. Previous studies on this topic focused mainly on paravians yet recent data suggests flight evolved in dinosaurs several times, including at least once among non-avian paravians. Thus, to fully explore the evolution of flight-related avian shoulder girdle characteristics, it is necessary to compare morphology more broadly. Here, we present information from pennaraptoran specimens preserving pectoral girdle elements, including all purportedly volant taxa, and extensively compare aspects of the shoulder joint. The results show that many pectoral girdle modifications appear during the evolution from basal pennaraptorans to paravians, including changes in the orientation of the coracoid body and the location of the articulation between the furcula and scapula. These modifications suggest a change in forelimb range of motion preceded the origin of flight in paravians. During the evolution of early avialans, additional flight adaptive transformations occur, such as the separation of the scapula and coracoid and reduction of the articular surface between these two bones, reduction in the angle between these two elements, and elongation of the coracoid. The diversity of coracoid morphologies and types of articulations joining the scapula-coracoid suggest that each early avialan lineage evolved these features in parallel as they independently evolved more refined flight capabilities. In early ornithothoracines, the orientation of the glenoid fossa and location of the acrocoracoid approaches the condition in extant birds, suggesting a greater range of motion in the flight stroke, which may represent the acquisition of improved powered flight capabilities, such as ground take-off. The formation of a new articulation between the coracoid and furcula in the Ornithuromorpha is the last step in the formation of an osseous triosseal canal, which may indicate the complete acquisition of the modern flight apparatus and the ability to perform sustained flight over large distances. These morphological transitions equipped birds with a greater range of motion, increased and more efficient muscular output and while at the same time transmitting the increased pressure being generated by ever more powerful flapping movements in such a way as to protect the organs. The driving factors and functional adaptations of many of these transitional morphologies are as yet unclear although ontogenetic transitions in forelimb function observed in extant birds provide an excellent framework through which we can explore the behavior of Mesozoic pennaraptorans.

INTRODUCTION

The pectoral girdle, formed by the scapula, coracoid, and furcula, connects the forelimbs and trunk of tetrapods and provides the attachment point (origin) for the muscles involved in forelimb locomotion; thus, its morphology is crucial for forelimb function (McGonnell, 2001; Benton, 2014). There have been many transformations in the morphology of the pectoral girdle that occurred during the evolution from non-avian maniraptoran theropod dinosaurs (hereafter simply maniraptorans or theropods) to birds (Avialae) as summarized by previous studies, such as the elongation of the coracoid body from a quadrangular (often described as trapezoidal) to strut-like morphology, the separation of the scapula and coracoid from a fused (or connected by long suture prior to fusion) scapulocoracoid to separate bones articulating through a ball and socket joint, the change in the angle demarcated by the scapulocoracoid from obtuse to acute, the orientation of the glenoid fossa from caudoventral to dorsolateral, the elongation of the acrocoracoid process (homologous to “coracoid tubercle” or “biceps tubercle” of theropods) and the rotation of the coracoid body from laterally facing to craniocaudally then ventrally facing (Turner, Makovicky & Norell, 2012; Lü et al., 2016; Wang, Stidham & Zhou, 2018; Novas et al., 2021b). The osseous triosseal canal is an important feature of extant birds that was absent in non-avian theropods, forming a pulley-like passage that guides the motion of the main muscle responsible for the upstroke, the *m. supracoracoideus* (Mayr, 2021; Wang et al., 2022b). This canal is formed by the acromion process of the scapula, the acrocoracoid process of the coracoid and the epicleideal process of the furcula, mainly through the coracoscapular joint, the scapuloclavicular joint and the acrocoracoclavicular joint (Baumel et al., 1993; Ando & Fukata, 2018). These changes of the scapula-coracoid were accompanied by the appearance of medial fusion of the sternal plates forming a sternum and a decrease in the interclavicular angle of the furcula.

Traditionally, birds were considered the only volant dinosaurian lineage and research seeking to understand flight related transformations focused on birds and their closest relatives, the Troodontidae and Dromaeosauridae, which all together form the clade Paraves. The Troodontidae and Dromaeosauridae together form the Deinonychosauria, which is commonly resolved as the sister group to Avialae (Turner, Makovicky & Norell, 2012; Sullivan, Xu & O’Connor, 2017). However, recent discoveries suggest that some form of volant ability likely evolved several times independently in the Maniraptora: in the Scansoriopterygidae,

Microraptorinae (Dromaeosauridae), Unenlaginae (Dromaeosauridae), and Avialae (Sullivan, Xu & O'Connor, 2017; Pei et al., 2020). All maniraptorans considered to have some volant capabilities belong to the plesiomorphically terrestrial clade Pennaraptora (Fig.1) (Pol & Goloboff, 2020; Pei et al., 2020). Pennaraptora is a node-based clade, defined as the last common ancestor of *Oviraptor philoceratops* Osborn, 1924, *Deinonychus antirrhopus* Ostrom, 1969, and *Passer domesticus* Linnaeus, 1758, and all its descendants (Foth, Tischlinger & Rauhut, 2014). The Pennaraptora consists of Paraves together with the Oviraptorosauria and Scansoriopterygidae, the latter commonly regarded as a basal lineage of the former (Gianechini et al., 2018; Pittman & Xu, 2020). Pennaceous feathers, which are crucial for flight in at least the Microraptorinae and Avialae, are only found in pennaraptorans (Lefèvre et al., 2020; Pittman & Xu, 2020).

In light of the recent discovery of volant abilities in scansoriopterygids, to fully understand the evolution of flight-related pectoral girdle characters we must explore the pectoral girdle morphology beyond Paraves to include a wider range of taxa across all of Pennaraptora. Furthermore, the continuous discovery of new taxa and specimens means that summaries of morphology and disparity pertaining to particular anatomical regions need to be regularly updated, especially in light of the increasing availability of computed tomographic (CT) data that reveals anatomical features in 3D and greater clarity. For example, reduction of the angle between the scapula and coracoid was once thought to be an avialan feature but recently was reported to be also less than 90° in the troodontid *Liaoningvenator* (Shen et al., 2017). In order to better understand flight related morphological transformations of the shoulder girdle features, here we utilize available data concerning the morphology of the pectoral girdle across pennaraptorans to summarize the variation, make comparisons between clades and taxa, and discuss the possible relationship between these transformations and changes in forelimb function as it pertains to the evolution of flight. This study will provide detailed information about the morphological and functional comparison of the shoulder girdle of pennaraptors for paleontologist who are interested in the evolution of pennaraptors and the origin of flight in early birds.

SURVEY METHODOLOGY

We collect specimens of pennaraptors reported in literatures and focus on those preserved shoulder girdle elements. The characters of shoulder girdle of different taxa of pennaraptors are re-evaluated and compared based on text and figures from the origin literatures, and listed in Table S1. We further listed those charectors that are considered to be closely related to flight evolution in table 1.

Phylogenetic framework

We follow the recent phylogeny by Pol and Goloboff (2020), in which Pennaraptora is formed by Oviraptorosauria, Scansoriopterygidae, Dromaeosauridae, Troodontidae and Avialae (Fig. 1). ‘*Scansoriopteryx*’ is interpreted as a junior synonym of *Epidendrosaurus* (Padian, 2004; Feduccia, Lingham-Soliar & Hinchliffe, 2005). *Ingenia yanshini* (Barsbold, 1981) was renamed as *Ajancingenia yanshini* (Easter, 2013), and later the genus name ‘*Ajancingenia*’ is considered to be synonym of *Heyuannia* (Funston et al., 2018), which is also accepted here. Anchiornithidae is interpreted as early diverging members of Avialae (Pol & Goloboff, 2020). ‘*Aurornis*’ is considered a junior synonym of *Anchiornis* (Pei et al., 2017). As part of the extant phylogenetic bracket, additional comparative morphological data comes from extant crocodilians, which like dinosaurs are archosaur reptiles.

Nomenclature

The anatomical nomenclature primarily follows Baumel et al. 1993, and osteological structures are described using the English equivalents of Latin terms. The “coracoid tubercle” (or coracoid tuber) or “biceps tubercle” in theropods is considered homologous with the modern avian “acrocoracoid process” (Ostrom, 1976). For convenience, this feature is referred to as the “acrocoracoid process” throughout; similarly, the posteroventral process of the coracoid in dinosaurs is homologous with and here referred to as the sternolateral process, as it is called in birds. The main surface of the coracoid is here referred to as the coracoid body. The orientation of the coracoid in birds is described as dorsoventral; we adopt this nomenclature for non-avialan pennaraptorans in which the coracoid has rotated from lateral facing to ‘anterior’ facing.

137 Institutional Abbreviations

138 AMNH, American Museum of Natural History, New York, USA; BMNHC, Beijing Museum of
 139 Natural History, Beijing, China; BPM, Beipiao Paleontological Museum, Liaoning, China;
 140 CAGS, China Academy of Geological Sciences, Beijing, China; DNHM, Dalian Natural History
 141 Museum, Dalian, China; GMNH, Ganzhou Museum of Natural History, Ganzhou City, Jiangxi
 142 Province, China; GMV, Geological Museum of China, Beijing, China; GSGM, Gansu
 143 Geological Museum, Lanzhou, China; HGM, Henan Geological Museum, Henan, China;
 144 HYMV, Heyuan Museum, Guangdong, China; IGM, Institute of Geology, Ulaan Battar,
 145 Mongolia; IVPP, Institute of Vertebrate Paleontology and Paleoanthropology, Beijing, China;
 146 MACN, Sección Paleontología de Vertebrados, Museo Argentino de Ciencias Naturales, Buenos
 147 Aires, Argentina; MCCM, Museo de Cuenca, Cuenca, Spain; MCF, Museo Carmen Funes, Plaza
 148 Huinul, Argentina; MCPA, Museo Provincial “Carlos Ameghino,” Cipolletti, Patagonian,
 149 Argentina; MNU, Mongolian National University, Mongolia; MPC, Institute of Paleontology
 150 and Geology, Mongolian Academy of Sciences, Ulaanbaatar, Mongolia; MPC-NEE, Nemegt
 151 Educational Expedition field number, specimens housed at the Institute of Paleontology and
 152 Geology, Mongolian Academy of Sciences, Ulaanbaatar, Mongolia; MPD, Mongolia
 153 Palaeontological Centre, Mongolia; MTM, Hungarian Natural History Museum, Budapest,
 154 Hungary; LPM, Liaoning Paleontology Museum, Shenyang Normal University, Shenyang,
 155 China; PIN, Paleontological Institute, Russian Academy of Sciences, Moscow, Russia; PMOL,
 156 Palaeontological Museum of Liaoning, China; PVL, Paleontologia de Vertebrados Lillo,
 157 Universidad Nacional de Tucuman, Tucuman, Argentina; SMM, Sternberg Memorial Museum,
 158 Kansas, USA; STM, Shandong Tianyu Museum of Nature, Shandong, China; TMP, Royal
 159 Tyrrell Museum of Palaeontology, Drumheller, Alberta, Canada; UA, Université
 160 d’Antananarivo, Antananarivo, Madagascar; YGFP, Yizhou Fossil and Geology Park, Yizhou,
 161 China; YPM, Yale Peabody Museum, New Haven, Connecticut, USA.

COMPARE OF PENNARAPTORAN PECTORAL GIRDLE

1. Oviraptorosauria

In oviraptorosaurs, the scapula and coracoid are fused or tightly articulated through a long synchondrosis (Osmólska, Currie & Barsbold, 2004), with the angle between the scapula and coracoid exceeding 90° as observed in *Tongtianlong* DYM-2013-8, *Heyuannia* HYMV1-2 and 1-5, and *Avimimus* PIN 3907-1 (Table S1) (Kurzanov, 1981). Previously, this articulation was described as a “suture” in some specimens (Makovicky & Sues, 1998; He, Wang & Zhou, 2008; Funston et al., 2018). However, this is a misapplication of the term. In anatomy, a “suture” indicates the rigid fibrous joint between membranous bones, such as the sutures in the skull (Hall, 2005; Ding & Liu, 2018). Since both the scapula and coracoid are endochondral bones, the appropriate term for such a tight articulation through cartilage should be “synchondrosis”, as in extant crocodilians (Brochu, 1995).

Most oviraptorosaur specimens identified as adults have fused scapulocoracoids (Table S1), except for one specimen of *Caudipteryx* IVPP V12430 (Zhou & Wang, 2000) which is a small individual and may in fact be immature. The scapula and coracoid are unfused (including fully separated and joined through synchondrosis) in 16 out of 27 reported oviraptorosaur species (Table S1), all of which are based on material that is inferred to be ontogenetically immature (juvenile or subadult) (Table S1), as in *Yulong* HGM 41HIII-0107 (Lü et al., 2013a), *Rinchenia* MPC-D 100/32A (Funston et al., 2018) and *Gobiraptor* MPC-D 102/111 (Lee et al., 2019). This evidence strongly suggests that fusion of the synchondrosis joint of the scapulocoracoid is related to ontogeny in oviraptorosaurs as in extant crocodilians (Brochu, 1995), and that the scapulocoracoid is fused in adults (Funston et al., 2021).

The glenoid fossa of oviraptorosaurs is described as caudoventrally oriented (Osmólska, Currie & Barsbold, 2004), as in *Oksoke* MPC-C 102/110 (Funston, 2020), *Avimimus* MPC-NEE.2016-257 (Funston et al., 2018), *Anzu* CM 78000 (Lamanna et al., 2014) and others (Table S1). Recently, the glenoid was described as laterally oriented in some oviraptorids, such as *Heyuannia* HYMV1-2 (Lü, 2003; Lü, Huang & Qiu, 2005), *Khaan* IGM 100/1002 (Balanoff & Norell, 2012), and *Apatoraptor* TMP 1993.051.0001 (Funston & Currie, 2016). Although the glenoid fossa of *Khaan* is indeed oriented more laterally than other oviraptorosaurs, being ventrolaterally rather than caudoventrally oriented (Fig. 2A) (Balanoff and Norell, 2012), the 2D

preservation of *Apatoraptor* makes interpretations equivocal for this taxon. The figure of *Heyuannia* HYMV1-2 in the original publication does not show the glenoid fossa since it is shield by the humerus, and in *Heyuannia* MPC-D 100/30 the glenoid fossa appears to be caudoventrally oriented (Fig. 2D). In light of such equivocal evidence, we prefer to be conservative about the orientation of glenoid fossa in oviraptorosaurs in which preservation is not clear and consider that the glenoid is caudoventrally oriented in the majority of taxa with the possible exception of the Late Cretaceous oviraptorid *Khaan*, in which changes in orientation are clearly apomorphic. Clearly, caudoventral orientation of the glenoid represents the plesiomorphic condition although a shift in the orientation of this articular surface may have evolved independently in some derived oviraptorid lineages by the Late Cretaceous.

The acromion process of the scapula is well developed and inflected craniolaterally in oviraptorosaurs (Fig. 2) (Osmólska, Currie & Barsbold, 2004; Balanoff & Norell, 2012), as in *Khaan* IGM 100/1002 (Balanoff & Norell, 2012), *Oksoko* MPC-D 102/110 (Funston et al., 2020) and *Heyuannia* MPC-D 100/30 (Osmólska, Currie & Barsbold, 2004), providing a sizeable articular surface along the dorsal edge of the scapula for the furcula (Balanoff & Norell, 2012). The joint between the acromion and furcula is clearly visible in *Rinchenia* and *Nankangia*, whose acromion and furcula are preserved in articulation (Fig 2) (Lü et al., 2013b; Funston et al., 2018). *Caudipteryx* was previously described as without a prominent acromion process (Zhou et al., 2000), but re-examination reveals that its acromion process is similar to other oviraptorosaurs (Fig. 2F). The acromion process is close to but still caudal to the articular surface of scapula and coracoid in oviraptorosaurs (Fig. 2), with the exception of *Elmisaurus* which has an acromion located a significant distance caudal to the scapula and coracoid articulation (Funston et al., 2021). Accordingly the acromion and furcula articulation may also be more caudally located in *Elmisaurus*.

In most oviraptorosaurs, the scapulocoracoid is axe-like in shape (with the scapula representing the handle of the axe and the coracoid representing the blade). The coracoid itself is mediolaterally oriented and trapezoidal, with relatively short and straight cranial and omal margins, a concave caudal margin and a convex sternal margin (Fig. 2) (Osmólska, Currie & Barsbold, 2004). A prominent acrocoracoid process (coracoid tubercle) is located on the craniolateral surface of the coracoid (fig. 2) (Osmólska, Currie & Barsbold, 2004), generally located below the coracoid foramen, if the latter is present, as in *Heyuannia* MPC-D 100/30

(Osmólska, Currie & Barsbold, 2004), *Oksoko* MPC-D 100/30 (Funston et al., 2020), *Chirostenotes* TMP 1979.020.0001 (Funston, 2020) and *Microvenator* AMNH 3041 (Makovicky & Sues, 1998). The sternal end of the coracoid is craniocaudally expanded with a sternolateral process, and articulated with the transverse groove on the craniodorsal edge of the sternum in oviraptorids (Osmólska, Currie & Barsbold, 2004). While in *Caudipteryx* the sternal plates are oval and separate, and as preserved they lack sternal processes, as in BPM001 and IVPP V 12344, so the coracoid and sternal plates may connect in a different way like by soft tissue, which needs further investigation on previous specimens to reveal (Ji et al., 1998; Zhou et al., 2000; Zhou & Wang, 2000).

The coracoid in *Avimimus* was originally described as elongated based on specimen PIN #3907/1 (Kurzanov, 1981) and later described as triangular (MPC-NEE.2016-257) (Funston et al., 2018). Funston et al. states that the triangular shape of the coracoid in *Avimimus* is due to the enlargement of the cranioventral part (Funston et al., 2018). However, given the morphological difference between the coracoid in these two specimens, and the poor preservation of *Avimimus* specimens, it cannot be ruled out that this unusual morphology is a preservational artifact.

2. Scansoriopterygidae

Scansoriopterygids are hypothesized to have a unique form of gliding flight utilizing a forelimb membrane supported by the apomorphic elongate third digit and styliiform process (Xu et al., 2015; Wang et al., 2019; Dececchi et al., 2020). There is no consensus as to their phylogenetic position. They have been regarded as members of the Oviraptorosauria (Agnolín & Novas, 2013; O'Connor & Sullivan, 2014; Brusatte et al., 2014; Pittman & Xu, 2020; Pei et al., 2020), early-diverging paravians (O'Connor & Sullivan, 2014; Wang et al., 2019), or even avialans (Senter, 2007; Zhang et al., 2008; Xu et al., 2011). Unlike the abundant remains available for other pennaraptoran clades, scansoriopterygids are exceedingly rare, with only four species, *Epidendrosaurus* (Zhang et al., 2002; Czerkas and Yuan, 2002), *Epidexipteryx* (Zhang et al., 2008), *Yi* (Xu et al., 2015) and *Ambopteryx* (Wang et al., 2019), each known from a single specimen with the exception of *Epidendrosaurus* (known from two immature specimens). The scansoriopterygid affinity of *Zhongornis* is controversial (Gao et al., 2008; O'Connor & Sullivan, 2014), hence it will not be considered here.

The scapula and coracoid are unfused in *Epidendrosaurus* IVPP V12653, *Epidexipteryx* IVPP V15471, and *Ambopteryx* IVPP V24192 (Fig. 3, table S1), but all these specimens represent individuals that are interpreted as juvenile or subadult (Czerkas & Yuan, 2002; Zhang et al., 2002, 2008; Wang et al., 2019). The holotype of *Yi* is considered to be an adult, but only the scapula is preserved (Xu et al., 2015). Therefore, additional specimens are needed to determine if the scapula and coracoid fuse in adult scansoriopterygids.

Although described simply as subquadrilateral (Czerkas & Yuan, 2002; Zhang et al., 2008), the scansoriopterygid coracoid varies in shape. The coracoids of the young juvenile represented by *Epidendrosaurus* IVPP V12653 and CAGS02-IG-gausa-l/DM 607 are unusual small. *Ambopteryx* IVPP V24192 has a trapezoidal coracoid with concave lateral margin (Fig. 3A) (Wang et al., 2019), while the coracoid of *Epidexipteryx* IVPP V15471 is polygonal (Fig. 3C) (Zhang et al., 2008). Given the poor preservation of these specimens, it is impossible to determine from the currently available evidence whether or not these morphological differences are genuine. Due to the two-dimensional preservation of available specimens, there is insufficient data to make further comparison of the shoulder girdle joint in this clade.

3. Troodontidae

In troodontids the scapula and coracoid are connected through a long synchondrosis (Fig. 3D-K), which may become fused in adults, as in *Jinfengopteryx* CAGS-IG-04-0801 (Ji et al., 2005) and *Pneumatoraptor* V.2008.38.1 (Ősi, Apesteguía & Kowalewski, 2010). These two elements are separate in juvenile specimens, e.g., *Mei* IVPP V12733 (Xu & Norell, 2004). This suggests the fusion of the scapula and coracoid in troodontids is also influenced by ontogeny, as in oviraptorosaurs. The angle between the scapula and coracoid are equal to or slightly less than 90° (Fig. 3D-K and Table S1), forming a smaller angle than observed in oviraptorosaurs. The glenoid is oriented caudoventrally, as in *Gobivenator* MPC-D 100/86, *Linhevenator* LHV0021 and *Liaoningvenator* DNHM D3012 (Fig. 3D), but is also weakly oriented laterally in some species, e.g., *Sinovenator* (Wang et al., 2022b). As in oviraptorosaurs, it is unclear to what degree this variation is an artifact of preservation.

The acromion of troodontids is well developed (Fig. 3). In *Gobivenator* (Tsuihiji et al., 2014), *Troodon* (Gilmore, 1924), and *Sinovenator* (Wang et al., 2022b), the acromion is located dorsally at the same level as the articular surface for the coracoid, which is cranial to its position

in oviraptorosaurs (Fig. 2). The acromion and furcula of *Sinornithoides* IVPP V9612 are preserved in articulation (Currie & Dong, 2001), which shows that the articular surface for the furcula is at the cranial tip of the acromion (Fig. 3), whereas in oviraptorosaurs it is located on the dorsal edge (Fig. 1, 2).

Different from the lateral facing coracoid in oviraptorosaurs, *Mei* IVPP V12733 and DNHM D2514, which are three-dimensionally preserved in articulation, and *Sinovenator* (Wang et al., 2022b) show that the body of the coracoid is rotated so that it is facing cranial (Xu & Norell, 2004; Gao et al., 2012). As a result, when the tightly articulated or fused scapulocoracoid is preserved in lateral view, only the narrow lateral margin of the coracoid is visible, showing a cranially projecting acrocoracoid process that forms an L-shaped scapulocoracoid, as in *Sinovenator* IVPP V12615 (Xu et al., 2002), *Liaoningvenator* DNHM D 3012 (Shen et al., 2017), and *Pneumatoraptor* MTM 2008.38.1 (Ósi, Apesteguía & Kowalewski, 2010). As in oviraptorosaurs, in troodontids the coracoid body is trapezoidal in cranial view, with the omal and medial margins relatively straight, a lateral margin concave, and convex sternal margin (Fig. 3D-K), and well-developed sternolateral and acrocoracoid processes, e.g., in *Mei* IVPP V12733 (Xu & Norell, 2004; Gao et al., 2012), *Gobivenator* MPC-D 100/86 (Tsuihiji et al., 2014), and *Sinovenator* IVPP V12615 (Wang et al., 2022b). The coracoid of *Sinovenator* IVPP V12615 possesses an acrocoracoid process nearly at the same level as the coracoid foramen (Wang et al., 2022b), more dorsally located than that in the oviraptorosaurs.

4. Dromaeosauridae

The pectoral girdle of non-volant dromaeosaurids such as *Velociraptor* IGM 100/986, *Deinonychus* AMNH 3015, *Achillobator* MNU FR-15, and other velociraptorines is quite similar to that of oviraptorosaurs (Fig. 4A-C) (Ostrom, 1974; Norell & Mackovicky, 1999; Perle, Norell & Clark, 1999). Their fused scapulocoracoids preserve a similar axe-like morphology to that observed in oviraptorosaurs (Fig. 2), but differ from troodontids (Fig. 3D-K), indicating that the coracoid may still be laterally facing as in oviraptorosaurs. The angle between the scapula and coracoid is also obtuse (from 120° to 135°) as in oviraptorosaurs (Fig. 2; Fig. 4A-C). The glenoid fossa of *Deinonychus* AMNH 2013 shows a similar caudoventral orientation to that of more basal theropods (Ostrom, 1974), as does that of *Velociraptor* whose osseous floor of the glenoid fossa is mostly visible in caudal view in specimen IGM 100/986 (Norell & Mackovicky, 1999).

The Boomerang-shaped furcular of the *Velociraptor* IGM 100/976 was preserved attach with the well developed acromion, as in troodontids (Norell & Mackovicky, 1999).

As in oviraptorosaurs, the coracoid of non-volant dromaeosaurids is trapezoidal in lateral view, with the cranial and sternal margins slightly convex, and the caudal margin concave with a hooked sternal lateral process in *Velociraptor* IGM 100/986 and *Deinonychus* AMNH 3015 (Fig. 4A, B) (Ostrom, 1974; Norell & Mackovicky, 1999). The acrocoracoid process is not very pronounced and is located near the caudal margin of the coracoid in *Velociraptor* IGM 100/986 and *Deinonychus* AMNH 3015 (Fig. 4A, B) (Ostrom, 1974; Norell & Mackovicky, 1999). These *Velociraptor* specimens are relatively derived in the phylogeny, as indicated by their long and curved claws and enlarged semilunate carpal bones. These features may be secondary adaptations related to their forelimb function, such as grasping prey or climbing trees. Velociraptorines are relatively derived dromaeosaurids in the phylogenetic analysis (Fig. 1). These features may be secondary adaptations related to their forelimb function.

In contrast, dromaeosaurids with flight potential (e.g., the *Unenlagiinae*, *Microraptor*, and *Bambiraptor*) show significant changes in the morphology of the pectoral girdle (Fig. 4). In species of the Microraptorinae, the scapulocoracoid is fused in adult specimens of *Microraptor*, e.g. CAGS 20-7-004 (Hwang et al., 2002), but unfused in the juvenile holotype of *Wulong* DNHM D2933 (Poust et al., 2020). This pattern is consistent with the oviraptorosaurs and troodontids. Although the scapula and coracoid are unfused in *Sinornithosaurus* IVPP V12811, whose relatively large size suggests it may be an adult individual (Xu, Wang & Wu, 1999), its scapula and coracoid are tightly articulated, and preserved in a state similar to *Microraptor* IVPP V13352 (Xu et al., 2003), indicating the individual may have died just prior to fusion. In *Buitreraptor* MCPA 245 and MPCN-PV-598, the scapula and coracoid are tightly articulated as in *Sinornithosaurus* IVPP V12811, with marked rugosities that indicate ongoing fusion on the coracoidal articular surface (Brochu, 1995; Parsons & Parsons, 2015; Gianechini et al., 2018; Novas et al., 2018). A similarly rugose articular surface is also observed on the scapula of *Unenlagia* MCF PVPH 78 (Novas et al., 2021a). The only exception is the smooth coracoid facet on the scapula of *Rahonavis* UA 8656 (Forster et al., 2020), which suggests a derived avian-like coracoscapsular joint that is apomorphic in *Rahonavis* and may be related to flight capabilities in this taxon.

In these potentially volant dromaeosaurids, the articular surface between the scapula and coracoid is shortened from the long condition in oviraptorosaurs, troodontids, and velociraptorine dromaeosaurids, to a more localized facet, as in *Bambiraptor* AMNH FR 30554, *Rahonavis* UA 8656 (Forster et al., 1998) and *Wulong* D2933 (Poust et al., 2020). When preserved in lateral view, only the narrow lateral margin of the cranially facing coracoid is visible, as in *Buitreraptor* (MPCN-PV-598), *Microraptor* IVPP V13353 and *Sinornithosaurus* IVPP V12811 (Fig. 4) (Xu, Wang & Wu, 1999; Xu et al., 2003; Novas et al., 2018), which confirms the cranial rotation of the coracoid body as in troodontids. The angle between the scapula and coracoid ranges from 90 to 100°, smaller than in oviraptorosaurs and non-volant dromaeosaurids (Fig. 2; Fig. 4A-C). The glenoid fossa of potentially volant dromaeosaurids is oriented laterally, as in *Bambiraptor* AMNH FR 30554 (Burnham, 2004), *Sinornithosaurus* IVPP V12811 (Xu, Wang & Wu, 1999), *Microraptor* IVPP V13353 and LHV 0026 (Xu et al., 2003; Gong et al., 2012), and *Changyuraptor* HG B016 (Han et al., 2014), which more closely approaches the condition in birds than that of velociraptorine dromaeosaurids and most troodontids, whose glenoid fossa oriented to caudoventrally as mentioned previously (Table S1 and Fig. 4).

The acromion process of the scapula of these potentially volant dromaeosaurids is very well developed, and is elongated cranially, extending over the articular surface to the coracoid, as clearly preserved in *Bambiraptor* AMNH FR 30554, *Sinornithosaurus* IVPP V12811, *Rahonavis* UA 8656 and *Unenlagia* MCF PVP 78 (Fig. 4). In volant dromaeosaurids, the coracoid is mediolaterally narrow forming a distinct neck below the glenoid fossa and scapula articular surface that separates the omal articular surface from the coracoid body, as observed in *Bambiraptor* AMNH FR 30554, *Wulong* D2933 and *Sinornithosaurus* IVPP V12811 (Fig. 4) (Burnham, 2004). This neck of the coracoid of *Bambiraptor* was considered to be the caused by loss of the medial margin of the coracoid which also occurs in *Buitreraptor* MPCN-PV-598 and MPCA 245 (Gianechini et al., 2018; Novas et al., 2018). However, in previous description the author stated that the left coracoid of *Bambiraptor* is complete (Burnham, 2004), and similar morphology is also observed in microraptorines. Then the neck of the coracoid is probably not a preservation artifact but a feature that occurs in the common ancestor of *Bambiraptor* and microraptorines and lost in velociraptorines, or equally parsimonily a homoplasy of these two taxa, independent of similar modifications observed in the avialan lineage.

The acrocoracoid process is well developed and located close to the glenoid fossa, as preserved in *Bambiraptor* MNH FR 30554 (Burnham, 2004), *Zhongjianosaurus* IVPP V22775 (Xu, Qin & Palasiatica, 2017), *Tianyuraptor* STM1-3 (Zheng et al., 2010), *Wulong* D2933 (Poust et al., 2020), and *Sinornithosaurus* IVPP V12811 (Xu, Wang & Wu, 1999). When the coracoid foramen is present, the acrocoracoid process is located between the foramen and the glenoid fossa, as in *Sinornithosaurus* IVPP V12811 (Xu, Wang & Wu, 1999).

5. Anchiornithidae

Anchiornithidae includes the most basal know clade of avialan, such as *Anchiornis*, *Eosinopteryx*, *Xiaotingia* and *Serikornis* (Pol & Goloboff, 2020). The phylogenetic placement of the Anchiornithidae has been contentious. It has been placed within Troodontidae (Xu et al., 2011; Lee & Worthy, 2012; Brusatte et al., 2014; Gianechini, Ercoli & Díaz-Martínez, 2020), or resolved as an early diverging lineage of avialans (Pittman & Xu, 2020). One recent study found that anchiornithids have potential for partially powered flight similar to that inferred for *Microraptor*, *Rahonavis*, *Jeholornis*, and *Confuciusornis* (Pei et al., 2020).

Hundreds of specimens of *Anchiornis* have been reported (Xu et al., 2009; Hu et al., 2009; Pei et al., 2017; Guo, Xu & Jia, 2018). Among them, the scapula and coracoid of the relative smaller specimen BMNHC PH 804 (humerus length 44.5-45.7 mm) are connected but unfused (Pei et al., 2017), while a larger specimen LPM-B00169 (humerus length 69.0 mm) is described as having a fused scapulocoracoid (Hu et al., 2009). In other anchiornithids known from single specimens the two elements are separate (Fig. 5A-D), e.g., in *Eosinopteryx* YFGP-T5197, *Xiaotingia* STM 27-2, and *Serikornis* PMOL-AB00200 (Xu et al., 2011; Godefroit et al., 2013; Lefèvre et al., 2017). Claims that the holotypes of *Eosinopteryx* and *Xiaotingia* are based on adult material are equivocal (Xu et al., 2011; Godefroit et al., 2013), and the only known specimen of *Serikornis* is considered by some to be a subadult (Lefèvre et al., 2017). Therefore, we suggest that the synchondrosis between the scapula and coracoid in anchiornithids fuses late in ontogeny, as in oviraptorosaurs and other non-avialan paravians.

Anchiornithids have a smaller articular surface between the scapula and coracoid than observed in oviraptorosaurs and troodontids (as in *Xiaotingia* STM 27-2 and *Serikornis* PMOL-AB00200), a laterally oriented glenoid fossa as in *Anchiornis* IVPP V14378 (Fig. 5A), an approximate right angle formed by the scapula and coracoid in lateral view (Fig. 5A) (Hu et al.,

2009). In lateral view, the fused scapulocoracoid of *Anchiornis* LPM-B00169 is “L-shape”, indicating the cranial orientation of the coracoid body (Fig. 5A). However, in contrast to *Microraptor*, the acromion of anchiornithids is not elongated cranially over the coracoid articular surface (Fig. 5A-D), resembling the condition in oviraptorosaurs (Fig. 2). The coracoid of *Anchiornis* BMNH PH804 and *Eosinopteryx* YFGP-T5197 is trapezoidal in cranial view with expanded sternal ends and concave lateral margin (Xu et al., 2009; Hu et al., 2009; Godefroit et al., 2013), resembling the plesiomorphic pennaraptoran condition. While in *Serikornis* PMOL-AB00200, the concave medial margin of the coracoid resembling that of the volant dromaeosaurids is probably a preservational artifact since the coracoid is overlapped by the furcula (Lefèvre et al., 2017).

Thus, it is not strictly correct to say that condition in anchiornithids is closer to birds than that of volant dromaeosaurids like *Microraptor*. Some characters but not all are consistent with birds whereas others resemble more basal pennaraptorans. This is consistent with the limited powered flight capacity inferred from their feather structure, forelimb proportions, and homoplasy related to the repeated evolution of flight in pennaraptorans (Pei et al., 2020), and suggests acquisition of some flight adaptive skeletal features in volant dromaeosaurids or the common ancestor of dromaeosaurids independent and in parallel to avialans.

6. Basal birds (non-ornithothoracine avialans)

Basal birds here representative non-ornithothoracine avialans, including long tail birds such as the *Archaeopteryx* (here regards as the most basal birds) and *Jeholornis*, basal pygostylians *Sapeornis*, as well as confuciusornithids and jinguofortisids, clades that are interpreted as crownward of *Jeholornis* and *Sapeornis* (Wang, Stidham & Zhou, 2018; Wang, O'Connor & Zhou, 2019; Wu et al., 2021b). The body plan of basal birds is highly diverse, differing in the morphology of the skull, tail, and the pectoral girdle (O'Connor, Chiappe & Bell, 2011). All birds possess a localized articular surface between the scapula and coracoid (Fig. 5E-H), e.g., *Archaeopteryx* 10th specimen (Ostrom, 1976; Elzanowski, 2001; Chiappe & Witmer, 2002; Rauhut, Foth & Tischlinger, 2018), *Jeholornis* IVPP V13274 and V13886 (Zhou & Zhang, 2002; Wang et al., 2022b), *Sapeornis* IVPP V13276 (Zhou & Zhang, 2003a; Wang et al., 2022b), and *Confuciusornis* IVPP V16066 (Fig. 5H) (Li, 2010), but the joint type between the scapula and coracoid is unclear.

Although these two elements were thought to be separate in most basal birds, like *Archaeopteryx*, *Jeholornis* and *Sapeornis* (Zhou & Zhang, 2003a; Mayr, Pohl & Peters, 2005; Wang, Stidham & Zhou, 2018), fusion of the scapulocoracoid was also reported in the Maxberg, Solnhofen, and Munich specimens of *Archaeopteryx* (Wellnhofer, 2009), as well as in the Confuciusornithidae and Jinguoformisidae (Wang, Stidham & Zhou, 2018; Wang, O'Connor & Zhou, 2019; Wu et al., 2021b). Hence, the scapula and coracoid may evolve to be unfused in basal birds crownward of *Archaeopteryx*, with that in the Confuciusornithidae and Jinguoformisidae being secondarily fused (Fig. 1) (Wu et al., 2021a). Alternatively, separation between the scapula and coracoid evolved independently in *Jeholornis*, *Sapeornis* and Ornithothoracines or in a clade formed by *Sapeornis* and Ornithothoracines (the sister taxon to Ornithothoracines is alternatively resolved as either *Sapeornis* or the Confuciusornithidae in various published phylogenetic analyses) (Gianechini et al., 2018; Wang, Stidham & Zhou, 2018; Agnolin et al., 2019; Wang et al., 2022a) – both interpretations are equally parsimonious.

However, a tightly connected scapula and coracoid forming an L-shape in lateral view are present in all non-ornithothoracines basal birds [e.g., *Jeholornis* YGFP-yb2 (Lefèvre et al., 2014), *Sapeornis* IVPP V12698 (Zhou & Zhang, 2003a)], resembling the preservation in some troodontids, dromaeosaurids, and anchiornithids (Fig. 2-5). This is not observed in the ornithothoracines (Fig. 6, 7). Considering that precise ontogenetic age is unverified through histology in most specimens, the absence of fusion between these two elements in basal birds may also be due to somatic immaturity in most specimens, as in non-avian pennaraptorans, and the separate, unfused scapula and coracoid may have only evolved in ornithothoracines. However, even if the scapula and coracoid of basal birds crownward of *Archaeopteryx* do not become fused with somatic maturity as in other early pennaraptorans, the joint between these two elements is still clearly different from that of ornithothoracines, in which the two elements are clearly preserved free (and not forming the “L-shape” in lateral view). In contrast to other basal birds, the scapula and coracoid of *Confuciusornis* become fused early in ontogeny well before skeletal maturity, forming a synostosis. This is considered an autapomorphy of this lineage (Wang, O'Connor & Zhou, 2019; Wu et al., 2021a).

The angle between the scapula and coracoid of basal birds is less than 90°, except for *Archaeopteryx*, in which the angle is approximately 90° (Fig. 5E). The lateral orientation of the glenoid fossa in *Sapeornis* (Wang et al., 2022b), *Archaeopteryx* (Rauhut, Foth & Tischlinger,

2018), and *Confuciusornis* (Martin et al., 1998; Li, 2010) are similar to the condition in volant dromaeosaurids and anchiornithids (Fig. 4, 5A-D). The glenoid fossa of *Jeholornis* IVPP V13353 and YFGP-yb2 was dorsolaterally oriented (Zhou & Zhang, 2003b; Lefèvre et al., 2014), but the humeral articular surface of the scapula is oriented laterally in STM 2-37 and IVPP V13886 (O'Connor et al., 2013; Wu et al., 2021a; Wang et al., 2022b). Deformation is a common phenomenon in fossil preservation. Based on the preservation status of majority specimens, we tend to believe that the glenoid fossa of *Jeholornis* is laterally oriented, as in other basal birds (Fig. 5E,G,H).

The scapular acromion process in basal birds is elongate and extends cranially over the coracoid articular surface (Fig. 5E-H) (Chiappe et al., 1999; Zhou and Zhang, 2003; Wellnhofer, 2009; Lefèvre et al., 2014), to articulate with the epicleideal process of furcula along its cranial tip as in ornithothoracines (Fig. 1) (Wang et al., 2022b). The acromion of *Archaeopteryx* is dorsally deflected slightly (Fig. 5E), while that of the *Jeholornis* and *Sapeornis* extends cranially (Fig. 5F, G) (Zhou & Zhang, 2003a; Wang et al., 2022b). The acromion of *Confuciusornis* appears to be less developed, developed only as a small bump in lateral view (Fig. 1D). The epicleideal process of the furcula was proposed to articulate with a small process on the medial side of the scapulocoracoid of *Confuciusornis* (Wu et al., 2021b). These two features together with the fused scapulocoracoid, make *Confuciusornis* a morphological outlier among basal birds.

Reconstructions based on 3D CT data demonstrate that the scapuloclavicular joint moved from dorsal side of the coracoscapular joint in non-avian pennaraptorans, to the medial side of the coracoscapular joint in ornithothoracines, and some basal birds like *Sapeornis* (Fig. 1, 5G) (Wang et al., 2022b). Under the latter circumstances, the acromion of the scapula is not visible when the pectoral girdle is in lateral view (Fig. 1) (Wang et al., 2022b). Hence, the acromion process of *Confuciusornis* may extend cranially along the medial side of the pectoral girdle like more derived ornithothoracines, and the small medial side process in articulation with the furcula found by Wu et al. (Wu et al., 2021b) may in fact be the cranial end of the acromion process, and the joint between is the scapuloclavicular joint rather than the coracoclavicular joint.

In *Jeholornis*, the acromion process is visible in dorsally preserved scapula of specimens like IVPP V13353 and YFGP-yb2 (Zhou & Zhang, 2003b; Lefèvre et al., 2014), but not in lateral view on either side of the fused scapulocoracoids of STM2-19 (O'Connor et al., 2018). Additionally, given the similarities between the shoulder girdle of *Jeholornis* and more

crownward birds, like the procoracoid process and acrocoracoid process, we believe that the scapuloclavicular joint is more likely to be medial than the coracoscapular joint, as in the *Confuciusornis* and *Sapeornis*. In contrast, in some other basal birds as *Archaeopteryx*, the cranial tip of the acromion (to which the furcula articulates) is clear visible in lateral view of the fused scapulocoracoid in lateral view (Fig. 5E) (Wellnhofer, 2009; Lefèvre et al., 2014), indicating the scapuloclavicular joint is still located dorsal than the coracoscapular joint.

The morphology of the coracoid in non-ornithothoracine birds varies greatly. *Archaeopteryx* has a plesiomorphically subquadrilateral coracoid with a shortened omal end, convex medial margin and concave lateral margin, and a acrocoracoid process that is located more dorsal than the supracoracoid foramen and almost level with the glenoid fossa (fig. 5E) (Ostrom, 1976; Mayr et al., 2005). The coracoid of *Sapeornis* is similar to that of the *Archaeopteryx* in shape, but the acrocoracoid process is more dorsocranially elongated, and located at the same level as the glenoid fossa (Fig. 5G) (Zhou and Zhang, 2003; Wang et al., 2022), as is the acrocoracoid process of *Jeholornis* and *Confuciusornis* (Fig. 5F, H) (Zhang et al., 2009; Li, 2010; Lefèvre et al., 2014), which is more dorsally located and prominent compared to non-avian paravians (Fig. 3-5).

Although elongated relative to more basal taxa and thus described as “strut-like”, the morphology of the coracoid in *Jeholornis* and *Confuciusornis* show some differences to that of extant birds, having a relative thicker coracoid ‘neck’ (Fig. 5F, H). This fairly robust coracoid neck is also observed in the stem-most ornithuromorph *Archaeorhynchus* IVPP V17091 (Zhou et al., 2013). The coracoid of *Jeholornis* is unique relative to that in other basal birds with a well-developed procoracoid process (Fig. 5F) (Turner, Makovicky & Norell, 2012; Lefèvre et al., 2014), being the stem-most appearance of this feature but represents a local apomorphy. The procoracoid process in *Jeholornis* is located on the omal portion of the medial margin of the coracoid, directed dorsomedially and at the same level as the large supracoracoid foramen (Turner, Makovicky & Norell, 2012; Lefèvre et al., 2014; Wang et al., 2022b). The procoracoid process may participate in the coracoscapular joint of *Jeholornis*, as in some extant birds (Baumel et al., 1993; Wang et al., 2022b).

7. Non-neornithine Ornithothoraces

Ornithothoraces comprises the sister groups: Enantiornithes and Ornithuromorpha, and the latter includes crown birds (Neornithes) (Livezey & Zusi, 2007; Wang, Stidham & Zhou, 2018). The pectoral girdle of non-neornithine ornithothoracines displays the essential morphological characteristics of extant birds, including an unfused scapula and coracoid, strut-like and ventrally oriented coracoid body, coracoscaphular joint located medial and not dorsal to the glenoid fossa, glenoid fossa located below the pronounced acrocoracoid process and oriented dorsolaterally, well-developed acromion process of the scapula elongated cranially over the coracoid articular surface, and articular surface with the furcula on the cranial tip of the scapular acromion (Chiappe & Witmer, 2002; Zhou, 2013). Although the disarticulation of the scapula and coracoid prevent accurate measurement of the scapula-coracoid angle, the morphology of the articular surfaces and CT reconstructions support an acute angle as in extant birds in both enantiornithines and ornithuromorphs (Mayr, 2017; Wang et al., 2022b).

Except for the presence of an acrocoracoid dorsal to the glenoid fossa, and dorsolaterally oriented glenoid fossa, other derived characters were already in place in basal birds. Among the three main joints forming the triosseal canal in extant birds, two have formed a similar state in non-neornithine ornithothoracines, even in some basal birds, namely the scapuloclavicular joint between the omal tip of the epicleideal process of the furcula and the cranial tip of the acromion process of the scapula, as well as the unfused and localized coracoscaphular joint between the scapula and coracoid (see the previous analysis). This indicates that the joint between the epicleideal process of the furcula and the acrocoracoid process of the coracoid is the last evolutionary step in the formation of an osseous triosseal canal. Besides these similarities, there are significant differences between the pectoral girdle of these two clades discussed separately below.

7.1 Enantiornithes

The scapular acromion process of the scapula in enantiornithines is well developed and elongated cranially, extending over the articular surface to the coracoid (Fig. 6). In most enantiornithines, the acromion is bend medially, except for *Concornis* and Pengornithidae, which have a hooked acromion (Fig. 6 B, L) (Zhou, Clarke & Zhang, 2008; Hu, Zhou & O'Connor,

2014; Wang et al., 2014; Hu, O'Connor & Zhou, 2015; Serrano et al., 2018). Most enantiornithines, with the exception of some of the Pengornithidae, have a straight acrocoracoid process that extends dorsally. The acrocoracoid is straight in *Eopengornis* STM 24-1 (Wang et al., 2014), slightly medially inclined in Pengornithid indet. IVPP V18632 (Hu, Zhou & O'Connor, 2014), but very weakly developed in *Parapengornis* IVPP V18687 (Hu, O'Connor & Zhou, 2015). The procoracoid process on the coracoid is absent with the exception of the basal *Protopteryx* IVPP V11844 and BMNHC Ph 1158 (Fig. 6), which has a small, triangular, procoracoid-like medial process (Zhang & Zhou, 2000; Chiappe et al., 2019a).

The scapular articular surface of the coracoid is weakly convex and the coracoid articular surface of the scapula is concave, which is opposite the condition in extant birds and considered to be an autapomorphy and diagnostic feature of enantiornithines. However, recent discoveries may challenge this view. In *Alethoalaornis* LPM00009 the coracoid articular surface on the scapula is reportedly slightly convex (Li et al., 2007) but this cannot be confirmed in the provided figures and preservation in these specimens is poor making support for this interpretation unlikely in this taxon. In the basal pengornithids *Parapengornis* IVPP V18687 and Pengornithid indet. V18632, the scapular articular surface on the coracoid is shallowly concave suggesting this feature is not diagnostic of the entire clade or that the condition in pengornithids is an autapomorphy of this clade (Wang et al., 2022b). The phylogenetic position of the Pengornithidae is controversial (Zelenkov, 2017), and requires further study.

3D reconstructions based on CT data show that the distance between the acrocoracoid process and the epicleideal process in enantiornithines is relatively far, indicating that both an articulation between these two elements like that in extant birds and a bony, closed triosseal canal are absent in this clade (Wang et al., 2022b).

7.2 Non-neornithine Ornithuromorpha

In contrast to enantiornithines, the articular surface between the scapula and coracoid in non-neornithine ornithuromorphs is convex on the scapula and concave on the coracoid, as in *Yixianornis* IVPP V12631, *Mengciusornis* IVPP V26275, *Gansus* CAGS-IG-04-CM-003, and *Ichthyornis* YPM 1733 (Fig. 7) (Zhou & Zhang, 2001; Clarke, 2002; You et al., 2006; Wang et al., 2020). This morphology is often described as a “ball and socket” joint (Turner, Makovicky & Norell, 2012), but this interpretation is debated (Mayr, 2021). Furthermore, a flat articular

surface for the scapula on the coracoid has evolved in crown birds at least 13 times (Mayr, 2021).

Except for *Apsaravis* IGM 100/1017 (Clarke & Norell, 2002), *Patagopteryx* MACN-N-11 (Chiappe, 1996; Chiappe & Witmer, 2002), and *Baptornis* KUV 2290 (Bell & Chiappe, 2020), all known Mesozoic ornithuromorphs possess a procoracoid process on the coracoid, including the Late Cretaceous flightless *Hesperornis* (Fig. 7). Instead of a well-developed procoracoid process, *Apsaravis* IGM 100/1017 possess a very slight bulging on the medial surface of the coracoid (Clarke & Norell, 2002), which may actually be the residual of a secondarily reduced or taphonomically lost procoracoid process. The procoracoid process has been lost in flightless *Patagopteryx* (Chiappe, 1996; Chiappe & Witmer, 2002), *Baptornis* KUV 2290 (Bell & Chiappe, 2020), and many neornithines as well, such as the volant *Pavo muticus* (Wang et al., 2022b), and flightless *Thambetochen chauliodus* (Feduccia, 1981). However, in the coracoid of some flightless taxa such as the Mesozoic *Pasquiaornis* RSM P1988.9 (Bell & Chiappe, 2020) and extant *Struthio camelus* (Vickaryous & Hall, 2006) the procoracoid process is retained, hence the relationship between the loss of the procoracoid process and flight in birds is unclear.

The acrocoracoid process in volant ornithuromorphs is well developed (Fig. 7) and more robust than that of enantiornithines (Fig. 6). This process varies from straight [as in *Archaeorhynchus* IVPP V17091 (Zhou, Zhou & O'Connor, 2013), *Hongshanornis* IVPP 14533 (Zhou & Zhang, 2005), and *Yanornis* IVPP V12558 (Zhou & Zhang, 2001), fig. 7], to medially inflected [as in *Yixianornis* IVPP V12631 (Zhou & Zhang, 2001), *Gansus* CAGS-IG-04 CM-004 (You et al., 2006), and *Mengciusornis* IVPP V26275 (Wang et al., 2020)], to hooked in some members of the derived, Late Cretaceous clade Ornithurae [as in *Ichthyornis* YPM 1733 (Clarke, 2004)]. The ‘neck’ of the coracoid of the basal ornithuromorph *Archaeorhynchus* IVPP V17091 is broader than that of other ornithuromorphs (fig. 7) (Zhou and Zhang, 2006; Zhou et al., 2013), but whether the acrocoracoid process has an articular surface for the furcula cannot be determined from the preservation of currently available specimens. In at least one Early Cretaceous ornithuromorph *Yixianornis* IVPP V13631, the articular surface is clearly visible on the medial surface of the acrocoracoid process (Clarke, Zhou & Zhang, 2006), resembling the articular surface in extant birds (Baumel et al., 1993) and indicating the presence of a modern triosseal canal in *Yixianornis*.

8. Secondarily flightless birds

There are several Mesozoic birds that are interpreted as secondarily flightless, e.g. *Patagopteryx*, *Elsornis*, and *Hesperornis* (Chiappe & Witmer, 2002; Chiappe et al., 2007). Flightlessness has also evolved many times in different lineages of crown birds, such as *T. chauliodus* (Anatidae) (Olson & Wetmore, 1976), *Strigops habroptilus* (Psittaciformes) (Livezey, 1992), several lineages of paleognaths (Houde, 1986), species of Phorusrhacidae (Cariamiformes) (Alvarenga & Höfling, 2003), and many island rails (Rallidae) (Olson, 1973).

Among these birds whose flight capability is secondarily reduced, the pectoral girdle shows some important morphological changes including (Fig. 5I-M): fusion of the scapula and coracoid in the flightless paleognaths, as in the ostrich (McGowan, 1982); decrease in the relative proportions of the forelimb and pectoral girdle relative to entire skeleton, as in flightless paleognaths and flightless rails (Olson, 1973); increase in the scapulocoracoid angle to 90°, as in flightless rails and *Strigops* (Olson, 1973; Livezey, 1992), or greater, as in flightless paleognaths (McGowan, 1982); reduction of the scapular acromion and acrocoracoid process of the coracoid, resulting in the glenoid located at the proximal end of coracoid rather than below it, as in flightless paleognaths and *Patagopteryx* (McGowan, 1982; Chiappe & Witmer, 2002); increase in the space between the left and right sternal articulation of the coracoids, as in *Patagopteryx*, *Strigops* and flightless paleognaths (McGowan, 1982; Livezey, 1992; Chiappe & Witmer, 2002); degeneration of the furcula, into two separate clavicles as in *Strigops* (Livezey, 1992), reduced and unfused clavicles in the ostrich and even the complete loss of the furcula in the kiwi (McGowan, 1982); as well as the loss of the triosseal canal as in the flightless paleognaths (McGowan, 1982). These characters represent the complete spectrum of pectoral girdle degeneration observed in different flightless lineages, though all these features do not simultaneously co-occur in any single species. Among these pectoral girdle transformations, the fusion of the scapula and coracoid, obtuse scapulocoracoid angle, degeneration of the scapular acromion and acrocoracoid processes, and loss of the osseous triosseal canal resemble the plesiomorphic conditions variably observed in non-avian pennaraptorans (Fig. 2).

MORPHOLOGY AND FUNCTION TRANSFORMATIONS OF PENNARAPTORAN PECTORAL GIRDLE ASSOCIATED WITH FLIGHT EVOLUTION

The pectoral girdle morphology changed dramatically during pennaraptoran evolution from oviraptorosaurs to birds, including (but not limited to) the location and morphology of the coracoscavular joint and the scapuloclavicular joint, the location and orientation of the glenoid fossa, the morphology and orientation of the coracoid, procoracoid and acrocoracoid process of the coracoid, and acromion process of the scapula (Fig. 1, table 1). These can be divided into three main transformations.

First, the change in the orientation of the glenoid fossa, from the caudovernal orientation in oviraptorosaurs (Osmólska, Currie & Barsbold, 2004), to relatively lateral orientation in volant dromaeosaurids and basal birds (Pittman & Xu, 2020; Wang et al., 2022b), culminating in the dorsolateral orientation present in ornithothoracines (Fig. 1) (Baumel et al., 1993). This transformation allowed the forelimb of ornithothoracines greater range of motion and to be fully elevated dorsally above the vertebral column to accommodate the extensive wing stroke utilized in the powered, flapping flight of modern birds.

Animals with laterally oriented glenoid fossae can certainly extend the forelimb laterally to glide as in extant birds, but may not be able to perform effective flapping wing-strokes, being limited in their dorsal amplitude. The humeral articular surface on the scapula (scapular half of the glenoid) in the basal bird *Sapeornis* is concave and possesses a raised lip along the dorsal to caudal margin (Wang et al., 2022b), which would have been further accentuated *in vivo* by cartilage tissue. Thus dorsal movement of the wing of the *Sapeornis* would likely have been prevented, limiting the vertical range of its wing-stroke and thus the amount of lift generated by its flapping motion. This is somewhat consistent with interpretations that *Sapeornis* would have relied primarily on soaring flight (Bell & Chiappe, 2011; Serrano & Chiappe, 2017; Serrano et al., 2020). However, soaring birds must be able to flap to achieve soaring altitude, which may suggest that *Sapeornis* instead utilized gliding flight. A reduction in wing loading can offset this limitation to some extent, but wing loading in basal birds is not considered to be significantly lower than that of ornithothoracines (Pei et al., 2020). This strongly suggests limits in the powered flight ability present in some basal birds, specifically the ability for ground take-off and sustained long distance flight, which require greater lift than passive gliding flight. This is also

consistent with the presence of claws on the hands of basal birds that can be used for climbing and resemble those present in juvenile *Hoatzins* (Abourachid et al., 2019).

Thus, extensive flapping motion of the forelimb similar to extant birds probably did not evolve until the appearance of a laterodorsally oriented glenoid fossa in ornithothoracines. This coincides with the appearance of a sternal keel, which provided an expanded surface for the attachment of the *m. pectoralis major*, the main muscle responsible for the down-stroke of the wing beat. The appearance of both a glenoid that permits the full range of flapping movement and increased surface area for the muscle that powers it in ornithothoracines may suggest fully equipped powered flight is limited to this clade. Further increases in the size of the sternal keel in ornithuromorphs relative to enantiornithines indicate the ability to generate greater power and lift through the wing stroke. Enlarged sternal keel likely evolved in parallel in enantiornithines by the Late Cretaceous, as evidenced by the well developed sternal keel present in *Neuquenornis* (Chiappe & Calvo, 1994). This may suggest ornithuromorphs were not only able to take-off from the ground, but also able to continuously fly for longer distances, which requires continuous power output from a large *m. pectoralis major*. This is consistent with interpretations that Early Cretaceous enantiornithines may be unable to sustain prolonged flight, but prefer to intermittent flight styles such as bounding or flap-gliding flight (Liu et al., 2017; Serrano et al., 2018; Chiappe et al., 2019a,b).

The second critical transformation is the formation of the triosseal canal. This is the most complex morphological transformation because of the greater number of elements involved. As the passage of the tendon of the *m. supracoracoideus*, the triosseal canal changes the *m. supracoracoideus* from protractor in early pennaraptorans to elevator of the humerus in ornithothoracines (Novas et al., 2020, 2021b), providing the muscular power for the upstroke during flapping flight. Compared to extant birds, basal pennaraptorans lack the acrocoracoclavicular joint between the coracoid and furcula and have only two joints between the three pectoral girdle elements at their omal ends (the long synchondrosis coracoscapular joint and the scapuloclavicular joint along the dorsal edge of the acromion of the scapula), which further differ in their morphology compared to extant birds. Hence, the transformation from the pennaraptoran to ornithothoracine condition involves morphological changes in the coracoscapular and the scapuloclavicular joints, as well as the formation of the acrocoracoclavicular joint.

This transformation involves: 1) a reduction in the articular surface between the scapula and coracoid from the long synchondrosis (which may fuse in adults) in oviraptorosaurs (as in *Khaan*) to localized articular surfaces in potential volant dromaeosaurids (as in *Rahonavis*) and avialans (as in *Anchiornis*); 2) cranial migration and enlargement of the acromion process of the scapula, from caudal to the scapula-coracoid articular surface in oviraptorosaurs (e.g., *Khaan* and *Heyuannia*) to elongate and cranially oriented in potential volant dromaeosaurids (as in *Bambiraptor*) and avialans crownward of anchiornithids; 3) change in the articulation between the scapula and furcula from contacting along the dorsal edge of the scapular acromion (as in oviraptorosaurs) to the cranial tip of this process (as in paravians) which freed the remainder of the furcular epicleideal process; and 4) the migration of the acrocoracoid process from below the supracoracoid foramen (as in oviraptorosaurs) to above (dorsal) the glenoid fossa (as in ornithothoracines). The last two morphological transformations facilitated the appearance of the acrocoracoclavicular joint between the furcular epicleideal process and the coracoid acrocoracoid process in the Ornithuromorpha. Notably, some of these transformations (e.g., 1, 2) evolved multiple times independently with the repeated evolution of flight in pennaraptorans.

The fully closed, bony triosseal canal was present in at least some early Cretaceous basal ornithuromorphs, such as *Yixianornis*, as indicated by the articular surface for the furcula visible on the acrocoracoid process. Further research on early diverging ornithuromorphs will help clarify the appearance of this feature. However, it is worth noting that a bony, closed triosseal canal may not be necessary to achieve the pulley function of the *m. supracoracoideus* (Novas et al., 2021b; Wang et al., 2022b). Soft tissues like the acrocoraco-acromial ligament may also help to close the supracoracoid canal for the passage of the *m. supracoracoideus* (Ando & Fukata, 2018; Novas et al., 2021b). In this regards, although enantiornithines do not possess a bony closed triosseal canal, the morphology of the pectoral girdle may still permit the *m. supracoracoideus* to function as a pulley as in extant birds (Wang et al., 2022b).

This raises questions as to the function of the additional acrocoracoclavicular joint present in ornithuromorphs, and suggests that the function of the triosseal canal may not be limited to the pulley-like motion of the *m. supracoracoideus*. The acrocoracoclavicular joint in extant birds shows considerable diversity: synovial joint, syndesmosis, and synostosis are all observed (Baumel et al., 1993; Wu et al., 2021b). The significance of this diversity and how it affects avian flight is unclear. During the flight stroke in extant birds, the acrocoracoclavicular joint

shows slight displacement together with the movement of the coracoid and the deformation of the furcula (Baier, Gatesy & Dial, 2013), suggesting this joint may play a role in the flight stroke, possibly facilitating the continuous flapping movement in ornithuromorphs. Research focused on the acrocoracoclavicular joint is limited and further analysis of the anatomy, histology and function of this joint will help reveal its role in avialan flight evolution.

In addition to the acrocoracoid process, acromion process and epicleidial process, the procoracoid process is also mentioned as an important component of the triosseal canal (Baumel et al., 1993). *Jeholornis* is the stem-most appearance of this feature and the only basal bird to possess a procoracoid process (Zheng et al., 2020). Mesozoic ornithuromorphs and the stem-most enantiornithine *Protopteryx* all have procoracoid processes, indicating the procoracoid process evolved at least twice during bird evolution, independently evolving in *Jeholornis* and the common ancestor of ornithothoracines (Zheng et al., 2020). Loss of the procoracoid process in enantiornithines more derived than *Protopteryx* may be secondary, or this feature may have evolved independently in *Protopteryx*. The procoracoid process of certain extant birds is also reduced, such as in the Phasianidae and Passeriformes (Oswald & Steadman, 2015; Wang et al., 2022b). This questions the contribution of the procoracoid process to the triosseal canal and its relation to flight ability. The evolution and secondary loss of the procoracoid process warrants further investigation.

The third major aspect of this transformation is the change in morphology and orientation of the coracoid and the reduction in the angle between the scapula and coracoid. The coracoid elongates from trapezoidal in early pennaraptorans to narrow and strut-like in birds (Turner, Makovicky & Norell, 2012). However, elongation of this element has also evolved independently in other non-avialan volant pennaraptorans and the trapezoidal morphology is retained in the basal birds *Archaeopteryx* and *Sapeornis*. The coracoid body also rotates from laterally oriented in early pennaraptorans to ventrally oriented in paravians, with only the lateral margin (caudal margin of more basal pennaraptorans), acrocoracoid process and sternal project visible in lateral view, forming an L-shaped scapulocoracoid (Fig. 1).

During avian flight, the pectoral girdle transmits the lift generated by the wing to the body (Pennycuick, 1967). A strut-like coracoid effectively resists the pressure of the muscles on the thorax when flapping, preventing damage to the thoracic and visceral structures (King & Mclelland, 1984; Gill, 2007), while the coracoid itself experiences great pressure (Samour,

2015). With the same bone mass, narrow strut-like coracoids can have thicker cortical bone compared to the wide and flat axe-like coracoid, permitting this bone to withstand higher pressure without causing damage. This may suggest that elongation of the coracoid indicates flapping, powered flight.

The change in coracoid orientation from lateromedial in early pennaraptorans to dorsoventral in paravians, including non-volant troodontids (Pei et al., 2020), suggests this modification may be related to forelimb and pectoral girdle functions other than powered flight, like sexual display, predation, or nest manipulation. As such, the rotation of the coracoid lay the foundation for the evolution of powered flight in birds and can be considered as an exaptation for flight evolution. The same is true for the cranial migration of the scapuloclavicular joint in paravians (Fig. 1). Alternatively, rotation of the coracoid towards the midline of the body may indicate some form of volant behavior was plesiomorphic to Paraves (or a more inclusive group), as has been previously suggested (Xu et al., 2015; Sullivan, Xu & O'Connor, 2017).

In paravians with ossified sternal plates the coracoid articulates in a groove on the cranial margin of the sternum (Burnham, 2004; Zheng et al., 2014; Cau et al., 2021). During powered flight in extant birds, the coracoid moves lateromedially within this groove to assist the flapping movement of the wing (Baier, Gatesy & Dial, 2013; Razmadze, Panyutina & Zelenkov, 2018), whereas in early pennaraptorans, the laterally oriented coracoid was more likely to move craniocaudally and a groove-like articulation with the sternal plates was likely absent in basal taxa, such as *Caudipteryx*. This morphological change and rotation of the coracoid coincided with a decrease in the angle formed by the scapula-coracoid from obtuse in early pennaraptorans, to approximately 90° in non-avian paravians, to an acute angle in basal birds crownward of *Archaeopteryx* (Fig. 1). The acute angle reduces the length of the dorsal elevator muscles (Gill, 2007), therefore decreasing the time required for the muscle to contract, allowing the wing to be uplifted faster. In extant birds, it can be clearly seen that the time required for the upstroke is shorter than the downstroke, which also experiences greater resistance as it pushes against the air (Rayner, 1988; Biewener, 2011). Except for the specialized condition in hummingbirds, the upstroke of extant birds does not generate lift (Biewener, 2011; Chin & Lentink, 2019), thus reduction of the time required to make the upstroke is beneficial to reduce altitude loss during powered flight.



793 It is proposed that flight capacity originated multiple times in pennaraptors (Wang et al.,
794 2019; Pei et al., 2020), especially in paravians, accompanied by occurrence of flight adaptive
795 features in different volant clades. Several avialian-like features are found in species of
796 Unenlagiinae, Microraptorinae and the taxon *Bambiraptor*, which is considered to belong to the
797 Saurornitholestinae, such as developed acromion process of scapula, reduced articular surface of
798 coracoscavular joint and lateral facing glenoid fossa. The occurrence of these features in several
799 dromaeosaurid clades suggests that these features may represent the plesiomorphic
800 dromaeosaurid condition, which evolved independently from those similar features in avialans.

801 The existence of these avialan-like plesiomorphic dromaeosaurid conditions is consistent
802 with the evolution of powered flight or nearly powered flight capacity in several dromaeosaurid
803 clades. This may support the alternative hypothesis that flight was plesiomorphic to Paraves and
804 secondarily lost, rather than evolved repeatedly or explain the repeated evolution of flight in
805 dromaeosaurids, because their plesiomorphic morphology provided the framework for potential
806 flight. Additionally, in microraptorines and *Bambiraptor*, the narrow neck of the coracoid differs
807 from the axe-like coracoid of early pennaraptorans, but represents an intermediate morphology
808 with the strut-like avian-like coracoid. In *Rahonavis*, the scapula and coracoid are unfused in
809 adult specimen UA 8656, resembling that of basal birds crownward of *Archaeopteryx* (expected
810 *Confuciusornis*), suggesting further development of powered flight capacity in at least some
811 unenlagiine dromaeosaurids independent from flight evolution in avialans.

812 However, these volant dromaeosaurids still lack some important flight adaptations of the
813 pectoral girdle that are found in birds, such as the strut-like coracoid, dorsolaterally oriented
814 glenoid fossa, and well developed acrocoracoid process dorsal than the glenoid fossa, suggesting
815 that if they were volant, they had limited flight capacity compared to ornithothoracine birds.
816 Their wings may have functioned to parachute from heights and glide short distances, but ground
817 takeoff and long distance continuous flight would have been challenging to these possibly volant
818 dromaeosaurids.

819 In avialans, the morphology of the pectoral girdle diversifies (e.g., the different coracoid
820 morphologies) as a product of the parallel refinement of the flight apparatus following the rapid
821 diversification of avialan lineages in the latest Jurassic. A modern-like pressure transition system
822 (strut-like coracoid) and glenoid fossa orientation characterizes the Ornithothoraces. The
823 acrocoracoclavicular joint evolves in the Ornithuromorpha and indicates the earliest appearance

of a fully closed bony triosseal canal. These transformations suggest that, although flight may have evolved several times in theropods, flight capabilities comparable to living birds were restricted to the Ornithuromorpha. The loss of some features (e.g., the acute angle between scapula and coracoid, well developed acromion of the scapula and acrocoracoid process of the coracoid, as well as the triosseal canal) in secondarily flightless birds, both Mesozoic and extant, further support inferences that these features are intrinsically linked to the evolution and refinement of dinosaurian flight.

CONCLUSIONS

Through the comparative analysis of pennaraptoran shoulder girdle characteristics, this study summarizes the major transformations of the pectoral girdle that appeared during the evolution of dinosaurian flight. These include changes in the orientation and position of the glenoid fossa, in the orientation and shape of the coracoid and the angle between the scapula and coracoid, the relative position of the acrocoracoid process of the coracoid, the articulation between the acromion of the scapula and the epicleideal process of the furcula, and the formation of the triosseal canal in birds. The three joints that link these pectoral girdle elements all are modified, including the morphology and position of the scapula-furcula joint, the morphology and type of the scapula-coracoid joint, and the formation of a new joint between the furcula and the coracoid.

Some character changes precede the rise of birds, but appear to be linked to the appearance of flight potential and the possible independent evolution of volant behavior in some non-avian pennaraptorans. The morphology of the pectoral girdle elements becomes further diversified in avialans, indicating different parallel attempts to refine flight performance in early birds from a flight apparatus tentatively limited to gliding or weak flapping flight, as in *Archaeopteryx*, to powered flight in ornithothoracines and possibly also *Jeholornis*. The glenoid fossa of the ornithothoracines could support similar forelimb flapping movement as observed in extant birds, and marks the appearance of a new joint between the coracoid and furcula, suggesting this clade had obtained fully equipped powered flight by the Early Cretaceous, only 20 million years after the appearance of the oldest known probable bird. The function of these morphological changes have been studied for decades as discussed here, yet some characteristics remain poorly understood. It is still unclear what is the functional difference between a fused and separate scapula-coracoid joint, or between the fully formed triosseal canal of ornithuromorphs and that

open canal present in enantiornithines. Additional fossil material and greater availability of 3D CT data will hopefully lend answers to these questions in the future.

Acknowledgements

We thank Wu Z. for illustration, Zhang Q. and Chen H. for discussion.

References

- Abourachid A, Herrel A, Decamps T, Pages F, Fabre A-C, Van Hoorebeke L, Adriaens D, Garcia Amado MA. 2019. Hoatzin nestling locomotion: Acquisition of quadrupedal limb coordination in birds. *Science Advances* 5:eaat0787. DOI: 10.1126/sciadv.aat0787.
- Agnolin FL, Motta MJ, Brissón Egli F, Lo Coco G, Novas FE. 2019. Paravian phylogeny and the dinosaur-bird transition: an overview. *Frontiers in Earth Science* 6. DOI: 10.3389/feart.2018.00252.
- Agnolín FL, Novas FE. 2013. Avian ancestors: a review of the phylogenetic relationships of coelurosaurian theropods closely related to birds. *Ameghiniana* 48.
- Alvarenga HM, Höfling E. 2003. Systematic revision of the *Phorusrhacidae* (Aves: Ralliformes). *Papéis Avulsos de Zoologia (São Paulo)* 43:55–91. DOI: 10.1590/S0031-10492003000400001.
- Ando T, Fukata K. 2018. A well-preserved partial scapula from Japan and the reconstruction of the triosseal canal of pterosaurs. *PeerJ* 6:e5391. DOI: 10.7717/peerj.5391.
- Baier DB, Gatesy SM, Dial KP. 2013. Three-dimensional, high-resolution skeletal kinematics of the avian wing and shoulder during ascending flapping flight and uphill flap-running. *PLoS ONE* 8:e63982. DOI: 10.1371/journal.pone.0063982.
- Balanoff AM, Norell MA. 2012. Osteology of *Khaan mckennai* (Oviraptorosauria: Theropoda). *Bulletin of the American Museum of Natural History* 2012:1–77. DOI: 10.1206/803.1.
- Barsbold R. 1981. Toothless carnivorous dinosaurs of Mongolia. *Trudy Sovmestnoi Sovetskoi Mongol'skoi Paleontologicheskoi Ekspeditsii* 15:28–39.
- Baumel JJ, King AS, Breazile JE, Evans HE, Berge JC. 1993. *Handbook of avian anatomy: nomina anatomica avium. Second Edition*. Cambridge: Nuttall Ornithological Club.

885 Bell A, Chiappe LM. 2011. Statistical approach for inferring ecology of Mesozoic birds. *Journal*
886 *of Systematic Palaeontology* 9:119–133. DOI: 10.1080/14772019.2010.525536.

887 Bell A, Chiappe LM. 2020. Anatomy of *Parahesperornis*: Evolutionary Mosaicism in the
888 Cretaceous Hesperornithiformes (Aves). *Life* 10:62. DOI: 10.3390/life10050062.

889 Benton MJ. 2014. *Vertebrate palaeontology*. John Wiley & Sons.

890 Biewener AA. 2011. Muscle function in avian flight: achieving power and control. *Philosophical*
891 *Transactions of the Royal Society B: Biological Sciences* 366:1496–1506. DOI:
892 10.1098/rstb.2010.0353.

893 Brochu CA. 1995. Heterochrony in the crocodylian scapulocoracoid. *Journal of Herpetology*
894 29:464. DOI: 10.2307/1565002.

895 Brusatte SL, Lloyd GT, Wang SC, Norell MA. 2014. Gradual assembly of avian body plan
896 culminated in rapid rates of evolution across the dinosaur-bird transition. *Current Biology*
897 24:2386–2392. DOI: 10.1016/j.cub.2014.08.034.

898 Burnham DA. 2004. New Information on *Bambiraptor feinbergi* (Theropoda: Dromaeosauridae)
899 from the Late Cretaceous of. *Feathered dragons: Studies on the transition from dinosaurs*
900 *to birds*:67.

901 Cau A, Beyrand V, Barsbold R, Tsogtbaatar K, Godefroit P. 2021. Unusual pectoral apparatus in
902 a predatory dinosaur resolves avian wishbone homology. *Scientific Reports* 11:14722. DOI:
903 10.1038/s41598-021-94285-3.

904 Chiappe LM. 1996. Late Cretaceous birds of southern South America: anatomy and systematics
905 of Enantiornithes and *Patagopteryx deferrariisi*. *Münchner Geowissenschaftliche*
906 *Abhandlungen* 30:203–244.

907 Chiappe LM, Calvo JO. 1994. *Neuquenornis volans*, a new Late Cretaceous bird (Enantiornithes:
908 Avisauridae) from Patagonia, Argentina. *Journal of Vertebrate Paleontology* 14:230–246.
909 DOI: 10.1080/02724634.1994.10011554.

910 Chiappe LM, Di L, Serrano FJ, Yuguang Z, Meng Q. 2019a. Anatomy and flight performance of
911 the early enantiornithine bird *Protopteryx fengningensis* : information from new specimens
912 of the Early Cretaceous Huajiyang Formation of China. *The Anatomical Record* 303:716–
913 731. DOI: 10.1002/ar.24322.

- Chiappe LM, Ji S, Ji Q, Norell MA. 1999. Anatomy and systematics of the Confuciusornithidae (Theropoda: Aves) from the late Mesozoic of northeastern China. *Bulletin of the American Museum of Natural History* 242:1–89.
- Chiappe LM, Meng Q, Serrano F, Sigurdson T, Wang M, Bell A, Liu D. 2019b. New *Bohaiornis*-like bird from the Early Cretaceous of China: enantiornithine interrelationships and flight performance. *PeerJ* 7:e7846. DOI: 10.7717/peerj.7846.
- Chiappe LM, Suzuki S, Dyke GJ, Watabe M, Tsogtbaatar K, Barsbold R. 2007. A new Enantiornithine bird from the Late Cretaceous of the Gobi desert. *Journal of Systematic Palaeontology* 5:193–208. DOI: 10.1017/S1477201906001969.
- Chiappe LM, Witmer LM. 2002. *Mesozoic birds: above the heads of dinosaurs*. Berkeley: University of California Press.
- Chin DD, Lentink D. 2019. Birds repurpose the role of drag and lift to take off and land. *Nature Communications* 10:1–10. DOI: 10.1038/s41467-019-13347-3.
- Clarke JA. 2002. The Morphology and Systematic Position of *Ichthyornis* Marsh and the Phylogenetic Relationships of Basal Ornithurae. PhD Thesis Thesis. Yale University.
- Clarke JA. 2004. Morphology, phylogenetic taxonomy, and systematics of *Ichthyornis* and *Apatornis* (Avialae: Ornithurae). *Bulletin of the American Museum of Natural History* 2004:1–179. DOI: 10.1206/0003-0090(2004)286<0001:MPTASO>2.0.CO;2.
- Clarke JA, Norell MA. 2002. The morphology and phylogenetic position of *Apsaravis ukhaana* from the Late Cretaceous of Mongolia. *American Museum Novitates* 2002:1–46. DOI: 10.1206/0003-0082(2002)387<0001:TMAPPO>2.0.CO;2.
- Clarke JA, Zhou Z, Zhang F. 2006. Insight into the evolution of avian flight from a new clade of Early Cretaceous ornithurines from China and the morphology of *Yixianornis grabaui*. *Journal of anatomy* 208:287–308. DOI: 10.1111/j.1469-7580.2006.00534.x.
- Currie PJ, Dong Z. 2001. New information on Cretaceous troodontids (Dinosauria, Theropoda) from the People’s Republic of China. *Canadian Journal of Earth Sciences* 38:1753–1766. DOI: 10.1139/e01-065.
- Czerkas SA, Yuan C. 2002. An arboreal maniraptoran from northeast China. *The Dinosaur Museum Journal* 1:63–95.

943 Dececchi TA, Roy A, Pittman M, Kaye TG, Xu X, Habib MB, Larsson HCE, Wang X, Zheng X.
944 2020. Aerodynamics Show Membrane-Winged Theropods Were a Poor Gliding Dead-end.
945 *iScience*:101574. DOI: 10.1016/j.isci.2020.101574.

946 Ding W, Liu X. 2018. *Systematic anatomy*. Beijing: People's Medical Publishing House.

947 Easter J. 2013. A new name for the oviraptorid dinosaur "*Ingenia*" *yanshini* (Barsbold, 1981;
948 preoccupied by Gerlach, 1957). *Zootaxa* 3737:184–190. DOI: 10.11646/zootaxa.3737.2.6.

949 Elzanowski A. 2001. A new genus and species for the largest specimen of *Archaeopteryx*. *Acta*
950 *Palaeontologica Polonica* 46.

951 Feduccia A. 1981. Cenozoic birds. *Paleobiology* 7:3–6. DOI: 10.1017/S0094837300003754.

952 Feduccia A, Lingham-Soliar T, Hinchliffe JR. 2005. Do feathered dinosaurs exist? Testing the
953 hypothesis on neontological and paleontological evidence. *Journal of Morphology* 266:125–
954 166. DOI: 10.1002/jmor.10382.

955 Forster CA, O'Connor PM, Chiappe LM, Turner AH. 2020. The osteology of the Late
956 Cretaceous paravian *Rahonavis ostromi* from Madagascar. *Palaeontologia Electronica*
957 23:a29.

958 Forster CA, Sampson SD, Chiappe LM, Krause DW. 1998. The theropod ancestry of birds: new
959 evidence from the Late Cretaceous of Madagascar. *Science* 279:1915–1919. DOI:
960 10.1126/science.279.5358.1915.

961 Foth C, Tischlinger H, Rauhut OWM. 2014. New specimen of *Archaeopteryx* provides insights
962 into the evolution of pennaceous feathers. *Nature* 511:79–82. DOI: 10.1038/nature13467.

963 Funston G. 2020. Caenagnathids of the Dinosaur Park Formation (Campanian) of Alberta,
964 Canada: anatomy, osteohistology, taxonomy, and evolution. *Vertebrate Anatomy*
965 *Morphology Palaeontology* 8:105–153. DOI: 10.18435/vamp29362.

966 Funston GF, Chinzorig T, Tsogtbaatar K, Kobayashi Y, Sullivan C, Currie PJ. 2020. A new two-
967 fingered dinosaur sheds light on the radiation of Oviraptorosauria. *Royal Society Open*
968 *Science* 7:201184. DOI: 10.1098/rsos.201184.

969 Funston GF, Currie PJ. 2016. A new caenagnathid (Dinosauria: Oviraptorosauria) from the
970 Horseshoe Canyon Formation of Alberta, Canada, and a reevaluation of the relationships of
971 Caenagnathidae. *Journal of Vertebrate Paleontology* 36:e1160910. DOI:
972 10.1080/02724634.2016.1160910.

Funston GF, Currie PJ, Tsogtbaatar C, Khishigjav T. 2021. A partial oviraptorosaur skeleton suggests low caenagnathid diversity in the Late Cretaceous Nemegt Formation of Mongolia. *PLOS ONE* 16:e0254564. DOI: 10.1371/journal.pone.0254564.

Funston GF, Mendonca SE, Currie PJ, Barsbold R. 2018. Oviraptorosaur anatomy, diversity and ecology in the Nemegt Basin. *Palaeogeography, Palaeoclimatology, Palaeoecology* 494:101–120. DOI: 10.1016/j.palaeo.2017.10.023.

Gao C, Chiappe LM, Meng Q, O’connor JK, Wang X, Cheng X, Liu J. 2008. A new basal lineage of Early Cretaceous birds from China and its implications on the evolution of the avian tail. *Palaeontology* 51:775–791. DOI: 10.1111/j.1475-4983.2008.00793.x.

Gao C, Morschhauser EM, Varricchio DJ, Liu J, Zhao B. 2012. A second soundly sleeping dragon: new anatomical details of the Chinese troodontid *Mei long* with implications for phylogeny and taphonomy. *PLoS ONE* 7. DOI: 10.1371/journal.pone.0045203.

Gianechini FA, Ercoli MD, Díaz-Martínez I. 2020. Differential locomotor and predatory strategies of Gondwanan and derived Laurasian dromaeosaurids (Dinosauria, Theropoda, Paraves): inferences from morphometric and comparative anatomical studies. *Journal of Anatomy* 236:772–797. DOI: 10.1111/joa.13153.

Gianechini FA, Makovicky PJ, Apesteguía S, Cerda I. 2018. Postcranial skeletal anatomy of the holotype and referred specimens of *Buitreraptor gonzalezorum* Makovicky, Apesteguía and Agnolín 2005 (Theropoda, Dromaeosauridae), from the Late Cretaceous of Patagonia. *PeerJ* 6:e4558. DOI: 10.7717/peerj.4558.

Gill FB. 2007. *Ornithology, 3rd Edition*. New York: W.H. Freeman and Company.

Gilmore CW. 1924. *On Troodon validus: An Orthopodous Dinosaur from the Belly River Cretaceous of Alberta, Canada*. University of Alberta Press.

Godefroit P, Cau A, Dong-Yu H, Escuillié F, Wenhao W, Dyke G. 2013. A Jurassic avialan dinosaur from China resolves the early phylogenetic history of birds. *Nature* 498:359–362. DOI: 10.1038/nature12168.

Gong E-P, Martin LD, Burnham DA, Falk AR, Hou L-H. 2012. A new species of *Microraptor* from the Jehol Biota of northeastern China. *Palaeoworld* 21:81–91. DOI: 10.1016/j.palwor.2012.05.003.

- Guo X, Xu L, Jia S. 2018. Morphological and phylogenetic study based on new materials of *Anchiornis huxleyi* (Dinosauria, Theropoda) from Jianchang, Western Liaoning, China. *Acta Geologica Sinica - English Edition* 92:1–15. DOI: 10.1111/1755-6724.13491.
- Hall BK. 2005. *Bones and cartilage: developmental and evolutionary skeletal biology*. Elsevier.
- Han G, Chiappe LM, Ji S-A, Habib M, Turner AH, Chinsamy A, Liu X, Han L. 2014. A new raptorial dinosaur with exceptionally long feathering provides insights into dromaeosaurid flight performance. *Nature Communications* 5:4382. DOI: 10.1038/ncomms5382.
- He T, Wang X, Zhou Z. 2008. A new genus and species of caudipterid dinosaur from the Lower Cretaceous Jiufotang Formation of western Liaoning, China. *Vertebrata Palasiatica* 46:178–189.
- Houde P. 1986. Ostrich ancestors found in the Northern Hemisphere suggest new hypothesis of ratite origins. *Nature* 324:563–565. DOI: 10.1038/324563a0.
- Hu D, Hou L, Zhang L, Xu X. 2009. A pre-*Archaeopteryx* troodontid theropod from China with long feathers on the metatarsus. *Nature* 461:640–643. DOI: 10.1038/nature08322.
- Hu H, O'Connor JK, Zhou Z. 2015. A new species of Pengornithidae (Aves: Enantiornithes) from the Lower Cretaceous of China suggests a specialized scansorial habitat previously unknown in early birds. *PLoS ONE* 10:e0126791. DOI: 10.1371/journal.pone.0126791.
- Hu H, Zhou Z, O'Connor JK. 2014. A subadult specimen of *Pengornis* and character evolution in Enantiornithes. *Vertebrata Palasiatica* 52(1):77–97.
- Hwang SH, Norell MA, Ji Q, Gao K. 2002. New specimens of *Microraptor zhaoianus* (Theropoda: Dromaeosauridae) from northeastern China. *American Museum Novitates* 3381:1–44. DOI: 10.1206/0003-0082(2002)381<0001:NSOMZT>2.0.CO;2.
- Ji Q, Currie PJ, Norell MA, Ji S. 1998. Two feathered dinosaurs from northeastern China. *Nature* 393:753–761. DOI: 10.1038/31635.
- Ji Q, Ji S, Lü J, You H, Chen W, Liu Y, Liu Y. 2005. First avialian bird from China. *Geological Bulletin of China* 24:197–210.
- King AS, McLelland J. 1984. *Birds, their structure and function*. London: Bailliere Tindall.
- Kurzanov SM. 1981. An unusual theropod from the Upper Cretaceous of Mongolia. *Joint Soviet-Mongolian Paleontological Expedition* 15:39–49.

- 1031 Lamanna MC, Sues H-D, Schachner ER, Lyson TR. 2014. A new large-bodied oviraptorosaurian
1032 theropod dinosaur from the latest Cretaceous of western North America. *PLoS ONE*
1033 9:e92022. DOI: 10.1371/journal.pone.0092022.
- 1034 Lee S, Lee Y-N, Chinsamy A, Lü J, Barsbold R, Tsogtbaatar K. 2019. A new baby oviraptorid
1035 dinosaur (Dinosauria: Theropoda) from the Upper Cretaceous Nemegt Formation of
1036 Mongolia. *PLoS ONE* 14:e0210867. DOI: 10.1371/journal.pone.0210867.
- 1037 Lee MSY, Worthy TH. 2012. Likelihood reinstates *Archaeopteryx* as a primitive bird. *Biology*
1038 *Letters* 8:299–303. DOI: 10.1098/rsbl.2011.0884.
- 1039 Lefèvre U, Cau A, Cincotta A, Hu D, Chinsamy A, Escuillié F, Godefroit P. 2017. A new
1040 Jurassic theropod from China documents a transitional step in the macrostructure of
1041 feathers. *The Science of Nature* 104:74. DOI: 10.1007/s00114-017-1496-y.
- 1042 Lefèvre U, Cau A, Hu D, Godefroit P. 2020. Feather evolution in pennaraptora. In: Foth C,
1043 Rauhut OWM eds. *The evolution of feathers: from their origin to the present*. Fascinating
1044 Life Sciences. Cham: Springer International Publishing, 103–118. DOI: 10.1007/978-3-030-
1045 27223-4_7.
- 1046 Lefèvre U, Hu D, Escuillié F, Dyke G, Godefroit P. 2014. A new long-tailed basal bird from the
1047 Lower Cretaceous of north-eastern China. *Biological Journal of the Linnean Society*
1048 113:790–804. DOI: 10.1111/bij.12343.
- 1049 Li D. 2010. Osteology of *Confuciusornis sanctus*. Master thesis Thesis. Beijing: Graduate School
1050 of Chinese Academy of Sciences.
- 1051 Li L, Hu D, Duan Y, Gong E, Hou L. 2007. Alethoalaornithidae fam. nov.: a new family of
1052 enantiornithine bird from the Lower Cretaceous of western Liaoning. *Acta Palaeontologica*
1053 *Sinica* 46:365–372.
- 1054 Liu D, Chiappe LM, Serrano F, Habib M, Zhang Y, Meng Q. 2017. Flight aerodynamics in
1055 enantiornithines: information from a new Chinese Early Cretaceous bird. *PLoS ONE*
1056 12:e0184637. DOI: 10.1371/journal.pone.0184637.
- 1057 Livezey BC. 1992. Morphological corollaries and ecological implications of flightlessness in the
1058 Kakapo (Psittaciformes: Strigops habroptilus). *Journal of Morphology* 213:105–145. DOI:
1059 10.1002/jmor.1052130108.

- 1060 Livezey BC, Zusi RL. 2007. Higher-order phylogeny of modern birds (Theropoda, Aves:
1061 Neornithes) based on comparative anatomy: II. - analysis and prospects. *Zoological Journal*
1062 *of the Linnean Society* 149:1–95. DOI: 10.1111/j.1096-3642.2006.00293.x.
- 1063 Lü J. 2003. A new oviraptorosaurid (Theropoda: Oviraptorosauria) from the Late Cretaceous of
1064 southern China. *Journal of Vertebrate Paleontology* 22:871–875. DOI: 10.1671/0272-
1065 4634(2002)022[0871:ANOTOF]2.0.CO;2.
- 1066 Lü J, Chen R, Brusatte SL, Zhu Y, Shen C. 2016. A Late Cretaceous diversification of Asian
1067 oviraptorid dinosaurs: evidence from a new species preserved in an unusual posture.
1068 *Scientific Reports* 6:35780. DOI: 10.1038/srep35780.
- 1069 Lü J, Currie PJ, Xu L, Zhang X, Pu H, Jia S. 2013a. Chicken-sized oviraptorid dinosaurs from
1070 central China and their ontogenetic implications. *Naturwissenschaften*. DOI:
1071 10.1007/s00114-012-1007-0.
- 1072 Lü J, Huang D, Qiu L. 2005. The pectoral girdle and the forelimb of Heyuannia (Dinosauria:
1073 Oviraptorosauria). In: Carpenter K ed. *Carnivorous Dinosaurs*. Bloomington: Indiana
1074 University Press, 256–273.
- 1075 Lü J, Yi L, Zhong H, Wei X. 2013b. A new oviraptorosaur (Dinosauria: Oviraptorosauria) from
1076 the Late Cretaceous of southern China and Its paleoecological Implications. *PLoS ONE* 8.
1077 DOI: 10.1371/journal.pone.0080557.
- 1078 Makovicky PJ, Sues H-D. 1998. Anatomy and phylogenetic relationships of the theropod
1079 dinosaur *Microvenator celer* from the Lower Cretaceous of Montana. *American Museum*
1080 *novitates*; 3240.
- 1081 Martin LD, Zhou Z, Hou L, Feduccia A. 1998. *Confuciusornis sanctus* compared to
1082 *Archaeopteryx lithographica*. *Naturwissenschaften* 85:286–289. DOI:
1083 10.1007/s001140050501.
- 1084 Mayr G. 2017. Pectoral girdle morphology of Mesozoic birds and the evolution of the avian
1085 supracoracoideus muscle. *Journal of Ornithology* 158:859–867. DOI: 10.1007/s10336-017-
1086 1451-x.
- 1087 Mayr G. 2021. The coracoscapular joint of neornithine birds—extensive homoplasy in a widely
1088 neglected articular surface of the avian pectoral girdle and its possible functional correlates.
1089 *Zoomorphology* 140:217–228.

- 1090 Mayr G, Pohl B, Peters DS. 2005. A Well-Preserved *Archaeopteryx* Specimen with Theropod
1091 Features. *Science* 310:1483–1486. DOI: 10.1126/science.1120331.
- 1092 McGonnell IM. 2001. The evolution of the pectoral girdle. *Journal of Anatomy* 199:189–194.
1093 DOI: 10.1046/j.1469-7580.2001.19910189.x.
- 1094 McGowan C. 1982. The wing musculature of the Brown kiwi *Apteryx australis mantellic* and its
1095 bearing on ratite affinities. *Journal of Zoology* 197:173–219. DOI:
1096 10.1111/jzo.1982.197.2.173.
- 1097 Norell MA, Mackovicky PJ. 1999. Important features of the dromaeosaurid skeleton II:
1098 information from newly collected specimens of *Velociraptor mongoliensis*. *American*
1099 *Museum Novitates* 3282:1–45.
- 1100 Novas FE, Agnolin F, Brissón Egli F, Lo Coco GE. 2020. Pectoral girdle morphology in early-
1101 diverging paravians and living ratites: implications for the origin of flight. *American*
1102 *Museum of Natural History* 440:345–353.
- 1103 Novas FE, Agnolín FL, Motta MJ, Brissón Egli F. 2021a. Osteology of *Unenlagia comahuensis*
1104 (Theropoda, Paraves, Unenlagiidae) from the Late Cretaceous of Patagonia. *The Anatomical*
1105 *Record* 304:2741–2788. DOI: 10.1002/ar.24641.
- 1106 Novas FE, Egli FB, Agnolin FL, Gianechini FA, Cerda I. 2018. Postcranial osteology of a new
1107 specimen of *Buitreraptor gonzalezorum* (Theropoda, Unenlagiidae). *Cretaceous Research*
1108 83:127–167. DOI: 10.1016/j.cretres.2017.06.003.
- 1109 Novas FE, Motta MJ, Agnolín FL, Rozadilla S, Lo Coco GE, Brissón Egli F. 2021b. Comments
1110 on the morphology of basal paravian shoulder girdle: new data based on unenlagiid
1111 theropods and paleognath birds. *Frontiers in Earth Science* 0:662167. DOI:
1112 10.3389/feart.2021.662167.
- 1113 O'Connor JK, Chiappe LM, Bell A. 2011. Pre-modern birds: avian divergences in the Mesozoic.
1114 In: Dyke GD, Kaiser G eds. *Living dinosaurs: the evolutionary history of modern birds*.
1115 Hoboken, NJ: J. Wiley & Sons, 39–114.
- 1116 O'Connor J, Sullivan C. 2014. Reinterpretation of the Early Cretaceous maniraptoran
1117 (Dinosauria: Theropoda) *Zhongornis haoae* as a scansoriopterygid-like non-avian, and
1118 morphological resemblances between scansoriopterygids and basal oviraptorosaurs.
1119 *Vertebrata Palasiatica*.

- 1120 O'Connor J, Wang X, Sullivan C, Wang Y, Zheng X, Hu H, Zhang X, Zhou Z. 2018. First report
1121 of gastroliths in the Early Cretaceous basal bird *Jeholornis*. *Cretaceous Research* 84:200–
1122 208. DOI: 10.1016/j.cretres.2017.10.031.
- 1123 O'Connor J, Wang X, Sullivan C, Zheng X, Tubaro P, Zhang X, Zhou Z. 2013. Unique caudal
1124 plumage of *Jeholornis* and complex tail evolution in early birds. *Proceedings of the*
1125 *National Academy of Sciences of the United States of America* 110:17404–17408. DOI:
1126 10.1073/pnas.1316979110.
- 1127 Olson SL. 1973. Evolution of the rails of the South Atlantic islands (Aves: Rallidae).
1128 *Smithsonian Contributions to Zoology*:1–53. DOI: 10.5479/si.00810282.152.
- 1129 Olson SL, Wetmore A. 1976. Preliminary diagnoses of two extraordinary new genera of birds
1130 from pleistocene deposits in the hawaiian islands. *Proceedings of the Biological Society of*
1131 *Washington* 89:247–258.
- 1132 Ősi A, Apesteguía S, Kowalewski M. 2010. Non-avian theropod dinosaurs from the early Late
1133 Cretaceous of central Europe. *Cretaceous Research* 31:304–320. DOI:
1134 10.1016/j.cretres.2010.01.001.
- 1135 Osmólska H, Currie PJ, Barsbold R. 2004. Oviraptorosauria. In: *The dinosauria*. London: Univ
1136 of California Press, 165–183.
- 1137 Ostrom JH. 1974. The pectoral girdle and forelimb function of *Deinonychus* (Reptilia:
1138 Saurischia): a correction.
- 1139 Ostrom JH. 1976. *Archaeopteryx* and the origin of birds. *Biological Journal of the Linnean*
1140 *Society* 8:91–182. DOI: 10.1111/j.1095-8312.1976.tb00244.x.
- 1141 Oswald JA, Steadman DW. 2015. The changing diversity and distribution of dry forest passerine
1142 birds in northwestern Peru since the last ice age. *The Auk* 132:836–862. DOI:
1143 10.1642/AUK-15-74.1.
- 1144 Padian K. 2004. Basal Avialae. In: Weishampel DB, Dodson P, Osmólska H eds. *The*
1145 *Dinosauria*. Berkeley: University of California Press, 210–231.
- 1146 Parsons WL, Parsons KM. 2015. Morphological variations within the ontogeny of *Deinonychus*
1147 *antirrhopus* (Theropoda, Dromaeosauridae). *PLoS ONE* 10. DOI:
1148 10.1371/journal.pone.0121476.

- 1149 Pei R, Li Q, Meng Q, Norell MA, Gao K-Q. 2017. New specimens of *Anchiornis huxleyi*
1150 (Theropoda: Paraves) from the Late Jurassic of northeastern China. *Bulletin of the American*
1151 *Museum of Natural History* 2017:1–67. DOI: 10.1206/0003-0090-411.1.1.
- 1152 Pei R, Pittman M, Goloboff PA, Dececchi TA, Habib MB, Kaye TG, Larsson HCE, Norell MA,
1153 Brusatte SL, Xu X. 2020. Potential for powered flight neared by most close avialan
1154 relatives, but few crossed its thresholds. *Current Biology*. DOI: 10.1016/j.cub.2020.06.105.
- 1155 Pennycuik CJ. 1967. The strength of the pigeon’s wing bones in relation to their function.
1156 *Journal of Experimental Biology* 46:219–233. DOI: 10.1242/jeb.46.2.219.
- 1157 Perle A, Norell M, Clark JM. 1999. *A new maniraptoran theropod, Achillobator giganticus*
1158 *(Dromaeosauridae), from the Upper Cretaceous of Burkhan, Mongolia*. Geology and
1159 Mineralogy Chair, National University of Mongolia.
- 1160 Pittman M, Xu X. 2020. Pennaraptoran theropod dinosaurs past progress and new frontiers.
1161 *Bulletin of the American Museum of Natural History* 440:1–355. DOI: 10.1206/0003-
1162 0090.440.1.1.
- 1163 Pol D, Goloboff PA. 2020. The impact of unstable taxa in coelurosaurian phylogeny and
1164 resampling support measures for parsimony analyses. *Bulletin of the American Museum of*
1165 *Natural History* 440:97–115.
- 1166 Poust AW. 2014. Description and ontogenetic assessment of a new Jehol microraptorine.
1167 Montana State University-Bozeman, College of Letters & Science.
- 1168 Poust AW, Gao C, Varricchio DJ, Wu J, Zhang F. 2020. A new microraptorine theropod from
1169 the Jehol Biota and growth in early dromaeosaurids. *Anatomical Record*:1–25. DOI:
1170 10.1002/ar.24343.
- 1171 Rauhut OWM, Foth C, Tischlinger H. 2018. The oldest *Archaeopteryx* (Theropoda: Avialiae): a
1172 new specimen from the Kimmeridgian/Tithonian boundary of Schamhaupten, Bavaria.
1173 *PeerJ* 6. DOI: 10.7717/peerj.4191.
- 1174 Rayner JMV. 1988. Form and function in avian flight. In: Johnston RF ed. *Current ornithology*.
1175 Boston, MA: Plenum Press, 1–66. DOI: 10.1007/978-1-4615-6787-5_1.
- 1176 Razmadze D, Panyutina AA, Zelenkov NV. 2018. Anatomy of the forelimb musculature and
1177 ligaments of *Psittacus erithacus* (Aves: Psittaciformes). *Journal of Anatomy* 233:496–530.
1178 DOI: 10.1111/joa.12861.
- 1179 Samour J. 2015. *Avian medicine*. Elsevier Health Sciences.

- Senter P. 2007. A new look at the phylogeny of Coelurosauria (Dinosauria: Theropoda). *Journal of Systematic Palaeontology* 5:429–463. DOI: 10.1017/S1477201907002143.
- Serrano FJ, Chiappe LM. 2017. Aerodynamic modelling of a Cretaceous bird reveals thermal soaring capabilities during early avian evolution. *Journal of the Royal Society Interface* 14:20170182. DOI: 10.1098/rsif.2017.0182.
- Serrano FJ, Chiappe LM, Palmqvist P, Figueirido B, Marugán-Lobón J, Sanz JL. 2018. Flight reconstruction of two European enantiornithines (Aves, Pygostylia) and the achievement of bounding flight in Early Cretaceous birds. *Palaeontology* 61:359–368. DOI: 10.1111/pala.12351.
- Serrano FJ, Pittman M, Kaye TG, Wang X, Zheng X, Chiappe LM. 2020. Laser-stimulated fluorescence refines flight modelling of the Early Cretaceous bird *Sapeornis*. In: *Pennaraptoran Theropod Dinosaurs: Past Prog. New Front.* 333–344.
- Shen C, Lue J, Liu S, Kundrat M, Brusatte SL, Gao H. 2017. A new troodontid dinosaur from the Lower Cretaceous Yixian Formation of Liaoning Province, China. *Acta Geologica Sinica-English Edition* 91:763–780. DOI: 10.1111/1755-6724.13307.
- Sullivan C, Xu X, O’Connor JK. 2017. Complexities and novelties in the early evolution of avian flight, as seen in the Mesozoic Yanliao and Jehol Biotas of Northeast China. *Palaeoworld* 26:212–229. DOI: 10.1016/j.palwor.2016.12.001.
- Tsuihiji T, Barsbold R, Watabe M, Tsogtbaatar K, Chinzorig T, Fujiyama Y, Suzuki S. 2014. An exquisitely preserved troodontid theropod with new information on the palatal structure from the Upper Cretaceous of Mongolia. *Naturwissenschaften* 101:131–142. DOI: 10.1007/s00114-014-1143-9.
- Turner AH, Makovicky PJ, Norell MA. 2012. A review of dromaeosaurid systematics and paravian phylogeny. *Bulletin of the American Museum of Natural History* 2012:1–206. DOI: 10.1206/748.1.
- Vickaryous MK, Hall BK. 2006. Homology of the reptilian coracoid and a reappraisal of the evolution and development of the amniote pectoral apparatus. *Journal of Anatomy* 208:263–285. DOI: 10.1111/j.1469-7580.2006.00542.x.
- Wang R, Hu D, Zhang M, Wang S, Zhao Q, Sullivan C, Xu X. 2022a. A new confuciusornithid bird with a secondary epiphyseal ossification reveals phylogenetic changes in

- 1210 confuciusornithid flight mode. *Communications Biology* 5:1–13. DOI: 10.1038/s42003-022-
1211 04316-6.
- 1212 Wang S, Ma Y, Wu Q, Wang M, Hu D, Sullivan C, Xu X. 2022b. Digital restoration of the
1213 pectoral girdles of two Early Cretaceous birds, and implications for early flight evolution.
1214 *eLife* 11:e76086. DOI: 10.7554/eLife.76086.
- 1215 Wang M, O’Connor JK, Xu X, Zhou Z. 2019. A new Jurassic scansoriopterygid and the loss of
1216 membranous wings in theropod dinosaurs. *Nature* 569:256–259. DOI: 10.1038/s41586-019-
1217 1137-z.
- 1218 Wang X, O’Connor JK, Zheng X, Wang M, Hu H, Zhou Z. 2014. Insights into the evolution of
1219 rachis dominated tail feathers from a new basal enantiornithine (Aves: Ornithothoraces).
1220 *Biological Journal of the Linnean Society* 113:805–819. DOI: 10.1111/bij.12313.
- 1221 Wang M, O’Connor JK, Zhou Z. 2019. A taxonomical revision of the Confuciusornithiformes
1222 (Aves: Pygostylia). *Vertebrata Palasiatica* 57:1–37. DOI: 10.19615/j.cnki.1000-
1223 3118.180530.
- 1224 Wang M, O’Connor JK, Zhou S, Zhou Z. 2020. New toothed Early Cretaceous ornithuromorph
1225 bird reveals intraclade diversity in pattern of tooth loss. *Journal of Systematic*
1226 *Palaeontology* 18:631–645. DOI: 10.1080/14772019.2019.1682696.
- 1227 Wang M, Stidham TA, Zhou Z. 2018. A new clade of basal Early Cretaceous pygostylian birds
1228 and developmental plasticity of the avian shoulder girdle. *Proceedings of the National*
1229 *Academy of Sciences U.S.A.* 115:10708–10713. DOI: 10.1073/pnas.1812176115.
- 1230 Wellnhofer P. 2009. *Archaeopteryx: The Icon of Evolution*. Verlag Dr. Friedrich Pfeil.
- 1231 Wu Q, Bailleul AM, Li Z, O’Connor J, Zhou Z. 2021a. Osteohistology of the scapulocoracoid of
1232 *Confuciusornis* and preliminary analysis of the shoulder joint in Aves. *Frontiers in Earth*
1233 *Science* 9:617124. DOI: 10.3389/feart.2021.617124.
- 1234 Wu Q, O’Connor J, Li Z-H, Bailleul AM. 2021b. Cartilage on the furculae of living birds and the
1235 extinct bird *Confuciusornis*: a preliminary analysis and implications for flight style
1236 inferences in Mesozoic birds. *Vertebrata Palasiatica* 59:106–124. DOI:
1237 10.19615/j.cnki.1000-3118.201222.
- 1238 Xu X, Norell MA. 2004. A new troodontid dinosaur from China with avian-like sleeping posture.
1239 *Nature* 431:838–841. DOI: 10.1038/nature02898.

- 1240 Xu X, Norell MA, Wang X, Makovicky PJ, Wu X. 2002. A basal troodontid from the Early
1241 Cretaceous of China. *Nature* 415:780–784. DOI: 10.1038/415780a.
- 1242 Xu X, Qiu Z, Palasiatica V. 2017. A new tiny dromaeosaurid dinosaur from the Lower
1243 Cretaceous Jehol Group of western Liaoning and niche differentiation among the Jehol
1244 dromaeosaurids. *Vertebrata Palasiatica* 55:129–144.
- 1245 Xu X, Wang X, Wu X. 1999. A dromaeosaurid dinosaur with a filamentous integument from the
1246 Yixian Formation of China. *Nature* 401:262–266. DOI: 10.1038/45769.
- 1247 Xu X, You H, Du K, Han F. 2011. An *Archaeopteryx*-like theropod from China and the origin of
1248 Avialae. *Nature* 475:465–470. DOI: 10.1038/nature10288.
- 1249 Xu X, Zhao Q, Norell M, Sullivan C, Hone D, Erickson G, Wang X, Han F, Guo Y, Xing XU,
1250 Qi Z, Mark N, Corwin S, David H, Gregory E, Xiaolin W, Fenglu HAN, Yu GUO. 2009. A
1251 new feathered maniraptoran dinosaur fossil that fills a morphological gap in avian origin.
1252 *Chinese Science Bulletin* 54:430–435. DOI: 10.1007/s11434-009-0009-6.
- 1253 Xu X, Zheng X, Sullivan C, Wang X, Xing L, Wang Y, Zhang X, O’Connor JK, Zhang F, Pan
1254 Y. 2015. A bizarre Jurassic maniraptoran theropod with preserved evidence of membranous
1255 wings. *Nature* 521:70–73. DOI: 10.1038/nature14423.
- 1256 Xu X, Zhou Z, Wang X, Kuang X, Zhang F, Du X. 2003. Four-winged dinosaurs from China.
1257 *Nature* 421:335–340. DOI: 10.1038/nature01342.
- 1258 You H, Lamanna MC, Harris JD, Chiappe LM, O’Connor J, Ji S, Lü J, Yuan C, Li D, Zhang K,
1259 Lacovara KJ, Dodson P, Ji Q. 2006. A nearly modern amphibious bird from the early
1260 Cretaceous of northwestern China. *Science* 312:1640–1643. DOI: 10.1126/science.1126377.
- 1261 Zelenkov NV. 2017. Early Cretaceous enantiornithine birds (Aves, Ornithothoraces) and
1262 establishment of the Ornithuromorpha morphological type. *Paleontological Journal*
1263 51:628–642. DOI: 10.1134/S0031030117060090.
- 1264 Zhang Z, Gao C, Meng Q, Liu J, Hou L, Zheng G. 2009. Diversification in an Early Cretaceous
1265 avian genus: evidence from a new species of *Confuciusornis* from China. *Journal of*
1266 *Ornithology* 150:783–790. DOI: 10.1007/s10336-009-0399-x.
- 1267 Zhang F, Zhou Z. 2000. A primitive enantiornithine bird and the origin of feathers. *Science*
1268 290:1955–1959. DOI: 10.1126/science.290.5498.1955.

- 1269 Zhang F, Zhou Z, Xu X, Wang X. 2002. A juvenile coelurosaurian theropod from China
1270 indicates arboreal Habits. *Naturwissenschaften* 89:394–398. DOI: 10.1007/s00114-002-
1271 0353-8.
- 1272 Zhang F, Zhou Z, Xu X, Wang X, Sullivan C. 2008. A bizarre Jurassic maniraptoran from China
1273 with elongate ribbon-like feathers. *Nature* 455:1105–1108. DOI: 10.1038/nature07447.
- 1274 Zheng X, O'Connor JK, Wang X, Wang M, Zhang X, Zhou Z. 2014. On the absence of sternal
1275 elements in *Anchiornis* (Paraves) and *Sapeornis* (Aves) and the complex early evolution of
1276 the avian sternum. *Proceedings of the National Academy of Sciences* 111:13900–13905.
1277 DOI: 10.1073/pnas.1411070111.
- 1278 Zheng X, Sullivan C, O'Connor JK, Wang X, Wang Y, Zhang X, Zhou Z. 2020. Structure and
1279 possible ventilatory function of unusual, expanded sternal ribs in the Early Cretaceous bird
1280 *Jeholornis*. *Cretaceous Research*:104597. DOI: 10.1016/j.cretres.2020.104597.
- 1281 Zheng X, Xu X, You H, Zhao Q, Dong Z. 2010. A short-armed dromaeosaurid from the Jehol
1282 Group of China with implications for early dromaeosaurid evolution. *Proceedings of the*
1283 *Royal Society B: Biological Sciences* 277:211–217. DOI: 10.1098/rspb.2009.1178.
- 1284 Zhou S. 2013. The anatomy, phylogeny and ecological behaviour analyse of the early Cretaceous
1285 ornithuromorpha of China. PhD Thesis Thesis. Beijing: The University of Chinese
1286 Academy of Sciences.
- 1287 Zhou Z, Clarke J, Zhang F. 2008. Insight into diversity, body size and morphological evolution
1288 from the largest Early Cretaceous enantiornithine bird. *Journal of Anatomy* 212:565–577.
1289 DOI: 10.1111/j.1469-7580.2008.00880.x.
- 1290 Zhou Z, Wang X. 2000. A new species of *Caudipteryx* from the Yixian Formation of Liaoning
1291 northeast of China. *Vertebrata Palasiatica* 38:111–127.
- 1292 Zhou Z, Wang X, Zhang F, Xu X. 2000. Important features of *Caudipteryx* evidence from two
1293 nearly complete new specimens. *Vertebrata Palasiatica*.
- 1294 Zhou Z, Zhang F. 2001. Two new ornithurine birds from the Early Cretaceous of western
1295 Liaoning, China. *Chinese Science Bulletin* 46:1258–1264. DOI: 10.1007/BF03184320.
- 1296 Zhou Z, Zhang F. 2002. A long-tailed, seed-eating bird from the Early Cretaceous of China.
1297 *Nature* 418:405–409. DOI: 10.1038/nature00930.

1298 Zhou Z, Zhang F. 2003a. Anatomy of the primitive bird *Sapeornis chaoyangensis* from the Early
1299 Cretaceous of Liaoning, China. *Canadian Journal of Earth Sciences* 40:731–747. DOI:
1300 10.1139/e03-011.

1301 Zhou Z, Zhang F. 2003b. *Jeholornis* compared to *Archaeopteryx*, with a new understanding of
1302 the earliest avian evolution. *Naturwissenschaften* 90:220–225. DOI: 10.1007/s00114-003-
1303 0416-5.

1304 Zhou Z, Zhang F. 2005. Discovery of an ornithurine bird and its implication for Early Cretaceous
1305 avian radiation. *Proceedings of the National Academy of Sciences U.S.A.* 102:18998–19002.
1306 DOI: 10.1073/pnas.0507106102.

1307 Zhou Z, Zhang F. 2006. A beaked basal ornithurine bird (Aves, Ornithurae) from the Lower
1308 Cretaceous of China. *Zoologica Scripta* 35:363–373. DOI: 10.1111/j.1463-
1309 6409.2006.00234.x.

1310 Zhou S, Zhou Z, O'Connor JK. 2013. Anatomy of the basal ornithuromorph bird
1311 *Archaeorhynchus spathula* from the Early Cretaceous of Liaoning, China. *Journal of*
1312 *Vertebrate Paleontology* 33:141–152. DOI: 10.1080/02724634.2012.714431.
1313
1314

Table 1 (on next page)

Overview of flight-related pectoral girdle features in pennaraptorans and the inferred flight capacities.

Features similar to condition of Ornithuromorpha are highlighted in Grey. GFO, glenoid fossa orientation (0: caudoventral; 1: dorsolateral); CSJ, coracoscapular joint (0: long synchondrosis fused in adult; 1: localized articular surface fused in adult; 2: localized articular surface unfused but tightly articulated; 3: localized articular surface fused during early ontogeny; 4: localized articular surface of flexible joint); PAR, acromion process of the scapula (0: caudal to coracoscapular articular surface; 1: dorsally at the same level as the coracoscapular articular surface; 2: cranially over the coracoscapular articular surface); SCJ, scapuloclavicular joint (0: along the dorsal edge of the scapula; 1: at the cranial tip of the acromion process of the scapula); PAC, acrocoracoid process (0: ventral to the coracoid foramen; 1: same level as the coracoid foramen; 2: close to the glenoid fossa; 3: same level as the glenoid fossa; 4 dorsally over the glenoid fossa); ACJ, acrocoracoid process of the coracoid articulate with the furcula form the acrocoracoclavicular joint (0: no; 1: yes); PPC, coracoid with procoracoid process (0: no; 1: yes); SCA, scapula-coracoid angle (0: $>110^{\circ}$; 1: $90 - 100^{\circ}$; 2: $<90^{\circ}$); CRS, coracoid shape (0: trapezoidal; 1: mediolaterally narrow forming a distinct neck near the scapular articular surface; 2: strut-like); CBO, coracoid body orientation (0: mediolateral; 1: dorsoventral); IFC, inferred flight capacity (0: terrestrial; 1: potential volant and gliding flight; 2: weak powered flight; 3: intermittent powered flight, 4 continuous powered flight)

Table 1 Overview of flight-related pectoral girdle features in pennaraptorans and the inferred flight capacities. Features similar to condition of Ornithuromorpha are highlighted in Grey. GFO, glenoid fossa orientation (0: caudoventral; 1: dorsolateral); CSJ, coracoscavular joint (0: long synchondrosis fused in adult; 1: localized articular surface fused in adult; 2: localized articular surface unfused but tightly articulated; 3: localized articular surface fused during early ontogeny; 4: localized articular surface of flexible joint); PAR, acromion process of the scapula (0: caudal to coracoscavular articular surface; 1: dorsally at the same level as the coracoscavular articular surface; 2: cranially over the coracoscavular articular surface); SCJ, scapuloclavicular joint (0: along the dorsal edge of the scapula; 1: at the cranial tip of the acromion process of the scapula); PAC, acrocoracoid process (0: ventral to the coracoid foramen; 1: same level as the coracoid foramen; 2: close to the glenoid fossa; 3: same level as the glenoid fossa; 4 dorsally over the glenoid fossa); ACJ, acrocoracoid process of the coracoid articulate with the furcula form the acrocoracoclavicular joint (0: no; 1: yes); PPC, coracoid with procoracoid process (0: no; 1: yes); SCA, scapula-coracoid angle (0: $>110^\circ$; 1: $90 - 100^\circ$; 2: $<90^\circ$); CRS, coracoid shape (0: trapezoidal; 1: mediolaterally narrow forming a distinct neck near the scapular articular surface; 2: strut-like); CBO, coracoid body orientation (0: mediolateral; 1: dorsoventral); IFC, inferred flight capacity (0: terrestrial; 1: potential volant and gliding flight; 2: weak powered flight; 3: intermittent powered flight, 4 continuous powered flight)

	GFO	CSJ	PAR	SCJ	PAC	ACJ	PPC	SCA	CRS	CBO	IFC
Early pennaraptorans	0	0	0	0	0	0	0	0	0	0	0
<i>Troodontidae</i>	0	0	1	1	1	0	0	1	0	1	0
<i>Buitreraptor</i>	1	1	2	1	2	0	0	1	0	1	1
<i>Rahonavis</i>	1	2	2	1	?	?	?	?	?	?	2
Microraptorinae	1	1	2	1	2	0	0	1	1	1	1
<i>Bambiraptor</i>	1	1	2	1	2	0	0	1	1	1	1
Velociraptorinae	0	0	1	1	0	0	0	0	0	0	0
Anchiornithidae	1	1	0	1	2	0	0	2	0	1	1
<i>Archaeopteryx</i>	1	1	2	1	2	0	0	1	0	1	2
<i>Jeholornis</i>	1	2	2	1	3	0	1	2	2	1	2
<i>Sapeornis</i>	1	2	2	1	3	0	0	2	0	1	2
<i>Confuciusornis</i>	1	3	2	1	3	0	0	2	2	1	2
Enantiornithes	2	4	2	1	4	0	0	2	2	1	3
Ornithuromorpha	2	4	2	1	4	1	1	2	2	1	4

Figure 1

Simplified phylogeny of Pennaraptora with reconstructions of pectoral girdle, the orientation of coracoid body in the skeleton, and the main characters transition.

Phylogenetic framework following Pol and Goloboff, 2020 . Left in lateral view and middle in cranial view. Right in lateral view showing the orientation of the coracoid body. coracoid facing laterally as in oviraptorosaurs and velociraptorines (top right), facing cranially as in troodontids, potential volant dromaeosaurids, anchiornithids and *Archaeopteryx* (middle right), and facing ventrally as in avialans crownward of *Archaeopteryx* (bottom right). Yellow indicates the scapula, green indicates the coracoid, and red indicates the furcula. Not to scale. 1, rotation of coracoid body, and furcular articulated with cranial tip of acromion process of scapula; 2, localized scapula and coracoid articular surface and lateral oriented glenoid fossa; 3, well develop acromion process of the coracoid; 4 acute angle between scapula and coracoid, and unfused coracoscapular joint; 5, glenoid fossa oriented dorsolaterally, acrocoracoid process dorsally than glenoid fossa, and occurrence of procoracoid process; 6 new joint between coracoid and furcula and the formation of bony closed triosseal canal; 7, lateral oriented glenoid fossa, localized scapula and coracoid articular surface, and well develop acromion process of the coracoid; 8, unfused coracoscapular joint in *Rahonavis*; 9, neck of coracoid body; 10, procoracoid process and strut-like coracoid; 11 strut-like coracoid. 7-9 show the independent evolution of flight adaptive features in several paravian clades.




Figure 2

Comparison of the pectoral girdle of oviraptorosaurs.

A, *Khaan* based on IGM 100/1002 and IGM 100/1127 (Balanoff & Norell, 2012); B, *Oksoko* based on MPC-C 102/110 (Funston et al., 2020); C, *Oviraptor* based on IGM 100/36 and 100/42 modified after Barsbold, 1983; D, *Heyuannia* based on MPC-D 100/30 modified after Osmólska et al., 2007; E, *Rinchenia* based on MPC-D 100/32-A (Funston et al., 2018); F, *Caudipteryx* based on BPM 001 modified after Zhou et al., 2000; G, *Nankang* based on GMNH F10003 (Lü et al., 2013b); H, *Elmisaurus* based on MPC-D 102/113 (Funston et al., 2021); I, *Microvenator celer* based on AMNH 3041 modified after Makovicky and Sues, 1998; J, *Chiostenotes* based on TMP 1979.020.0001 (Funston, 2020). Reconstructed portion marked with dash line; gray color indicates the articular surface for humerus when identical from the specimen during reconstruction. Scapula and coracoid in lateral view, and furcula in cranial view. Abbreviations: cf, coracoid foramen; fc, furcula; gf, glenoid fossa; lc, left coracoid, ls, left scapula; rc, right coracoid; rs, right scapula; pac, acrocoracoid process; par, acromion process; ppc, procoracoid process. Scale bar = 1cm.




Figure 3

Comparison of the pectoral girdle of Scansoriopterygidae and Troodontidae.

A, *Amblopteryx* based on IVPP V24192 modified from Wang et al., 2019a; B, *Epidendrosaurus* based on IVPP V12653 modified from Zhang et al., 2002; C, *Epidexipteryx* based on IVPP V15471 modified from Zhang FC 2008; D, *Gobivenator* based on MPC-D 100/86 (Tsuihiji et al., 2014); E, *Yixianosaurus* based on IVPP V12638 (Dececchi, Larsson & Hone, 2012); F, *Sinornithoides* based on IVPP V9612, modified from Currie and Dong, 2001; G, *Troodon* based on specimen from University Alberta Collections (Gilmore, 1924); H, *Mei* based on IVPP V12733 (Xu & Norell, 2004); I, *Pneumatoraptor* based on MTM V 2008.38.1 (Ósi, Apesteguía & Kowalewski, 2010); J, *Sinovenator* based on IVPP V12615 (Xu et al., 2002); K, *Liaoningvenator* based on DNHM D3012 (Shen et al., 2017). Reconstructed portion marked with dash line; gray color indicates the articular surface for humerus when identical from the specimen during reconstruction. Right scapulocoracoid in lateral view, left coracoid and furcula (H) in cranial view. Abbreviations as in previous figure. Scale bar = 1cm.




Figure 4

Comparison of the pectoral girdle of Dromaeosauridae.

A, *Velociraptor* based on IGM 100/986 and 976 modified after Norell & Mackovicky, 1999; B, *Deinonychus* based on AMNH 3015 modified after Ostrom, 1974; C, *Achillobator* based on MNU FR-15 modified after Perle et al., 1999 ; D, *Bambiraptor* based on AMNH FR 30554 modified from Burnham, 2004; E, *Wulong* based on D2933 modified from Poust et al., 2020; F, *Sinornithosaurus* based on IVPP V12811 modified from Xu et al., 1999; G, *Buitreraptor* based on MPCN-PV-598 modified after (Novas et al., 2018); H, *Rahonavis* based on UA 8656 modified after Forster et al., 2020; I, *Unenlagia* based on MCF PVPH 78 modified from Novas and Puerta, 1997 . Reconstructed portion marked with dash line; gray color indicate the articular surface for humerus when identical from specimen during reconstruction. Right scapulocoracoid in lateral view, left coracoid and furcula in cranial view. Abbreviations as in previous figure. Scale bar = 1cm.




Figure 5

Comparison of the pectoral girdle of Anchiornithidae and basal birds, as well as pectoral girdle morphology change (lateral view) of flightless terrestrial birds.

A, *Anchiornis* right scapulocoracoid in lateral view (showing the medial and lateral crash L-shape), furcula in cranial view based on LPM-B00169 and left coracoid in cranial view (showing the subaquatic shape) based on BMNHC PH804 (originally right side) modified after Hu et al., 2009 and Pei et al., 2017, and IVPP V14378 based on personal observation; B, *Eosinopteryx* based on YFGP-T5197 modified after Godefroit et al., 2013; C, *Xiaotingia* based on STM 27-2 modified after Xu et al., 2011 (originally no scale bar); D, *Serikornis* based on PMOL-AB00200 modified after Lefèvre et al., 2017. E, *Archaeopteryx* right scapulocoracoid based on Mexberg specimen modified after Wellnhofer, 2009, and left coracoid and furcula based on 10th specimen modified after Mayr et al., 2005; F, *Jeholornis* right scapulocoracoid based on STM after O'Connor et al., 2018, left coracoid based on STM 2-49 and IVPP V13886 modified after Wang et al., 2022, furcula based on YFGP-yb2 modified after Lefèvre et al., 2014; G, *Sapeornis* right scapulocoracoid based on IVPP V12698, furcula and left coracoid based on IVPP V13276 modified after Zhou and Zhang, 2003; H, *Confuciusornis* right scapulocoracoid based on IVPP V13168 and GMV-2132 modified from Li, 2010 and Chiappe et al., 1999; furcula based on GMV-2131 modified after Chiappe et al., 1999, left coracoid based on IVPP V16066 modified after Li, 2010. I, crown birds based on *Gallus*; J, *Patagopteryx* based on MACN-N-11 modified after Chiappe, 2002; *Rallus* subadult (47 days) (K) and juvenile (17 days) (L) modified from Olson, 1973; M, *Struthio* modified from McGowan, 1982. In B-D, scapula in lateral view, coracoid and furcula in cranial view. In E-H, Right scapulocoracoid in lateral view, left coracoid and furcula in ventral view. Reconstructed portion marked with dash line; gray color indicates the articular surface for humerus when identical from the

specimen during reconstruction. Abbreviations: ppc, procoracoid process; other abbreviations as in previous figure . In A-H, Scale bar = 1cm. In I-M, Not to scale.




Figure 6

Comparison of the pectoral girdle of Enantiornithes.

A, *Eoalulavis* based on MCCM-LH-13500 modified after Sanz et al., 1996; B, *Concornis* based on MCCM-LH-1184 (Serrano et al., 2018); C, *Elsornis* based on MPD-b 100/201 (Chiappe et al., 2007); D, *Enantiornis* based on PVL-4035 (coracoid) and PVL-4055 (scapula) (Chiappe & Witmer, 2002); E, *Bohaiornis* based on IVPP V17963 modified after Li et al., 2014; F, *Dunhuangia* based on GSGM-05-CM-030 after Wang et al., 2015; G, *Xiangornis* based on PMOL-AB00245 after Hu et al., 2012; H, *Eocathayornis* based on IVPP V10916 after Zhou, 2002; I, *Junornis* based on BMNHC PH 919 Liu et al., 2017; J, *Protopteryx* based on BMNHC Ph 1158 after Chiappe et al., 2019; K, *Shangyang* based on IVPP V25033 after Wang et al., 2019a; L, *Parapengornis* based on IVPP V18687 after Hu et al., 2015; M, *Piscivorenanantiornis* based on IVPP V22582 (Wang et al., 2022). Reconstructed portion marked with dash line; gray color indicates the articular surface for humerus when identical from the specimen during reconstruction. Scapula and coracoid in dorsal view, furcula in ventral view. Abbreviations: acs; articular surface for the scapula, other abbreviations as in previous figure. Scale bar = 1cm.




Figure 7

Comparison of pectoral girdle of Ornithuromorpha.

A, *Archaeorhynchus* based on IVPP V17091 and IVPP V14287 modified from Zhou et al., 2013; B, *Hongshanornis* based on IVPP V14533 (Zhou and Zhang, 2005); C, *Archaeornithura* based on STM7-145 modified from Wang et al., 2015b; D, *Abitusavis* (Yanornithidae), based on IVPP V14606 modified from Wang et al., 2020a; E, *Yixianornis* based on IVPP V12631 (Zhou & Zhang, 2001); F, *Mengciusornis* based on IVPP V26275 modified from Wang et al., 2020b; G, *Gansus* based on CAGS -IG-04-CM-003 and GSGM-07-CM-006 (You et al., 2006; Wang et al., 2016) and 05-CM-026; H, *Ambiortus* based on PIN 3790/271 modified from O'Connor and Zelenkov, 2013; I, *Ichthyornis* based on SMM 2503, YPM 1755, YPM 1733, YPM 1773 (Clarke, 2004). Reconstructed portion marked with dash line; gray color indicates the articular surface for humerus when identical from the specimen during reconstruction. Scapula and coracoid in dorsal view, furcula in ventral view. Abbreviations as in previous figure. Scale bar 1cm. B, E, G, I are drawn by the author.

