

# Lost, hidden, broken, cut - estimating and interpreting the shapes and masses of damaged assemblages of plesiosaur gastroliths (#97916)

1

First submission

## Guidance from your Editor

Please submit by **9 Apr 2024** for the benefit of the authors (and your token reward) .



### Structure and Criteria

Please read the 'Structure and Criteria' page for general guidance.



### Raw data check

Review the raw data.



### Image check

Check that figures and images have not been inappropriately manipulated.

If this article is published your review will be made public. You can choose whether to sign your review. If uploading a PDF please remove any identifiable information (if you want to remain anonymous).

## Files

Download and review all files from the [materials page](#).

11 Figure file(s)

1 Table file(s)

4 Raw data file(s)



# Structure and Criteria

## Structure your review

The review form is divided into 5 sections. Please consider these when composing your review:

1. BASIC REPORTING
2. EXPERIMENTAL DESIGN
3. VALIDITY OF THE FINDINGS
4. General comments
5. Confidential notes to the editor

 You can also annotate this PDF and upload it as part of your review

When ready [submit online](#).

## Editorial Criteria

Use these criteria points to structure your review. The full detailed editorial criteria is on your [guidance page](#).

### BASIC REPORTING

-  Clear, unambiguous, professional English language used throughout.
-  Intro & background to show context. Literature well referenced & relevant.
-  Structure conforms to [PeerJ standards](#), discipline norm, or improved for clarity.
-  Figures are relevant, high quality, well labelled & described.
-  Raw data supplied (see [PeerJ policy](#)).

### EXPERIMENTAL DESIGN

-  Original primary research within [Scope of the journal](#).
-  Research question well defined, relevant & meaningful. It is stated how the research fills an identified knowledge gap.
-  Rigorous investigation performed to a high technical & ethical standard.
-  Methods described with sufficient detail & information to replicate.

### VALIDITY OF THE FINDINGS

-  Impact and novelty not assessed. *Meaningful* replication encouraged where rationale & benefit to literature is clearly stated.
-  All underlying data have been provided; they are robust, statistically sound, & controlled.
-  Conclusions are well stated, linked to original research question & limited to supporting results.



The best reviewers use these techniques

## Tip

## Example

**Support criticisms with evidence from the text or from other sources**

*Smith et al (J of Methodology, 2005, V3, pp 123) have shown that the analysis you use in Lines 241-250 is not the most appropriate for this situation. Please explain why you used this method.*

**Give specific suggestions on how to improve the manuscript**

*Your introduction needs more detail. I suggest that you improve the description at lines 57- 86 to provide more justification for your study (specifically, you should expand upon the knowledge gap being filled).*

**Comment on language and grammar issues**

*The English language should be improved to ensure that an international audience can clearly understand your text. Some examples where the language could be improved include lines 23, 77, 121, 128 – the current phrasing makes comprehension difficult. I suggest you have a colleague who is proficient in English and familiar with the subject matter review your manuscript, or contact a professional editing service.*

**Organize by importance of the issues, and number your points**

1. Your most important issue
2. The next most important item
3. ...
4. The least important points

**Please provide constructive criticism, and avoid personal opinions**

*I thank you for providing the raw data, however your supplemental files need more descriptive metadata identifiers to be useful to future readers. Although your results are compelling, the data analysis should be improved in the following ways: AA, BB, CC*

**Comment on strengths (as well as weaknesses) of the manuscript**

*I commend the authors for their extensive data set, compiled over many years of detailed fieldwork. In addition, the manuscript is clearly written in professional, unambiguous language. If there is a weakness, it is in the statistical analysis (as I have noted above) which should be improved upon before Acceptance.*

# Lost, hidden, broken, cut - estimating and interpreting the shapes and masses of damaged assemblages of plesiosaur gastroliths

Donald M Henderson <sup>Corresp. 1</sup>

<sup>1</sup> Royal Tyrrell Museum of Palaeontology, Drumheller, Alberta, Canada

Corresponding Author: Donald M Henderson  
Email address: don.henderson@gov.ab.ca

**Background.** Gastroliths are stones of uncertain purpose that are commonly found inside the body cavity of plesiosaur fossils worldwide. Gastroliths from four Alberta plesiosaurs were studied to determine both their shapes and masses, and their mass fractions relative to body mass. One animal's set of gastroliths was 100% complete and fully visible, but the others showed varying degrees of loss, damage or obscuration, so estimations of their original states needed to be done. **Methods.** The studied animals were: *Albertonectes vanderveldei*, *Fluvionectes sloanae*, *Nichollssaura borealis* and *Wapuskanectes betsynichollsae*. The animals come from three different environments: open marine, near shore marine, and fluvial. Gastrolith shapes were classified as either xiphoid, cylindrical, discoidal or spherical based on observed and/or estimated dimensions. Although not all methods could be applied in all cases, gastrolith shapes and masses were estimated four different ways – 1) direct measurement and weighing of a subset and predicting the properties of the remaining obscured and hidden stones; 2) measuring triaxial ellipsoid dimensions of free stones to calculate volumes and multiplying by the mass density of chert; 3) measuring two visible triaxial dimensions of embedded stones, estimating the hidden third dimension three different ways, and then determining volumes and masses by calculation; and 4) predicting the density and mass of a densely packed cluster of small gastroliths using geometrical arguments. **Results.** Total gastrolith mass never exceeded 0.2% of body mass in any plesiosaur. The largest plesiosaur in the sample had the largest single gastrolith and total gastrolith mass increases with body size. The shape characteristics of the gastroliths were different for different environments, but compositionally they are dominated by black cherts. A possible common source for the gastroliths was identified for the two geographically close and near-contemporaneous Nichollssaura and Wapuskanectes.

1 Lost, hidden, broken, cut - estimating and interpreting the shapes and  
2 masses of damaged assemblages of plesiosaur gastroliths

3  
4 Donald M. Henderson

5 Royal Tyrrell Museum of Palaeontology, P.O. Box 7500, Drumheller, AB,  
6 Canada, T0J 0Y0

7 Email address: don.henderson@gov.ab.ca

8  
9 **Abstract**

10 **Background.** Gastroliths are stones of uncertain purpose that are commonly found  
11 inside the body cavity of plesiosaur fossils worldwide. Gastroliths from four Alberta  
12 plesiosaurs were studied to determine both their shapes and masses, and their mass  
13 fractions relative to body mass. One animal's set of gastroliths was 100% complete and  
14 fully visible, but the others showed varying degrees of loss, damage or obscuration, so  
15 estimations of their original states needed to be done.

16 **Methods.** The studied animals were: *Albertonectes vanderveldei*, *Fluvionectes sloanae*,  
17 *Nichollssaura borealis* and *Wapuskanectes betsynichollsae*. The animals come from  
18 three different environments: open marine, near shore marine, and fluvial. Gastrolith  
19 shapes were classified as either xiphoid, cylindrical, discoidal or spherical based on  
20 observed and/or estimated dimensions. Although not all methods could be applied in all  
21 cases, gastrolith shapes and masses were estimated four different ways – 1) direct  
22 measurement and weighing of a subset and predicting the properties of the remaining

obscured and hidden stones; 2) measuring triaxial ellipsoid dimensions of free stones to calculate volumes and multiplying by the mass density of chert; 3) measuring two visible triaxial dimensions of embedded stones, estimating the hidden third dimension three different ways, and then determining volumes and masses by calculation; and 4) predicting the density and mass of a densely packed cluster of small gastroliths using geometrical arguments.

**Results.** Total gastrolith mass never exceeded 0.2% of body mass in any plesiosaur. The largest plesiosaur in the sample had the largest single gastrolith and total gastrolith mass increases with body size. The shape characteristics of the gastroliths were different for different environments, but compositionally they are dominated by black cherts. A possible common source for the gastroliths was identified for the two geographically close and near-contemporaneous *Nichollssaura* and *Wapuskanectes*.

## Introduction

Plesiosaurs were unusual animals with nothing like them living today which makes them both very interesting and very frustrating animals to study and try and understand. The last of plesiosaurs went extinct at the end of the Cretaceous, and their evolutionary origins are obscure, but they are diapsid reptiles and maybe more closely related to archosaurs than to lizards and snakes (Bardet et al, 2023), and were all exclusively aquatic. They were among the first vertebrate fossils to be studied in a rigorous, scientific fashion beginning in the early 19<sup>th</sup> century (Ellis 2003), and gastroliths (“stomach stones”) are frequently found with their body fossils. The purpose of the stones has been controversial ever since they were first encountered, with the

most common suggestions being that they were either for digestion, ballast, or material accidentally ingested. See Taylor (1993) and Wings (2007) for comprehensive reviews.

Several **nearly complete** plesiosaurs have been discovered in the western Canadian province of Alberta over the past 30 years, with the most recent one being from **December 2012** – not counting more fragmentary **specimens from 2019 and 2023**. **These fossils** come from two different time periods – Early Cretaceous (Aptian-Albian boundary) and Late Cretaceous (late Campanian) – and from three **very** different environments - open marine, near-shore marine, and fluvial. Within the intact **body walls** **of some of these specimens have been found collections of gastroliths, and it was** **realized that a quantitative analysis of the stomach stones and the bodies that hosted** **them could be done with the knowledge that the stones really did come from within the** **specimens and were not washed into the body cavity after death.** The rock units hosting the fossils are devoid of any gravels, pebbles or cobbles, demonstrating that the gastroliths within the bodies were genuinely allochthonous. However, the hosting **fossils** were either subject to varying degrees of erosion prior to ~~their~~ discovery, or were damaged when first exposed, leading to a loss of fossil material and often a partial loss of any enclosed gastroliths. Additionally, in all but one **case, decisions about the** **preparation of the fossils resulted in** bones and any enclosed gastroliths not being removed, thus leaving quantities of stones incompletely exposed or fully hidden inside **the bodies.**

Despite uncertainty about their actual biological function(s), any new analyses of plesiosaur gastroliths and their relationship to other **aspects of the bodies of the animals** have the potential to improve our understanding of these intriguing geological-biological

entities. This paper presents the results of using quantitative methods to make estimates of the original masses and shape characteristics of incompletely preserved, broken or obscured stomach stones found with plesiosaur fossils. Lastly, the body masses of these plesiosaurs, derived from three-dimensional, digital models of the animals, are used to compare the relative mass fractions of the gastroliths to the bodies that hosted them.

Institutional abbreviation: TMP - Royal Tyrrell Museum of Palaeontology.

## Materials

### Body Fossils

The geographic locations of the four species are shown in figure 1A. Three of the studied specimens are based on single individuals: *Albertonectes vanderveldei* TMP2007.11.1, *Fluvionectes sloanae* TMP2009.37.68, *Nichollssaura borealis* TMP1994.122.1; while the analysis of *Wapuskanectes betsynichollsae* is based on two separate specimens - TMP2011.88.1 and TMP2012.50.1. Three of the specimens were found during open pit mining – *Albertonectes*, *Nichollssaura*, and the first *Wapuskanectes* TMP2011.88.1. The second specimen of *Wapuskanectes*, TMP2012.55.1, was exposed during roadworks, while *Fluvionectes* was discovered during field prospecting. Figure 1B shows the chronostratigraphic positions of the four genera.



*Albertonectes* (Fig. 2) was found in 2007 during open pit mining for gem quality ammonite shells (“ammonite”) south of the town of Lethbridge in the mine operated by Korite International. It comes from the Late Cretaceous Bearpaw Formation and was described and named as the elasmosaurid *Albertonectes vanderveldei* by Kubo *et al.* (2012). This specimen is missing its head, its left forelimb and portions of the distal regions of the hind limbs, and these losses happened prior to final burial. However, all the vertebrae from the atlas-axis to the tip of the tail, and most of the ribs, were found in articulation, although the neck had snapped into four sections. Gastroliths with this specimen were first observed in the field, with more being revealed during preparation.

*Fluvionectes* (Fig. 3) was found during fossil prospecting in the extreme southeast of the province in 2009 in an area known as the Porcupine Pocket of the Sage Creek Grazing Preserve. It is another elasmosaur (Campbell *et al.*, 2021) and was found in rocks of the Lethbridge Coal Zone, a subdivision of the Dinosaur Park Formation (DPF), and the Zone represents a near-coastal setting that was subject to tidal influences (Eberth, 2005). The biozone defined by the ammonite *Baculites compressus* is the same for Bearpaw Formation that produced the *Albertonectes* and the Lethbridge Coal Zone (Tsujita 1995). *Fluvionectes* was found in fluvial sediments along with many pieces of coalified wood in close association with the bones, and the interpretation is that the carcass was caught in a log jam (Campbell *et al.*, 2021). The periphery of the outcrop which held the specimen was heavily eroded when found, and much of the animal’s extremities were lost – most of the tail, neck and distal limbs. However, most the axial body from the proximal quarter of the tail to the proximal quarter of the neck is preserved, with all the bones in close association, and this allows

an estimation of the animal's size to enable a body reconstruction. The presence of gastroliths with this specimen was revealed during preparation.

*Nichollssaura* (Fig. 4) was uncovered during overburden removal in the Syncrude Canada Ltd. tar sand mine north of Fort McMurray, and comes from the Wabiskaw Member of the Early Cretaceous Clearwater Formation which is interpreted to be earliest Albian in age (Caldwell et al. 1978). This specimen was almost complete except for a missing left forelimb, the bones distal the tarsals on the right hindlimb, and the proximal third of the cervical ribs on the left side, and the first few anterior dorsal ribs, also on the left side. These missing elements were reconstructed for display purposes. This animal is a leptocleidid plesiosaur and was described by Druckenmiller & Russell (2008). The presence of its gastroliths was revealed during preparation.

The first *Wapuskanectes* specimen, TMP2011.88.1 (Fig. 5), is an early elasmosaurid and comes from the same Syncrude Canada Ltd. tar sand mine and rock unit that produced *Nichollssaura* – the Wabiskaw member of the Clearwater Formation. The genus was described and named by Druckenmiller & Russell (2006), with the holotype specimen being TMP1998.49.2 which also came from the same mine and rock unit. The present specimen consists of proximal neck vertebrae, anterior dorsal vertebrae, the pectoral region, a left humerus, some manual phalanges, and some incomplete ribs and gastralia. This specimen has a substantial collection of gastroliths visible at the posterior end of the pectoral girdle that was revealed during preparation.

The second *Wapuskanectes* specimen (Fig. 6) also comes for the Wabiskaw Member of the Clearwater Formation, but was found during road construction for the

Parson's Creek Interchange on the north side of the town of Fort McMurray in December of 2012. It was located about 30km south-southeast of the localities of the earlier specimens from the Syncrude mine. Unfortunately, it was exposed when a grader ploughed through the neck resulting in the destruction and loss of the skull and most of the neck. Additionally, there was no trace of the right forelimb, and this loss is interpreted to have occurred some time prior to the final burial of the animal. Despite these missing pieces, the rest of the specimen is very well preserved. Preparation revealed some small gastroliths visible between the posterior dorsal ribs of this specimen. The relative completeness of this specimen enabled the generation of a 3D body model for mass estimation. The maximum transverse widths of the pectoral girdles of the two *Wapuskanectes* specimens, as measured at the postero-lateral margins of the glenoids, are identical at 57cm, and it is assumed that the overall body sizes and proportions of the two animals would have been very similar.

# Stomach Stones

*Albertonectes* was first exposed when an excavator bucket unexpectedly struck the fossil. Portions of the mid-trunk dorsal and ventral ribs, and an unknown quantity of gastroliths, were lost when the excavator bucket smashed through the fossil. Some time after death the carcass came to lie on the seabed on its back. As the internal organs, and the stomach in particular, decayed and lost their ability to support themselves, the gastroliths gravitated downwards towards the medial side of the dorsal body wall and some came into direct contact with ribs. Subsequent compaction resulted in some

portions of the ribs being plastically deformed around the gastroliths. Except for four stones that were knocked loose at the time of impact, the remainder were tightly clustered together and held in the matrix in a roughly spherical volume and did not show any degree of size or shape sorting. Given the uniqueness of the specimen, and its excellent state of preservation, it was decided to leave it intact and not remove any bones or gastroliths. 97 gastroliths were revealed in total, four in the field, with the rest being exposed during preparation (Fig 2B). 52 stones could be reliably measured to obtain three dimensional radial measurements. The remaining 45 were visible but were either too deeply embedded in the hosting matrix, or were too obscured by ribs, to enable the collection of reliable geometry data. The gastroliths are all gray to black, sub-spherical, chert cobbles with some having a high polish.

For *Fluvionectes*, given the incomplete nature of its preservation, and its modest level of disarticulation, it was decided to fully prepare its remains and remove all the bones. During this preparation 75 gastroliths was discovered and removed (Fig 3B). These gastroliths tend to be disk-shaped and are all black cherts. The complete removal of these stones permitted the accurate measurement of their lengths, widths and depths, and the direct determination of their masses. These data were used as a basis for assessments of the reliability of the methods of estimation of missing gastrolith data used with the other plesiosaurs (see Methods).

The gastroliths of the *Nichollsaura* were inadvertently exposed when a saw cut, intended to cut away excess matrix from the ventral side of the block, went through the trunk region at a level that intersected limb girdles, dorsal vertebrae, gastralium and gastroliths (Fig. 4B). 165 stones, composed of cherts and quartzites, are exposed on

the cut surface as isolated, two-dimensional elliptic shapes with most of them arranged along the left and right sides of the vertebral column, but with a substantial cluster immediately in front of the left pubis. This entire collection of stones appears to be spread out uniformly in a single layer. The visible co-occurrence of limb girdles, vertebrae, gastralia and gastroliths on the frontal plane defined by the cut surface demonstrates the substantial amount of dorso-ventral compaction that the fossil experienced after burial.

The gastroliths associated with the first *Wapuskanectes* specimen, TMP2011.88.1 (Fig. 5B), were found during preparation as an isolated, elliptical cluster with semi-major and intermediate diameters of approximately 25 and 20cm, and a thickness (semi-minor diameter) of roughly 5cm. The stones are almost exclusively black, polished cherts with some minor quartzites. There are two regions within the cluster comprising two different sets of stone sizes: a loosely packed region of 93 stones with an average maximum diameter of about 2-3cm and a densely packed region with an unknown, but large, number of small stones with an average maximum diameter of no more than 1cm. This latter collection is defined by a sharp, posterior margin that may indicate the original boundary of the stomach (gizzard?) wall. The collection of coarser gastroliths was sufficiently exposed by mechanical preparation to obtain reliable lengths and widths for them, but not depths. It was not possible to obtain reliable measurements from any of the densely packed, smaller stones.

With the second, Fort McMurray Parson's Creek roadworks specimen of *Wapuskanectes*, TMP2012.50.1, there were no gastroliths visible initially. The specimen came to rest on the seabed on its back, and during initial preparation a single, black

chert pebble was uncovered poking out between a pair of mid-trunk dorsal ribs on the right side of the body. Similar to what occurred with the *Albertonectes* gastroliths (see above), the stomach stones of TMP 2012.50.1 also settled towards the medial side of the dorsal ribs in the posterior trunk region. Before preparation of the torso went any further, the specimen was X-rayed at an industrial facility that analyses large metal castings for defects where they can easily detect tiny fractures and voids. The hope was that this technology would reveal the sizes and extents of other gastroliths within the body cavity, but it was unable to detect anything resembling gastroliths (or even bones). Subsequent preparation revealed more small, black chert pebbles lying between the ribs, and close to the vertebral column, on both the left and right sides at a position just posterior to the midpoint of the trunk (Fig. 6B). Given the overall quality of the fossil, it was decided to leave all the bones in place, thus leaving an unknown number of gastroliths hidden within. Despite the limited number gastroliths exposed with this specimen, they are very similar in size, shape and composition to the small gastroliths seen with TMP2011.88. As both specimens come from the same rock unit, the Wabiskaw Member of the Clearwater Formation, it was assumed that the overall gastrolith composition would be similar for the two specimens.

## Methods

### Gastrolith volume and mass estimates

Four of the gastroliths associated with the *Albertonectes* were free of the matrix and could be confidently measured to obtain the three diameters, the remainder were

223 partially embedded within the matrix and some were also partly obscured by the ribs.  
 224 Ninety seven stones were observed in total, but reliable measurements in all three  
 225 dimensions could only be taken from 52 of them. These gastroliths were viewed as tri-  
 226 axial ellipsoids and their semi-major, intermediate and semi-minor diameters were  
 227 measured with digital calipers to the nearest tenth of a millimetre. The expression to  
 228 compute the volume of a tri-axial ellipsoid is  $Volume = \frac{4}{3}\pi abc$ , where 'a', 'b', and 'c' are  
 229 the semi-major, intermediate, and semi-minor radii, respectively, of the ellipsoid. Chert  
 230 has a density of 2.67 gm/cc (Deer et al., 1992), and the masses of these 52 chert  
 231 gastroliths were computed by multiplying their volumes by the density of chert. For the  
 232 remaining 45 stones only two diameters could be confidently measured. Lacking full  
 233 knowledge of their dimensions, and noting that no sorting by shape or size was  
 234 apparent with the fully measurable cluster of 52 stones, this latter assemblage was  
 235 taken to be a representative, and random, sample of the original full set of gastroliths. A  
 236 simple ratio was used to estimate the combined mass of the remaining stones: if the  
 237 measured 52 stones have a combined mass of 4.98 kg, then the mass of the remaining  
 238 45 will come from solving for '?kg' in the expression:  $\frac{4.98\text{ kg}}{52} = \frac{?kg}{45}$

239 Only with *Fluvionectes*, and its fully removed gastroliths, was it possible to get  
 240 the actual masses of all the stones. The stones were weighed to the nearest tenth of a  
 241 gram on electronic scales (Symmetry ED-150 by Cole-Parmer). As a check on the  
 242 gastrolith mass estimation schemes outlined above and below for the other plesiosaur  
 243 specimens, the three, tri-axial dimensions of the Sage Creek gastroliths were also  
 244 measured and their masses estimated by multiplying their calculated volumes by the  
 245 density of chert. The semi-major and intermediate diameters were also used to predict

the third diameter. The goal was to test the accuracy of the computed masses against the observed mass.

The *Nichollssaura* gastroliths were exposed on the saw-cut surface as closed contours of elliptic shape, from which the longitudinal and transverse diameters could have been obtained by direct measurement. However, to properly estimate the volume and shape of the gastroliths, the third diameter needs to be estimated, and it was decided to use a computational method to do this and objectively determine the lengths and widths of the exposed elliptical cross-sections at the same time. A digital image of the cut surface exposing the gastroliths was imported into the drawing program Corel Draw!, and all the visible perimeters of gastroliths were digitally traced, and the traces were then exported as individual AutoCAD DXF files. These DXF files were reduced to simple (X,Y) co-ordinate pairs defining the stone perimeters, and a computer program was written to carry out the following processing of the data. The longest diameter of a stone cross-section was found by determining the greatest distance between a pair of points for a given stone perimeter. Using its perimeter data, the cut-exposed area of the stone was computed using a triangular decomposition method (Henderson, 2002). The formula for the area of an ellipse given by  $Area = \pi \left(\frac{a}{2}\right) \left(\frac{b}{2}\right)$ , where 'a' and 'b' are the semi-major and semi-minor diameters of the visible ellipse, respectively. Using the observed value for 'a' (the longest diameter) and the computed area, the value of 'b' can be derived via the expression  $b = 2 \cdot \frac{Area}{\left(\frac{\pi a}{2}\right)}$ . These values of 'a' and 'b' are used in estimation methods outlined in the next paragraph.



267        Like what was seen with the *Nichollssaura* gastroliths, those of *Wapuskanectes*  
 268        could only be reliably measured in two dimensions - length and width, with the third  
 269        dimension, depth, needing to be estimated. Three methods were used to estimate this  
 270        third dimension for the gastroliths of these two plesiosaurs: 1) depth = length ÷ 2; 2)  
 271        depth = average of length and width = (length + width) ÷ 2; and 3) depth = square root  
 272        of the product of length and width =  $\sqrt{(\text{length} \times \text{width})}$ . These three methods were also  
 273        applied to the fully measured stones of *Albertonectes* and *Fluvionectes* using the  
 274        observed lengths and widths to estimate depths. These latter results were used to see  
 275        which of the three methods produced an estimated mass closest to the properly  
 276        measure ones.

277        For a long time, mathematicians have been interested in knowing the best way  
 278        pack spheres so as to have the least amount of space between them, and this became  
 279        known as the Kepler Conjecture (Kepler, 1611). Eventually, it was formally proven that  
 280        the most efficient method achieves a packing density of approximately 0.74048 (Hales,  
 281        2012). The spherical packing idea was applied to the densely packed cluster of small  
 282        gastroliths found with first *Wapuskanectes* specimen, TMP2011.88.1, in an attempt to  
 283        estimate the mass of the stones. The gastroliths visible on the surface of the cluster are  
 284        clearly touching all their neighbours, as posited by the sphere packing theorem, and this  
 285        packing configuration was assumed to be true for the entire cluster of small stones  
 286        inside. With an estimate of the volume of this cluster, multiplying the volume by the  
 287        density of chert, and then applying the packing density factor would give an estimate of  
 288        the cluster mass.

289

# 290 Body mass estimations

291 Three-dimensional meshes representing the axial body and limbs of the four  
 292 plesiosaurs were generated using the methods of Henderson (1999). The actual body  
 293 outlines were based on the preserved skeletal forms along with estimates of the soft  
 294 tissues that would have surrounded them. For the neck regions, the dorso-ventral  
 295 diameters were set so that space for an esophagus and trachea could be  
 296 accommodated. Given the great length of the trachea in these animals, it was assumed  
 297 that the tracheal lumen would have to be large to reduce the effects of the viscous drag  
 298 on air flow caused by the large amount of surface area of the trachea. It has been  
 299 shown that the resistance to flow decreases exponentially with increasing tracheal  
 300 diameter (Daniels and Pratt 1992). The outlines of the flippers were extended beyond  
 301 their known bony extents by comparison with the limbs of sea-turtles and penguins. The  
 302 bones forming the limbs of *Nicholssaura* and the *Wapuskanectes* road works specimen  
 303 (TMP 2012.50.1) were both much broader (greater fore-aft chordal lengths) than those  
 304 of the two elasmosaurs, and this resulted in their modelled limbs being broader than  
 305 those of the elasmosaurs. Lung volumes were estimated for each model, and were set  
 306 to represent between 8-10% of the axial body volume, based on observations of the  
 307 lungs of living reptiles (Tenney and Tenney 1970). Actual computation of the masses of  
 308 the body regions (axial and appendicular) involves multiplying the volumes of these  
 309 regions by a predefined value for the tissue density. The volumes were estimated using  
 310 the methods outlined in Henderson (1999). A uniform body density of 1,050 gm/L was  
 311 used for all the post-cervical body regions in all the models. This value is higher than  
 312 that of pure water at 1000 gm/l, but it was felt that given the dense, non-pneumatic

nature of the bones of the axial and appendicular skeletons, and in particular the high proportion of bone relative to soft-tissue inferred for the limbs, that this denser value was justified. The necks, with their large, air-filled trachea, were set to a lower density of 900 gm/l. Despite the main body density value being greater than that of water, when a full body model is combined with its lung, the animals are still positively buoyant when the lungs are fully inflated as observed in a study of buoyancy and equilibrium in plesiosaurs that used digital models with the same densities and lung volume proportions used here (Henderson 2006). The assumptions and methods that went into the generation of the above models have been validated with accurate mass estimates for similarly constructed models of extant, semi-aquatic reptiles – alligators (Henderson, 2003), sea turtles (Henderson, 2006) and penguins (Henderson, 2018) – and fully terrestrial animals such as horses and giraffes (Henderson and Naish, 2010) and elephants (Henderson, 2006).

## Results

Figure 7 shows the four body models generated from the plesiosaur skeletons, and Table 1 presents the physical attributes determined from the models. Two of the models were based on nearly complete fossils – *Albertonectes* and *Nichollssaura* – and their necks (grey coloured regions on models) are estimated to weigh 1100 kg and 10.6 kg, respectively. Relative to body mass, these necks represent 22.7% and 7.86% of total body mass. The necks of the other two – *Fluvionectes* and *Wapuskanectes* – were incompletely preserved, and this could lead to uncertainty regarding their actual body

mass. As restored, the necks for these two animals are estimated to have mass of 72.9 kg and 198 kg, respectively, and their relative mass fractions are 18.6% and 16.5%, respectively. As these latter two animals are early elasmosaurids from close to the Aptian/Albian boundary, they were given substantial necks and their relative neck mass fractions approach that of the later and derived Campanian *Albertonectes*.

Table 2 presents observed and estimated gastrolith masses for the four plesiosaurs. The 52 stones that could be fully measured for *Albertonectes* were found to have a combined volume of 1,865 cm<sup>3</sup>, and when multiplied by the density of chert at 2.67 gm/cm<sup>2</sup>, to have a mass of 4,980 gm. From the calculated mass of the observable 52 stones, the remaining, unmeasured 45 stones are predicted via a simple ratio expression to have a combined mass of 4,310 gm. Together, these two estimates give a total gastrolith mass of 9,290 gm. Using the measured semi-major and intermediate diameters of the first 52 gastroliths of *Albertonectes*, the three methods of predicting the third diameter gave the following mass results - Half Length: 4,654 gm; Average of Length and Width: 10,695 gm; RMS of Length and Width: 10,577 gm. The Half Length method clearly produced the result closest to the one that used the three measured diameters.

Direct weighing of the *Fluvionectes* gastroliths gave a total gastrolith mass of 359 gm. Determining the volumes of the stones from their measured diameters, and multiplying them by the density of chert, gave a total mass estimate of 325 gm – a value 9.56% less than the directed weighed value. ~~At first it might seem reasonable to apply the 9.56% mismatch as a correction factor the stone masses calculated for~~ *Albertonectes* that were also based on geometry. However, the shape distributions of

the two assemblages are very different (see the histograms and pie charts below), suggesting that the mismatch between observed and calculated mass for *Fluvionectes* might be sample specific, and not be applied as a correction factor to the results obtained for *Albertonectes*. Applying the three, third-dimension estimation methods to the measured semi-major and intermediate diameters of the *Fluvionectes* gastroliths gave the following mass estimates - Half Length: 337.7 gm; Average of Length and Width: 780.7 gm; RMS of Length and Width: 770.8 gm. Again, the Half Length estimation provides the estimate closest to the one derived from actually weighing the gastroliths.

In light of the close agreement between gastrolith mass estimates produced using the Half Length method and those from direct measurement of *Albertonectes* and *Fluvionectes* gastroliths, the obscured depth dimensions for the gastroliths of *Nichollssaura* and *Wapuskanectes* were estimated using the Half Length method. This method gave a total mass for the cut *Nichollssaura* gastroliths of 105.4 gm, and a mass of 186.7 gm for the scattered cluster of larger gastroliths from *Wapuskanectes*.

The densely packed cluster of small gastroliths found with *Wapuskanectes* specimen TMP2011.88.1 has a shape similar to that of a flattened, tri-axial ellipsoid with its length, width and depth being 20, 10 and 5 cm, respectively. This cluster has a volume of 157.1 cm<sup>3</sup>, and when multiplied by the density of chert and the spherical packing density factor, has an estimated stone mass of 310.6 gm. Adding the mass estimates of the loose and dense clusters give a total mass of 497.3 gm.

Histograms and pie charts were generated to aid visualization of the differences and similarities between the shapes and masses of stomach stones. Figure 8 presents histograms that show marked differences in the ranges and proportions of the masses of stones ingested by the animals. *Albertonectes*, being the largest animal in the study, also had the greatest range of stone sizes, with the largest stone being 1.13 kg. The largest stones recovered from the other animals were all an order of magnitude smaller (Table 2). To facilitate comparisons between the stones of all four animals, the histogram for *Albertonectes* was done again but with the same smaller range of bin sizes (0 – 16 gm) that was applied to the other specimens (Fig. 8B). The gastroliths of the three smaller animals are dominated by stones in the 0 – 4 gm range, while these stones represent a minor component for *Albertonectes*. Visual inspection of the gastrolith size distributions for the smaller animals shows them to be skewed to the right, but with *Fluvionectes* having less of a skew.

Pie charts were generated for all the gastrolith samples using four shape categories – xiphoid (“blade-like”), discoid, spherical, and cylindrical based on the classification scheme of Dobkins and Folk (1970). The pie charts only analyze those gastroliths that could be fully or partly measured. The pie chart proportions were computed two ways: 1) using the individual masses of the stones and seeing how the masses of stones distributed across each category (Fig. 9), and 2) the absolute count of how many stones were in each category (Fig. 10). For *Albertonectes* and *Fluvionectes*, their pie charts demonstrate that the two different ways of looking at gastrolith shape distribution can give very different results. This is especially noticeable with the blade-like (xiphoid) class where *Albertonectes* would appear to have almost none (1.1%)

when their mass is considered (Fig. 9A), but almost 10 times as much when counted (Fig. 10A). However, both measures are consistent in showing that the blade-like gastroliths of *Albertonectes* make up the smallest fraction of the entire collection. The differences in shape category fractions based on different methods of analysis also apply to *Fluvionectes* (Fig 9B vs Fig. 10B). It should be noted that the present count fraction pie chart for *Albertonectes* gastroliths differs slightly from the one originally presented in the initial description by Kubo et al. (2012, Fig. 9) – a small error was discovered in the earlier program used for calculating the shape fractions. The corrected plot has slightly larger spheroid and smaller cylindrical fractions than were previously presented.

Figure 11 summarizes the relationships between largest gastrolith and total gastrolith mass relative to body mass. The 2 orders of magnitude differences seen in the ranges of stone masses necessitated plotting the data on log-log plots. Although it is just a sample of four plesiosaurs, and the gastrolith collections each have their deficiencies, two trends are noticeable from the two plots. The first is that the largest plesiosaur, *Albertonectes*, has both the largest single gastrolith and the most gastroliths. A regression computed for the largest gastrolith vs. body mass has correlation of 0.8762, but the uncertainty on the computed slope (0.5474) is almost half the slope value (1.40760). A better regression result comes from plotting total gastrolith mass against body mass. The uncertainty on the computed slope (0.2446) is less than half that seen with previous plot, and the correlation coefficient is ~~much~~ higher at 0.9606. In both plots, the amounts of gastroliths estimated for *Wapuskanectes* lie below the fitted line. The collection of stones found with the first specimen of *Wapuskanectes*,

TMP2011.88.1, was disturbed after death as shown by the “smeared-out” shape of the collection, and suggests that an unknown number of gastroliths were lost prior to final burial of the carcass. Of the four fossils studied, this one was also the most disrupted, with the pectoral girdle being inverted relative to the rest of the body prior to final burial. The specimen was discovered when some neck vertebrae were exposed by heavy equipment. It was removed from the mine as a single, large, intact block with no chance of any stones being lost during this process (pers. obs.).

## Discussion

Although both are derived Late Cretaceous elasmosaurs, *Albertonectes* and *Fluvionectes* come from rock formations that represent ~~very~~ different environments – open marine vs. fluvial, respectively, and this could explain the differences in their respective gastrolith compositions. Support for this idea might come from the observation that the other two plesiosaurs – *Nichollssaura* and *Wapuskanectes* – both come from the Wabiskaw Member of the Clearwater Formation, and by both pie chart measures their gastrolith composition are very similar. This is also remarkable because the body sizes of the animals are ~~very~~ different in body proportions and size, with *Wapuskanectes* being approximately ten time more massive than *Nichollssaura* (Table 1).

The pie charts reveal that the discoid fractions of the stomach stones represent either major (*Fluvionectes*) or substantial (*Albertonectes*) portions of the sample. The strong discoid signal seen in these samples suggests that these animals were collecting



potential stomach stones mainly from beaches (discs), but also some from the mouths of rivers (spheres), based on the observations of Dobkins and Folk (1970). The bias towards crypto- and micro-crystalline quartz (chert) gastroliths for plesiosaurs of the present study may indicate that the animals actively sought these rock types for their hardness and durability. It could also be argued that we have biased samples of stomach stones because any ingested limestone or carbonate-cemented clastic pebbles would have been dissolved and/or disaggregated by stomach acids and the small constituent grains excreted. However, if the gastrolith samples represent an instantaneous, random “snap-shot” of the stone assemblages carried by the animals at the time of their deaths, it is surprising that none of four gastrolith samples studied show even the slightest trace of any sandstone or limestone pebbles.

As can be seen from Table 2, the masses of gastroliths represent extremely small fractions of total body mass, with an average value being just one tenth of one percent. The 9.29kg mass of stones estimated for *Albertonectes* is similar to the 8.84kg mass of stones recovered from an elasmosaur from the Bearpaw Formation of Montana (Darby and Ojakangas, 1980), but the largest stone from this latter animal was just 662gm, approximately half the size of the largest stone from *Albertonectes*. In their review of elasmosaur gastroliths, Thompson et al. (2007) comment on the extremely variable nature of the range of sizes and the total masses of the gastroliths recovered from this group of plesiosaurs. A large Antarctic specimen examined by Thomson et al. (2007) was found to have 2,626 gastroliths, but their total mass was just 3.02kg, and the largest was only 46.6gm. At the other extreme, Everhart (2000) reports on a total mass of gastroliths from a Kansas elasmosaur being equal to 13.1kg with the largest weighing

1.49kg. If gastroliths were truly related to buoyancy control the expectation would be that elasmosaurs of the same size should have the same amounts of gastroliths, but this is ~~clearly~~ not the case. Similar what was argued for in modelling studies of gastroliths in crocodilians (Henderson 2003) and plesiosaurs (Henderson 2006), and the suspicions of other authors eg. (Cicimurri & Everhart 2001), the effects of these relatively tiny, and variable, masses of stones on the buoyancy and equilibrium of the animals when they were alive are considered to be almost non-existent.

The stones found with *Nichollssaura* and *Wapuskanectes* are very similar in size, shape and composition to the clasts found within the Cadomin Conglomerate, a Lower Cretaceous rock formation which is found the length of the Rocky Mountain foothills in Alberta from the 49th to the 60<sup>th</sup> parallels (Schultheis and Mountjoy, 1978). This identification was done with reference to a large sample of the conglomerate held in the collections of the Royal Tyrrell Museum with specimen number TMP2016.38.4. This conglomerate is early Aptian in age, while the Wabiskaw Member and its plesiosaurs are earliest Albian, and this temporal gap represents an interval of proximately 8 – 10 million years (Alberta Geological Survey, 2015). It is hypothesized that *Nichollssaura* and *Wapuskanectes*, living the northern Western Interior Seaway during the Albian, could have swum westwards to beaches and river mouths along the west coast of the Seaway to collect either uncemented, or eroding, Cadomin clasts.

## CONCLUSIONS

Using samples of gastroliths from four plesiosaur fossils (two Early Cretaceous and two Late Cretaceous) with varying degrees of completeness, it has been shown that plausible estimates of the original masses of the stones can be made. Total body masses were made for the four animals, and these can be used as a reference standard for other plesiosaurs with similar body shapes. Consistent with earlier suspicions about the ineffectiveness of the relatively small amounts of stones found with plesiosaurs on their buoyancy, the total masses of the stones found with the present plesiosaurs was never more 0.2% of total body mass. With geometry data from the stones their shapes can be categorized and hypotheses made about where the animals collected the stones. eg. river or beach setting. Lastly, the sizes, shapes and compositions of the gastroliths found with the two different species of Early Cretaceous plesiosaur that came from the same geographic area and time were found to be very similar, and suggest a common origin.

# ACKNOWLEDGMENTS

The assistance from the Syncrude Canada Ltd. mine people when we regularly arrive to collect the fossils they bump into (*Nichollssaura* and *Wapuskanectes*, in this case) is greatly appreciated, as their people always go out of their way to help us. Similarly, the staff at the Korite Mine were most helpful when we collected *Albertonectes*. Many people who were, or still are, staff at the Royal Tyrrell Museum of Palaeontology (RTMP) were involved in the lengthy preparations of the fossils discussed in this study. Preparation of *Albertonectes* was done by Mark Mitchell, Robin

Cooke, Dawna Macleod and Judy Graham. *Fluvionectes* was prepared by Rebecca Sanchez. *Nichollssaura* was prepared by Mark Mitchell, Shane Zimmer, Stuart Wright and Jim McCabe, with restoration work done by Mark Mitchell. The first *Wapuskanectes* was prepared solely by Mark Mitchell, while the second one was prepared by Marilyn LaFramboise, Ramon Nagesan, Emily Frampton and Samantha Haddon. The X-raying of the torso block of the second *Wapuskanectes* specimen was done in Burnaby, British Columbia at the invitation of David G. Stasuk, president of Stasuk Testing & Inspection Ltd. Mr Stasuk and his staff put in many long hours and a whole weekend in an attempt to get results. Rebecca Sanchez and Tom Courtenay of Collections at RTMP dealt with my many requests to move and view specimens. Specimen photography and assembly of composite images was done by Sue Sabrowski (RTMP). Mark Mitchell (RTMP) is thanked for his expertise in the field when we were collecting all four specimens and for his profound knowledge of the plesiosaurs in the RTMP collections.

# References

- Alberta Geological Survey. 2015. Alberta Table of Formations; Alberta Energy Regulator, [https://ags.aer.ca/publications/Table\\_of\\_Formations\\_2019.html](https://ags.aer.ca/publications/Table_of_Formations_2019.html), February 2024.
- Bardet, N., Houssaye, A., Jouve, S., and Vincent, P. 2023. Ocean Life in the Time of Dinosaurs. Princeton University Press. 208 pp.
- Caldwell, W.G.E., North, B.R., Stelck, C.R., and Wall, J.H. 1978. A **formanifera** zonal scheme for the Cretaceous Systems in the interior plains of Canada. In Western and Arctic Biostratigraphy. C.R. Stelck and B.D.E. Chatterton (eds.), Geological Association of Canada Special Paper 18.
- Cicimurri, D.J. & Everhart, M.J. 2001: An elasmosaur with stomach contents and gastroliths from the Pierre Shale (Late Cretaceous) of Kansas. Transactions of the Kansas Academy of Sciences 104, 129-143.
- Daniels, C. B., and J. Pratt 1992. Breathing in long necked dinosaurs; did the sauropods have bird lungs? Comp. Biochem. Physiol. 101A: 43-46.
- Darby, D. G., and Ojakangas. R. J. 1980.Gastroliths from an Upper Cretaceous plesiosaur. Journal of Paleontology 54(3): 548-556.
- Deer, W.A.R., Howie, R.A., Zussman, J. 1992. An introduction to the rock-forming minerals. Second edition. Pearson Education Limited, Harlow, UK,. 696 pp.
- Dobkins, J.E. and Folk, R.L. 1970. Shape development on Tahiti-Nui. Journal of Sedimentary Petrology 40:129-143.

548 Druckenmiller, P.S., Russell, A.P. 2008. Skeletal anatomy of an exceptionally complete  
549 specimen of a new genus of plesiosaur from the Early Cretaceous (Early Albian) of  
550 northeastern Alberta, Canada. *Palaeontographica Abteilung A* 283: 1–33.

551 Druckenmiller, Patrick S., Russell, A.P. 2009. The new plesiosaurian genus  
552 *Nichollssaura* from Alberta, Canada: replacement name for the preoccupied genus  
553 *Nichollsia*. *Journal of Vertebrate Paleontology* 29: 276.

554 Eberth, D.A. 2005. The geology. pp. 54-82 in P.J. Currie and E.B. Koppelhus (eds.),  
555 Dinosaur Provincial Park: A Spectacular Ancient Ecosystem Revealed. Indiana  
556 University Press, Bloomington, Indiana.

557 Ellis, R. 2003. Sea dragons: predators of the prehistoric oceans. University of Kansas  
558 Press, Lawrence, Kansas. 313pp.

559 Everhart, M. J. 2000. Gastroliths Associated with Plesiosaur Remains in the Sharon  
560 Springs Member of the Pierre Shale (Late Cretaceous), Western Kansas. *Transactions*  
561 *of the Kansas Academy of Sciences* 103(1-2): 64-75.

562 Hales, Thomas C. (2012). *Dense Sphere Packings: A Blueprint for Formal Proofs*.  
563 London Mathematical Society Lecture Note Series. Vol. 400. Cambridge University  
564 Press.

565 Henderson, D. M. 1999. Estimating the masses and centers of mass of extinct animals  
566 by 3-D mathematical slicing. *Paleobiology* 25: 88-106.

- 567 Henderson, D. M. 2002. The eyes have it: the sizes, shapes, and orientations of  
568 theropod orbits as indicators of skull strength and bite force. *Journal of Vertebrate*  
569 *Paleontology* 22: 766-778.
- 570 Henderson, D. M. 2003. Effects of stomach stones on the buoyancy and equilibrium of a  
571 floating crocodilian: a computational analysis. *Canadian Journal of Zoology* 81: 1346-  
572 1357.
- 573 Henderson, D. M. 2006. Floating point: a computational study of buoyancy, equilibrium  
574 and gastroliths in plesiosaurs. *Lethaia* 39: 227-244.
- 575 Kepler, J. 1611. *Strena seu de nive sexangula* [The six-cornered snowflake] (in Latin),  
576 Paul Dry Books.
- 577 Kubo, T., Mitchell, M.T., and Henderson, D.M. 2012. *Albertonectes vanderveldei*, a new  
578 elasmosaur (Reptilia, Sauropterygia) from the Upper Cretaceous of Alberta. *Journal of*  
579 *Vertebrate Paleontology* 32: 557-572.
- 580 Schultheis, N.H. and Mountjoy, E.W. 1978. Cadomin conglomerate of western Alberta  
581 — a result of early cretaceous uplift of the main ranges. *Bulletin of Canadian Petroleum*  
582 *Geology* (1978) 26 (3): 297–342.
- 583 Taylor, M. A. 1993. Stomach stones - for feeding or buoyancy? The occurrence and  
584 function of gastroliths in marine tetrapods. *Philosophical Transactions of the Royal*  
585 *Society of London, Series B* 341: 163-175.
- 586 Tenney, S.M. & Tenney, J.B. 1970: Quantitative morphology of coldblooded lungs:  
587 *Amphibia and Reptilia. Respiratory Physiology* 9:197\_215.

- 588 Thompson, W. A., Martin, J. E. 2007. Comparison of gastroliths within plesiosaurs
- 589 (Elasmosauridae) from the Late Cretaceous marine deposits of Vega Island, Antarctic
- 590 Peninsula, and the Missouri River area, South Dakota, pp.147-153. In Martin, J.E. and
- 591 Parris, D.C. (eds.) The Geology and Paleontology of the Late Cretaceous Marine
- 592 Deposits of the Dakotas: Geological Society of America Special Paper 427.
  
- 593 Tsujita, C.S. 1995. Stratigraphy, taphonomy and paleoecology of the Upper Cretaceous
- 594 Bearpaw Formation in southern Alberta. PhD. Thesis, McMaster University, Hamilton,
- 595 Ontario.
  
- 596 Wings, O. 2007. [A review of gastrolith function with implications for fossil vertebrates](#)
- 597 [and a revised classification](#). Acta Palaeontologica Polonica 52(1): 1-16.

598



# **Table 1**(on next page)

Body model data (table 1) and gastrolith data (table 2)

1    Table 1. Summary of physical attributes of the four plesiosaur models. Ordering is alphabetical by genus.

	Body Length (m)	Total Body Mass (kg)	Lung Volume (L) <sup>1</sup>	Axial Body Mass (kg)	Single Arm Mass (kg) <sup>2</sup>	Single Leg Mass (kg) <sup>2</sup>	Centre of Mass (m) <sup>3</sup>
<i>Albertonectes vanderveldei</i> TMP2007.11.1	12.1	4810	43.8 (9.36%)	4480	115 (2.40%)	52.0 (1.08%)	(4.26, 0.579)
<i>Fluvionectes sloanae</i> TMP2009.37.68	5.21	392	24.2 (6.20%)	378	3.42 (0.875%)	3.54 (0.905%)	(1.84, 0.274)
<i>Nichollssaura borealis</i> TMP1994.122.1	2.86	135	10.7 (8.27%)	117	2.75 (2.17%)	2.19 (1.72%)	(1.26, 0.163)
cf. <i>Wapuskanectes</i> sp. Plesiosaur TMP2012.50.1	6.63	1120	84.3 (7.31%)	1090	32.0 (2.68%)	19.8 (1.67%)	(2.57, 0.356)

2    <sup>1</sup> Lung volume percentage expressed as a percentage of total axial body volume.

3    <sup>2</sup> Limb mass percentage expressed as a percentage of total body mass.

4    <sup>3</sup> Centre of mass expressed as (X,Y) where X is the distance from tip of tail and Y is the height above the

5    ventral-most part of the axial body.

6

7

8

9 Table 2. Observed and estimated gastrolith data for the plesiosaurs in the present study. See Methods  
10 and Results for derivations of Predicted Missing Mass. Ordering is alphabetical by genus. Total Gastrolith  
11 Mass as a percentage of Total Body Mass (Table 1) is shown in parentheses.

	Measured/Observed Mass (gm)	Predicted Missing Mass (gm)	Total Gastrolith Mass (gm)	Largest Single Gastrolith (gm)
<i>Albertonectes</i> <i>vanderveldei</i> TMP2007.11.1	4980	4310	9290 (0.193%)	1130
<i>Fluvionectes</i> <i>sloanae</i> TMP2009.37.68	359	†	359 (0.0916%)	15.3
<i>Nichollssaura</i> <i>borealis</i> TMP1994.122.1	††	105	105 (0.0778%)	9.96
<i>Wapuskanectes</i> sp. TMP2012.50.1	††	497	497 (0.0444%)	14.5



12 †All *Fluvionectes* stones could be weighed, so no estimate needed.

13 ††None of the stones were fully visible, so no sets of observable triaxial measurements possible.

# Figure 1

Geographic locations of the four Cretaceous plesiosaurs from the province of Alberta, Canada discussed in the text.

Geographic locations of the four Cretaceous plesiosaurs from the province of Alberta, Canada discussed in the text. (A) *Albertonectes vanderveldei* TMP2007.11.1, Bearpaw Formation, late Campanian. (B) *Fluvionectes sloanae*, TMP2009.37.68, Dinosaur Park Formation, late Campanian. (C) *Nichollsaura borealis* TMP1994.122.1, Clearwater Formation, early Albian. (D) *Wapuskanectes betsynichollsae* TMP2011.88.1 and TMP2012.50.1, Clearwater Formation, early Albian. (B) Stratigraphic positions of the four plesiosaurs. Dorsal silhouettes are to scale with *A. vanderveldei* at 12m. Chronostratigraphic chart after Cohen *et al.* (2013), with the numbers on the righthand side indicating boundary ages in millions of years.



# Figure 2

*Albertonectes vanderveldei* TMP2007.11.1 (Kubo et al., 2010).

(A) View of the original downside in the field and the best preserved side as it experienced the least disruption by scavenging sharks. (B) Detail of midbody region showing the large gastroliths that settled downwards onto the inside of the right, dorsal ribs. This region was hit by the excavator bucket with the partial loss of ribs and an unknown number of gastroliths. Fortuitously, the broken blocks hosting gastroliths can be removed and their contents inspected from several sides. Scalebar is 10cm.



# Figure 3

*Fluvionectes sloanae* TMP2009.37.68 (Campbell et al.,2021).

(A) Recovered skeletal and gastrolith material with the gastroliths arranged in a grid at the lower right. (B) Full complement of gastroliths removed from inside the rib cage of TMP2009.37.68 during preparation. This view is an enlargement of the gastrolith grid seen in (A).





B



# Figure 4

*Nichollsaura borealis* TMP1994.122.1 (Druckenmiller and Russell, 2009).

(A) Dorsal view of the specimen which was found intact with its limbs fully outstretched. The left fore flipper, the phalanges of the right pes, the left proximal third of the cervical ribs, and the left anterior dorsal ribs are restored. (B) Internal, ventral view of TMP1994.122.1 produced by a rock saw cut, originally intended to remove excess matrix, that fortuitously exposed the dorsal and ventral components of the axial skeleton and enclosed gastroliths (highlighted with white outlines).



# Figure 5

An incomplete specimen of *Wapuskanectes betsynichollsae* TMP2011.88.1 that has a large number of gastroliths visible.

(A) Posterior cervical and anterior dorsal vertebrae in left lateral view, the pectoral girdle in ventral view and the left humerus, together with an intact collection of gastroliths located at the posterior end of the pectoral girdle (circled). Large scale bar at right glenoid is 10cm. The maximum pectoral width of this specimen, 57 cm, is identical that of TMP2012.50.1. (B) Close up the gastroliths found with TMP2011.88.1.






# Figure 6

A more complete specimen of *Wapuskanectes betsynichollsae*. TMP2012.50.1.

(A) Dorsal view of the originally upside down remains recovered from north of the town of Fort McMurray, Alberta. The head and most of the neck were lost when intercepted by a grader during road construction. The right flipper was lost sometime in the Early Cretaceous prior to the final burial of the body. (B) The pelvic and abdominal regions of TMP2012.50.1 showing gastroliths (black arrows) within the body cavity that settled between the ribs of the inverted carcass and hint at a more substantial collection that is hidden inside the body cavity. Scale bars on body regions are 10cm.









# Figure 7

Three-dimensional, digital models of the four plesiosaurs analyzed in the present study.

The models were used for calculation of body mass estimates. The model of *Wapuskanectes* is based on the more complete TMP2012.55.1. The model of *Fluvionectes* is based on the full body outlines drawn by Campbell *et al.* (2021). Hollow lung volumes are indicated by the dark grey shapes in the chest regions. Limb and axial body densities were set to 1050 gm/l, except for the necks (medium grey) which were set to 900 gm/l to account for the empty space occupied by the tracheal and esophageal volumes. Black '+' signs indicate the centres of mass computed for the combined axial body, lungs and limbs and incorporates the regional density differences. See Table 1 for the physical parameters determined for the models.










# Figure 8

Histograms showing the very different mass distributions of the sets of gastroliths found with the plesiosaurs of the present study.


Note that the *Albertonectes* analysis is done twice: first encompassing the full mass range of its stones, and second only applying the smaller mass range of 0 – 16 gm that was also used with the other plesiosaurs. Only the stones masses of *Fluvionectes* were weighed directly. The other masses came from estimation techniques. See Methods and Results for details. Note that the maximum frequency range of each histogram plot is different to make the detailed counts visible.




# Figure 9

Pie charts showing the relative proportions by mass of the different shapes of the gastroliths recovered from the four plesiosaur specimens using the shape categories of Dobkins and Folk (1970).


*Fluvionectes* is distinguished from the others by the high fraction of discoid gastroliths and may reflect its being found in fluvial sediments. *Nichollssaura* and *Wapuskanectes* both come from the same formation and show very similar gastrolith shape distributions that are dominated by spherical pebbles.




*Albertonectes vanderveldei*  
 TMP 2007.11.1  
 Bearpaw Fm.  
 U. Cretaceous  
 Southern Alberta



*Fluvionectes sloanae*  
 TMP 2009.37.68  
 Dinosaur Park Fm.  
 U. Cretaceous  
 Southern Alberta



*Nichollssaura borealis*  
 TMP 1994.122.1  
 Clearwater Fm.  
 L. Cretaceous  
 Northern Alberta




*cf. Wapuskanectes sp.*  
 TMP 2011.88.1  
 Clearwater Fm.  
 L. Cretaceous  
 Northern Alberta


# Figure 10

Pie charts showing the relative proportions by absolute counts of the different shapes of the gastroliths recovered from the four plesiosaur specimens using the shape categories of Dobkins and Folk (1970).


The higher number of xiphoid clasts with *Albertonectes* contrasts with their lower total mass fraction (Fig. 9) and shows that these clasts tend to be small. *Fluvionectes* still shows a majority of discoid gastroliths. *Nichollssaura* and *Wapuskanectes* continue to show the same pattern of having mainly spherical gastroliths.




*Albertonectes vanderveldei*  
 TMP 2007.11.1  
 Bearpaw Fm.  
 U. Cretaceous  
 Southern Alberta



*Fluvionectes sloanae*  
 TMP 2009.37.68  
 Dinosaur Park Fm.  
 U. Cretaceous  
 Southern Alberta



*Nichollssaura borealis*  
 TMP 1994.122.1  
 Clearwater Fm.  
 L. Cretaceous  
 Northern Alberta



*cf. Wapuskanectes* sp.  
 TMP 2011.88.1  
 Clearwater Fm.  
 L. Cretaceous  
 Northern Alberta


# Figure 11

Maximum plesiosaur gastrolith size and total gastrolith mass plotted as functions of body mass for the four animals of the present study.

Although based on a sample of just four animals, larger plesiosaurs appear to have a larger maximum stone size and greater total mass of stones than smaller plesiosaurs. See Table 1 for body mass data and Table 2 for stone mass data. Logarithmic plotting is used as both body masses and stone masses span approximately two orders of magnitude. Abbreviations: Alb – *Albertonectes vanderveldei*, Flu – *Fluvionectes sloanae*, Nic – *Nichollssaura borealis*, Wap – *Wapuskaneptes betsynichollsae*.



Largest Gastrolith vs Body Mass



Total Gastrolith Mass vs Body Mass

