

Quantitative heterodonty in Crocodylia: assessing size and shape across modern and extinct taxa

Domenic C D'Amore ^{Corresp., 1}, **Megan Harmon** ¹, **Stephanie K Drumheller** ², **Jason J Testin** ³

¹ Department of Natural Sciences, Daemen College, Amherst, NY, United States

² Department of Earth and Planetary Sciences, University of Tennessee - Knoxville, Knoxville, Tennessee, United States

³ Department of Physical Science, Physics and Pre-Engineering, Iowa Western Community College, Council Bluffs, IA, United States

Corresponding Author: Domenic C D'Amore

Email address: ddamore@daemen.edu

Heterodonty in Crocodylia and closely related taxa has not been defined quantitatively, as the teeth rarely have been measured. This has resulted in a range of qualitative descriptors, with little consensus on the condition of dental morphology in the clade. The purpose of this study is to present a method for the quantification of both size- and shape-heterodonty in members of Crocodylia. Data were collected from dry skeletal and fossil specimens of 34 crown crocodylians and one crocodyliform, resulting in 21 species total. Digital photographs were taken of each tooth and the skull, and the margins of both were converted into landmarks and semilandmarks. We expressed heterodonty through Foote's morphological disparity, and a principal components analysis quantified shape variance. All specimens sampled were heterodont to varying degrees, with the majority of the shape variance represented by a 'caniniform' to 'molariform' transition. Heterodonty varied significantly between positions; size undulated whereas shape was significantly linear from mesial to distal. Size and shape appeared to be primarily decoupled. Skull shape correlated significantly with tooth shape. High size-heterodonty often correlated with very large caniniform teeth, reflecting a prioritization of securing prey. Large, highly molariform, distal teeth may be a consequence of high-frequency durophagy combined with prey size. The slender-snouted skull shape correlated with a caniniform arcade with low heterodonty. This was reminiscent of other underwater-feeding tetrapods, as they often focus on small prey that requires minimal processing. Several extinct taxa were very molariform, which was associated with low heterodonty. The terrestrial peirosaurid shared similarities with large modern crocodylian taxa, but may have processed prey differently. Disparity measures can be inflated or deflated if certain teeth are absent from the tooth row, and regression analysis may not best apply to strongly slender-snouted taxa. Nevertheless, when these methods are used in tandem they can give a complete picture of crocodylian heterodonty. Future researchers may apply our proposed method to most crocodylian

specimens with an intact enough tooth row regardless of age, species, or rearing conditions, as this will add rigor to many life history studies of the clade.

TITLE: Quantitative heterodonty in Crocodylia: assessing size and shape across modern and extinct taxa.

AUTHORS: Domenic C. D'Amore*¹, Megan Harmon¹, Stephanie K. Drumheller², Jason J. Testin³

1. Department of Natural Sciences, Daemen College, 4380 Main Street, Amherst, New York 14226 United States of America

2. Department of Earth and Planetary Sciences, University of Tennessee, 1621 Cumberland Avenue, 602 Strong Hall, Knoxville, Tennessee 37996 United States of America

3. Department of Physical Science, Physics and Pre-Engineering, Iowa Western Community College, 2700 College Road, Council Bluffs, Iowa, 51503 United States of America

***Corresponding Author:** Domenic C. D'Amore, ddamore@daemen.edu

13 **ABSTRACT**

14 Heterodonty in Crocodylia and closely related taxa has not been defined quantitatively, as the
 15 teeth rarely have been measured. This has resulted in a range of qualitative descriptors, with
 16 little consensus on the condition of dental morphology in the clade. The purpose of this study is
 17 to present a method for the quantification of both size- and shape-heterodonty in members of
 18 Crocodylia. Data were collected from dry skeletal and fossil specimens of 34 crown crocodylians
 19 and one crocodyliform, resulting in 21 species total. Digital photographs were taken of each
 20 tooth and the skull, and the margins of both were converted into landmarks and
 21 semilandmarks. We expressed heterodonty through Foote's morphological disparity, and a
 22 principal components analysis quantified shape variance. All specimens sampled were
 23 heterodont to varying degrees, with the majority of the shape variance represented by a
 24 'caniniform' to 'molariform' transition. Heterodonty varied significantly between positions; size
 25 undulated whereas shape was significantly linear from mesial to distal. Size and shape
 26 appeared to be primarily decoupled. Skull shape correlated significantly with tooth shape. High
 27 size-heterodonty often correlated with very large caniniform teeth, reflecting a prioritization of
 28 securing prey. Large, highly molariform, distal teeth may be a consequence of high-frequency
 29 durophagy combined with prey size. The slender-snouted skull shape correlated with a
 30 caniniform arcade with low heterodonty. This was reminiscent of other underwater-feeding
 31 tetrapods, as they often focus on small prey that requires minimal processing. Several extinct
 32 taxa were very molariform, which was associated with low heterodonty. The terrestrial
 33 peirosaurid shared similarities with large modern crocodylian taxa, but may have processed
 34 prey differently. Disparity measures can be inflated or deflated if certain teeth are absent from

the tooth row, and regression analysis may not best apply to strongly slender-snouted taxa. Nevertheless, when these methods are used in tandem they can give a complete picture of crocodylian heterodonty. Future researchers may apply our proposed method to most crocodylian specimens with an intact enough tooth row regardless of age, species, or rearing conditions, as this will add rigor to many life history studies of the clade.

INTRODUCTION

What constitutes heterodonty in vertebrates is often difficult to delineate, with different qualitative definitions in place depending on the clade being studied (Shimada, 2001). Kieser et al. (1993, p.195) referred to the definition of heterodonty as “a bone of contention,” and since then the issue has not been fully resolved. Arguably, this lack of clarity is most pronounced within members of Crocodylia. Researchers have often referred to crocodylians as homodont (Langston, 1973; Osborn, 1998; Larsson & Sidor, 1999; Zahradnicek et al., 2014). Peyer (1968 p.17) defined the term as lacking the discrete dental categories seen in mammals (incisors, canines, premolars, molars), even though he admitted “a sharp distinction between homodont and heterodont is not possible.” Ferguson (1981) referred to *Alligator mississippiensis* as “pseudoheterodont,” because it showed a gradual, as opposed to punctuated, change in tooth shape along the tooth row (see also Grigg and Gans, 1993; Hendrickx, Mateus, & Araújo, 2015a). Size variability along the tooth row has motivated the term “heterometric homodonty” for *Crocodylus niloticus* (Fruchard, 2012). Others have applied anisodonty to the clade, which is an apparent change in tooth size but not shape (Vullo et al., 2016). Certain fossil crocodylians,

often interpreted as herbivores or omnivores, exhibit multi-cusped and/or grinding teeth, and are specifically called “heterodont” crocodyliforms by researchers (e.g. Martin, 2007; Ósi, Clark, & Weishampel, 2007; Novas et al., 2009; Ósi, 2014). Lastly, some researchers have argued certain modern crocodylians are actually heterodont, and claim dental categories do in fact exist (Aoki, 1989; Kieser et al., 1993).

Semantics aside, one reason for the lack of resolution concerning crocodylian heterodonty is that their teeth rarely have been measured. Few studies have performed quantitative shape analyses of crocodylian teeth. Of these, linear-distance measures have been used for fossil identification (Frey & Monninger, 2010), replacement rates (Bennett, 2012), and biomechanical analyses (Monfroy, 2017). Aside from a study evaluating two fossil notosuchians (Lecuona & Pol, 2008), and a preliminary geometric morphometric investigation of *Crocodylus niloticus* (Farrugia, Polly, & Njau, 2016), no studies have quantitatively investigated heterodonty either within or between species. Typically, crocodylian dentition is described qualitatively, with the goal of characterization for phylogenetic analysis, or paleoecological inference (e.g. Schwarz-Wings, Rees, & Lindgren, 2009; Young et al., 2012; Salas-Gismondi et al., 2015; Adams, Noto, & Drumheller, 2017). Qualitative descriptors of crocodylian tooth morphology are numerous, and include terms such as “blunt,” “bulbous,” “broadened,” “button-shaped,” “conical,” “globular,” “fang,” “kidney-shaped,” “lanceolate,” “needle-like,” “procumbent,” “pseudocanine,” “robust,” “short,” “slender,” “spike-like,” and “thick” (e.g. Brazaitis, 1973; Groombridge, 1982; Aoki, 1989; Brochu, 1999; Erickson, Lappin, & Vliet, 2003; Ósi, Clark, & Weishampel, 2007; Schwarz-Wings, Rees, & Lindgren, 2009; Fruchard, 2012; Gignac & Erickson, 2014; Salas-Gismondi et al., 2015; Berkovitz and Shellis, 2017). There is clearly a gap in our

knowledge concerning the nature of dental morphology in this clade, and closing this gap may be crucial for a more complete understanding of performance, behavior, and trophic ecology within Crocodylia, as well as more distantly related, crocodylian-line archosaurs.

The lack of quantitative studies on heterodonty in crocodylians and closely related taxa is not due to a lack of applicable methodology, as there has been a burst of morphometric research in non-mammalian teeth in the past decade. Dinosaur teeth have probably received the most attention, with multiple studies using linear-distance measures for the identification of loose fossil crowns or to infer functional paleoecology (D'Amore, 2009; Larson & Currie, 2013; Buckley and Currie, 2014; Hendrickx and Mateus, 2014; Torices, Reichel, & Currie, 2014; Hendrickx, Mateus, & Araújo, 2015b, Gerke and Wings, 2016; Larson, Brown, & Evans, 2016). Similar measurements have been taken from a number of extinct marine reptiles (Foffa et al., 2018). Extant reptiles have been investigated quantitatively as well, including colubrid snakes (Britt, Clark, & Bennett, 2009; Juarez & D'Amore, 2018) and varanid lizards (D'Amore, 2015). Prior to this, sharks were studied heavily (Shimada, 2002b, 2004; Shimada and Seigel, 2005; Ciampaglio, Wray, & Corliss, 2005). These morphometric analyses have shed light on the nature of heterodonty, dental allometry, and ecomorphology in these vertebrates, and similar methods may be applied to Crocodylia to clarify the state of heterodonty in this taxon.

The purpose of this study is to present a method for the quantification of both size- and shape-heterodonty in members of Crocodylia. Data were collected from a multispecific sample of both extant and extinct specimens housed in museum collections, and their tooth morphology was assessed through two-dimensional geometric morphometric methods. In

addition to this major goal, we also 1) outline and describe dental morphology within the specimens sampled; 2) report any morphological consistencies found within the members of our sample; and 3) present the advantages, limitations, and potential future uses of the method. Our intention is to put forward a method for assessing heterodonty that may be applicable to most crocodylian specimens, and may allow for direct comparisons between crocodylians and a variety of other terrestrial and aquatic tetrapods.

MATERIALS AND METHODS

Institutional abbreviations

American Museum of Natural History, New York, NY (AMNH); Royal Ontario Museum, Toronto, ON (ROM); University of California Museum of Paleontology, Berkeley, CA (UCMP)

Nomenclature

Crocodylian teeth have very few discrete homologous anatomical loci, but, because they exhibit thecodont dentition (sensu Edmund, 1962, 1969), we defined them as having a crown with an apex, a neck, and a root within an alveolus. Nomenclature for tooth morphology used here was proposed by Smith & Dodson (2003; Figure 1A-B): mesial, towards the point where the premaxillae meet at the midline, or towards the mandibular symphysis; distal, away from the medial premaxillae or the mandibular symphysis; lingual, towards the tongue; labial, towards the “lips”; basal, towards the base of the tooth or alveolus; apical, away from the alveolus or towards the apex. Crocodylians are known for a condition where a large tooth may be surrounded by much smaller ones. This large tooth is typically referred to as a procumbent

119 tooth (Gignac & Erickson, 2014) or a pseudocanine (Brochu, 1999), but we simply refer to it as
120 ‘enlarged.’

121 Tooth position was indicated by either the presence of a tooth or an empty alveolus in
122 the host bone (Figure 1A). Teeth were lettered based on the host bone (premaxilla = P, maxilla
123 = M, dentary = D), and numbered in ascending order from mesial to distal positions (the mesial-
124 most dentary tooth was D1, followed by D2, D3, etc.). For consistency, all specimens were
125 assumed to have five premaxillary positions (P1–P5) (Berkovitz & Shellis, 2017). Members of
126 *Paleosuchus* and *Osteolaemus* have only four premaxillary teeth during early stages of
127 ontogeny (Brochu and Storrs, 2012; Narvaez et al., 2015), and an alveolus may atrophy in
128 certain species (usually P2) as they grow (Webb & Messel, 1978; Brown et al., 2015; DC
129 D’Amore, personal observation). If only four premaxillary positions were present, position P2
130 was assumed absent, and skipped over during numbering. In one case, a specimen had six
131 premaxillary teeth (*Alligator mississippiensis*, ROM 4408). This tooth position (P6) was omitted
132 for consistency. Our *Alligator prenasalis* specimen (ROM 1375) had its distal-most cranial
133 positions obscured by poor preservation and matrix. We therefore based its maxillary tooth
134 count on previous osteological accounts (a total of 15 maxillary teeth based on Harvard
135 Museum of Comparative Zoology specimen #1015, Mook, 1932).

136 Specimens

137 Data were collected from 20 species of crown crocodylians, and one species of peirosaurid
138 crocodyliform (Supplemental Information Table S1). We included the later as it was readily
139 available with excellent tooth preservation, and allowed us to consider if characteristics

indicative of crocodylian heterodonty may be found in species outside the crown clade. The end result was 27 extant and eight extinct specimens, from which we measured 1,263 teeth in total. Although *Caiman crocodilus* is extant, a fossil specimen (UCMP 42844) was also included. Although we did not use any distinct criteria to distinguish juveniles from adults, larger specimens were selected when possible. We chose specimens with the most complete tooth rows in the collections, in that they had the most tooth positions represented by measurable teeth on at least one side of the mouth. Because of normal tooth replacement, post-mortem damage, and/or poor preservation, the percentage of tooth positions represented by measurable teeth was highly variable (Supplemental Information Table S2). Modern specimens had tooth rows with 42-100% of their tooth positions represented, and fossil tooth rows ranged 30-78%. Certain fossil specimens only had cranial (*Alligator prenasalis* ROM 1375, *Borealosuchus sternbergii* UCMP 126099, “*Crocodylus*” *affinis* UCMP 131090, *Hamadasuchus rebouli* ROM 52620, *Leidyosuchus canadensis* ROM 1903) or dentary (*Borealosuchus sternbergii* UCMP 131769) material to sample. This variability allowed us to consider in what way the degree of incompleteness along the tooth row may affect the proposed method, as incomplete tooth rows may be common in collections.

Tooth data collection

Methods were similar to those proposed by D’Amore (2015). We photographed each tooth using either an Olympus Stylus or a Canon Rebel T3 EOS camera with a non-zoom lens. Skulls were positioned on a flat surface with a dark background such as a tabletop or camera stand, and held stationary by an available prop such as a box or sandbag if necessary. A scale was

positioned at the same distance from the camera as the tooth. The camera was either mounted on a camera stand, or was held stationary by a researcher (for larger specimens). Digital photographs were taken from the labial perspective (Figure 1B). For each tooth, we positioned the specimen so the camera lens was parallel to the host bone adjacent to the tooth. This resulted in both carinae being visible in the shot (if present). We simultaneously positioned the lens parallel to the apical-basal long axis, determined qualitatively as when the tooth looked its tallest to the photographer regardless of any labio-lingual curvature. Each tooth was photographed separately, and teeth from both sides were photographed if available. Only fully erupted teeth with the neck visible were included (Figure 1B). Tooth quality was variable in extant specimens. Teeth with slightly worn apices were included. As the outline of the tooth margin was our basis of measurement, we omitted any teeth with large wear facets or chips that largely interrupted this margin. Cracks down the long axis of the teeth were common, and were omitted if the crack distorted the shape of the tooth or resulted in a space where light could be seen from the other side.

We used a sliding semilandmark analysis (Bookstein, 1997; Sheets, Kim, & Mitchell 2004; Zelditch et al., 2004; Mitteroecker et al., 2013) to derive shape measurements from each tooth's outline. Photographs were entered in TpsDig 2.16, and the margin of the tooth was traced using the curve drawing tool (Rohlf, 2010) (Figure 1B). Because the enamel margin was not always clear, each tooth was traced from apex to the point where the tooth ceased to taper on the neck for both the mesial and distal side. TpsDig then transformed each of the two traced margins into 30 equidistant coordinates, and we combined the apical-most coordinates. This resulted in three discrete landmarks (two at the base and one at the apex) and 56

semilandmarks (Figure 1B). This number of coordinates has been used in previous studies of both dinosaur (Smith, Vann, & Dodson, 2005) and monitor lizard (D'Amore, 2015) dentition, as well as claw morphology (Tinius and Russel, 2016; D'Amore et al., 2018), in which it has been shown to accurately represent the totality of two-dimensional shape (Tinius and Russel, 2016). We calculated centroid size (CS), and performed a generalized least squares Procrustes (GLSP) superimposition while sliding the semilandmarks to minimize the total bending energy (Perez, Bernal, & Gonzalez, 2006; Gunz & Mitteroecker, 2013), using the program TpsRelw 1.53 (Rohlf, 2013).

Skull data collection

The shape of the skull, and particularly the rostrum, has long been considered both an important phylogenetic and ecomorphological feature in crocodylians (Busbey, 1995; Daniel & McHenry, 2001; Brochu, 2001; Sadleir & Makovicky, 2008; Salas-Gismondi et al., 2016; Drumheller, Wilberg, & Sadler, 2016; Wilberg, 2017). We attempted to determine if there was a correlation between tooth morphology and head shape, as these traits may be linked. All specimens' skulls were photographed from the dorsal perspective using the same cameras as above (Figure 1C). Each skull was positioned so the palate was parallel with the tabletop, and the camera was positioned with a camera stand and leveled. A scale was included. We derived skull shape data using a modified version of our technique for tooth outlines. Using TpsDig again, we traced the skull margin from the rostral-most point of contact between the premaxillae to the caudal-most quadratojugal along the margin on each side (Figure 1C). We chose this margin because it outlined the shape of the head as close to as it would have

appeared in life as possible, but avoided internal structures such as the jaw articulations or occipital condyles. Each margin was broken into 50 equidistant coordinates, and the rostral-most coordinates were combined. This resulted in three landmarks (two at the quadratojugals and one at the premaxillary junction) and 97 semilandmarks (Figure 1C). These also underwent a GLSP superimposition and the semilandmarks were slid to minimize the total bending energy using TpsRelw 1.53. In specimens with damaged or missing bones on one side, bilateral symmetry was assumed and the coordinates on the intact side were mirrored. This was achieved by placing another landmark along the mid-sagittal plane at the caudal-most point available. This landmark and the one at the premaxillary junction resulted in a plane that the landmarks were mirrored against.

A body-size metric was needed for several of the following analyses, but unfortunately few were available for all specimens. Commonly used metrics such as snout-vent length and mass were not recorded for most dry skeletons prior to cataloging, and many specimens (especially fossils) lacked femora (see Farlow et al., 2005). Therefore, the length of the skull was used as a body size metric (see Fukuda et al. 2013 for potential influences on this measurement). We derived skull length from the same landmarks outlining the skull above; it was the linear distance from the rostral-most landmark to the posterior-most landmarks along the mid-sagittal plane (Figure 1C). (Note: *Borealosuchus sternbergii* UCMP 131769 and *Crocodylus niloticus* AMNH 142494 did not have intact skulls, and were therefore omitted from all analyses involving skull data.)

Statistical approaches

All analyses were conducted in MorphoJ v. 106d (Klingenberg 2011), SPSS Version 19.0 [IBM Corp, Armonk, NY], and PAST (Hammer, Harper, & Ryan, 2001). If both left and right teeth were available at a given position, we averaged them. For size, CS values were simply averaged together. For shape, each x-y coordinate of the GLSP superimposed landmarks and semilandmarks was averaged with its counterpart for both teeth. To ensure that the left and right sides were not significantly different, we ran a 10,000 permutations test on the Procrustes distances between left and right teeth at positions that had both. This test failed to reject the null hypothesis of bilateral symmetry ($p = 0.6785$). If only one tooth was available for a given position, that tooth alone represented said position.

We tested the null hypothesis that there was no statistical difference between tooth rows in our sample. We ran a 10,000 permutations test on the Procrustes distance between cranial (premaxilla and maxilla) and dentary teeth for those that had both.

Skull shape and tooth orientation may be irregularly influenced by captive rearing (Erickson et al., 2004; Drumheller, Wilberg, & Sadleir, 2016), and how this influences tooth shape in crocodylians has yet to be determined. All the modern specimens sampled in this study were categorized as wild caught or ‘no data’ (Supplimental Information Table S2). The latter category indicated the host museum did not know the living conditions of the specimen while alive, and could mean (but does not guarantee) that the specimen was captive raised. To determine if rearing conditions influenced our shape data, we ran a 10,000 permutations test on the Procrustes distances between wild caught and ‘no data’ specimens in MorphoJ. We

excluded *Gavialis gangeticus*, *Mecistops cataphractus*, and *Tomistoma schlegelii*, as they represent an extreme cranial condition and only one individual of each species was available.

A singular measure of heterodonty was derived for each specimen in the form of Foote's morphological disparity [$MD = (\sum_{i=1}^m D_i^2) / (m - 1)$] (Foote, 1993; Zelditch, Sheets, & Fink, 2003; Sheets & Zelditch, 2013). Disparity (MD) was the sum of the differences of the values of a given tooth (i) from the mean for all teeth from that single specimen (D_i , also known as the grand mean) squared, with the number of tooth positions (m) factored in. We calculated disparity for all occupied tooth positions for each specimen. For size-heterodonty, D_i was simply the difference in CS of a tooth from the mean of the specimen (Zelditch et al., 2004). For shape-heterodonty D_i was the Procrustes distance between the tooth and the mean, and was calculated using DisparityBox7 (Sheets, 2012). Heterodonty then was regressed with reduced major axis against skull length to determine if there was a significant allometric change in the clade. To test if the more incomplete tooth rows were strongly affecting heterodonty, we ran both regressions a second time, yet only included specimens that had no less than 70% of their tooth rows represented by measurable teeth. If the regression statistics were similar to when all specimens were included, this would suggest incompleteness had a minor effect on our results.

We attempted to correlate skull shape to tooth shape between individuals by using a two-block partial least squares (PLS) analysis in MorphoJ. Skull shape represented one block, and average tooth shape represented the other. Average tooth shape was constructed by averaging the corresponding GLSP superimposed landmarks and semilandmarks of every tooth

from an individual. The scores for the first PLS of each shape block were plotted against one another and regressed with a reduced major axis. Visualization of variation along each PLS axis was depicted through vector diagrams.

To determine if size and shape were coupled, regression scores of full shape data were generated by MorphoJ (as described in Drake and Klingenberg, 2008) and regressed against CS using a reduced major axis. Significance and a high goodness of fit would be indicative of strong coupling between size and shape. A principal component analysis (PCA) was then conducted to visualize the degree of shape variance within all cranial and dentary teeth. PC scores were represented in bivariate plots, and the shape variation of each PC axis was visualized using vector diagrams.

As heterodonty is defined here as variability along the tooth row, we attempted to evaluate the nature of this variability between tooth positions. We used an analysis of variance (ANOVA) to determine if the teeth differed significantly in CS between positions for all specimens sampled. This size metric had unequal variances according to Levene's test, so we specifically ran a Welch's ANOVA. As shape is inherently a multivariate measure, we ran a multivariate analysis of variance (MANOVA) comparing shape between positions. As some specimens had fewer tooth positions than others, the number of teeth occupying the distal-most positions ended up being low. These positions were excluded from the statistical tests, resulting in the only positions considered having at least 7 teeth. To visually represent variability by position, we plotted size and shape against tooth position in a series of box plots. For size, CS was normalized by dividing it by skull length (so as to not obscure the degree of

variability in smaller specimens), and then was plotted against tooth position. For shape, PC scores of biologically relevant PCs were plotted against tooth position in a similar fashion.

Preliminary quantitative work has suggested a linear transition in tooth shape along the arcade from mesial to distal (Farrugia, Polly, & Njau, 2016). We test this by regressing shape data against tooth position using ordinary least squares regressions for each individual. To standardize these regressions, we normalized tooth position into a proportion. We numbered the positions along the tooth row starting with 1 at the mesial-most position, divided each by the total number of positions along the arcade, and then subtracted 0.5 (this subtraction placed the y-intercept halfway along the arcade without affecting any ensuing statistics). PCs for each tooth were then regressed against this, and regression statistics were collected. Several factors may be implied by a significantly linear crocodylian tooth row. Slope may be linked to heterodonty, as a steeper slope would imply more shape change along the PC1 scores at the y-axis and consequently greater shape-heterodonty. The y-intercept represented the shape value at the median position, as the intercept was located half-way along the tooth row. This allowed for direct shape comparison between all taxa regardless of whether or not the tooth was actually present at said position. To visualize these coefficients, we plotted both slope and y-intercept for each regression in scatterplots for both the cranium and the dentary.

Results:

Shape variability in the sample

No statistically significant difference was found between cranial and dentary tooth rows ($p=0.2455$) or wild caught versus 'no data' modern specimens ($p=0.4229$), failing to reject the

308 null hypothesis under both circumstances. When regression scores were plotted against CS,
309 the regression had a goodness of fit accounting for less than 10% of the variance ($y=0.313x-$
310 0.981 ; $r^2=0.09$; $p<0.0001$; $95\% = 0.296, 0.328$).

311 Most of the shape variance in Crocodylia was along a single PC axis. PC1 accounted for
312 over 92.11% of the variance (Supplemental information Table S3). The shape changes towards
313 negative PC1 scores include apical-basal elongation, narrowing at the base, and a gentle
314 concavity on the distal margin (Figure 2A). For simplicity, we will refer to this extreme as
315 ‘caniniform’ (Erickson et al., 2012; 2014; Gignac & Erickson, 2014). Positive shape changes
316 depicted an apical-basal shortening and mesial-distal broadening, and we will refer to the
317 extreme as ‘molariform’ (Erickson et al., 2012; 2014; Gignac & Erickson, 2014). We describe
318 PC2 (3.22% of the variance) as the orientation of the tooth, or how much it ‘leans’ (Figure 2A).
319 Positive values indicate the apex leaning in the mesial direction, and negative values indicate a
320 lean in the distal direction. Note that this is not a measure of curvature, as neither margin
321 changes its concavity or convexity. We do not consider any other PCs, as the amount of
322 variance represented by them is very low (Supplemental Information Table S3).

323 Figure 2B illustrates the morphospace produced by PC1 and PC2 scores. At the
324 superfamily level, there was a large amount of overlap between alligatoroids and crocodyloids.
325 Most specimens had teeth ranging a large portion of the PC1 score spectrum, with little
326 separation between them. The only exceptions were some crocodyloid teeth below PC1 scores
327 of -0.2. Both *Borealosuchus sternbergii* tooth rows had PC1 scores between -0.22 and 0.20, and
328 *Hamadasuchus rebouli* ranged between -0.19 and 0.23. These were nested within the

alligatoroids and crocodyloids. *Gavialis gangeticus* deviated from the rest in that most teeth had PC1 scores of <-0.20 (Figure 2B). PC2 scores did not differ between groupings of taxa, as each group occupied most of the shape range.

Skull vs. tooth morphology

Skull and average tooth shape were significantly correlated. For the two-block PLS test, PLS1 encompassed 99.96% of total covariation and had a correlation coefficient of 0.7937. Shape variability within the skull shape block showed the snout transitioning from narrow to broad (Figure 3A). Taxa that occurred below a PLS1 score of -0.15 were the slender-snouted taxa as defined by Brochu (2001), including *Gavialis gangeticus*, *Mecistops cataphractus*, and *Tomistoma schlegelii*. The remainder of the species, defined as either generalized or blunt-snouted (also by Brochu, 2001), occurred around the mean and positive half mixed together. Shape variability within the tooth shape block was similar to the above PCA of tooth shape, displaying a transition from caniniform to molariform with increasing values (Figure 3A). These blocks regressed significantly against one another (Figure 3B), with slender-snouted taxa separating out with the most caniniform teeth. Scatter increased around the means, indicating the correlation was not as strong among the generalized-to-blunt snouted taxa. *Alligator prenasalis*, *Brachychampsia* sp., and "*Crocodylus*" *affinis* were all relatively blunt-snouted, but rose noticeably above the regression. This suggested they possessed much more molariform teeth on average than their counterparts of similar skull shape.

Footnote's disparity and heterodonty

Size-heterodonty was significantly correlated with skull length, with an r^2 of 0.760. The largest individuals according to skull length (members of *Crocodylus niloticus* and *Crocodylus porosus*) possessed the greatest unadjusted size-heterodonty (Figure 4A). Members of *Alligator* had negative residual size heterodonty, with *Alligator prenasalis* as the lowest. On the other side of the regression, residuals of caimanine specimens (*Caiman*, *Paleosuchus*) were all positive with the exception of one individual. Several members of *Crocodylus* had values around or below zero, but one *Crocodylus porosus* specimen had a high residual. One *Osteolaemus tetraspis* individual had the highest size-heterodonty residual, with the other close to the regression. *Hamadasuchus rebouli* had positive residuals, similar to the larger *Crocodylus porosus* and the caimanine specimens. The slender-snouted taxa (*Gavialis gangeticus*, *Mecistops cataphractus*, *Tomistoma schlegelii*) had some of the more negative residuals. For the regression excluding individuals with less than 70% of either tooth row represented, the regression statistics ($y=2.208x-8.583$; $r^2=0.770$; $p<0.0001$) were strikingly similar to those of the complete dataset ($y=2.196x-8.549$; $r^2=0.760$; $p<0.0001$).

Shape-heterodonty was highly variable. Shape regressed significantly, but had a rather poor correlation ($r^2=0.157$), with skull length (Figure 4B). Similar to size-heterodonty, the slender-snouted taxa had some of the lowest shape-heterodonty, although *Tomistoma schlegelii* was greater than several other taxa. In addition, members of *Brachychampsa* sp. and *Alligator prenasalis* also had some of the lowest shape-heterodonty in our sample. *Crocodylus siamensis* specimens were more shape-heterodont than their congeners, with one individual being the most shape-heterodont in our sample. Several caimanine individuals, and both *Osteolaemus tetraspis* specimens, also had relatively high shape heterodonty. For the

regression excluding individuals with less than 70% of either tooth row represented, regression statistics ($y = -0.648x - 0.235$; $r^2 = 0.238$; $p < 0.0397$) were also similar to those of the complete dataset ($y = -0.715x - 0.172$; $r^2 = 0.157$; $p < 0.0223$).

Heterodonty along the tooth row

Tooth position count varied between species (see Supplemental Information Table S2). Most alligatoroids had between 19-20 positions on the cranial tooth row. Many had a similar number on the dentary, except that members of *Paleosuchus* had 22 positions. *Leidyosuchus canadensis* had the most (23) cranial positions of the alligatoroids. *Hamadasuchus rebouliei* (20 cranial) and *Borealosuchus sternbergii* (23 cranial and 20 dentary) specimens fit within ranges of alligatoroids. Members of *Crocodylus* and *Mecistops cataphractus* had between 18-19 cranial and 15 dentary positions. *Osteolaemus* specimens had the least tooth positions for any crocodyloid (17 cranial and 14 dentary), and *Tomistoma schlegelii* had the most (21 cranial and 19 dentary). The *Gavialis gangeticus* specimen had more positions than any other species sampled (28 cranial and 26 dentary). These tooth counts are similar to previous published accounts (Brown et al., 2015; Berkovitz & Shellis, 2017).

In all taxa combined, ANOVA indicated size differed significantly between tooth positions [$F(34,261.45) = 4.57$; $p < 0.0001$]. In Alligatoroidea and Crocodyloidea, size undulated three times along the dental arcade resulting in significant differences between positions for both the cranium and mandible (Figure 5A-B). Each undulation peaked with an enlarged tooth. These were typically represented by P4 for both clades, and M4 for alligatoroid and M5 for crocodyloid specimens (sensu Brochu and Storrs, 2012). In addition, members of *Paleosuchus*

had very large P3 and M3. "*Crocodylus*" *affinis* also had a large P3. Unlike other alligatoroid specimens, *Leidyosuchus canadensis* had both M4 and M5 enlarged, and the *Brachychampsa* sp. had an enlarged M5 like crocodyloids (sensu Norell, Clark, & Hutchison, 1994). A final undulation resulted in an enlarged tooth at M9-11 (Figure 5A-B). Interspersed between these were smaller teeth, with the distal-most tooth often the smallest. The dentary was similar to the cranium, with three undulations in size. Enlarged teeth were found at positions D1 and D4, with a third size-peak between D11 and D14. Note that the position of the enlarged teeth along the cranial tooth row tended to align with smaller teeth along the dentary tooth row, and vice versa. This resulted in an 'adjoining' pattern between the size peaks of one arcade and the valleys of the other. The gavialoid specimen differed markedly by having the two mesial-most teeth enlarged, and the remainder showed a gradual decrease in size distally (Figure 5C). *Hamadasuchus rebouli* had some of the largest teeth for its skull length with a dramatic variation in size.

Shape also differed significantly between positions according to MANOVA [$F(4046,23939.54)=1.27$; $p<0.0001$; Wilk's $\Lambda=0.002$; partial $\eta^2=0.171$], although in a visibly different fashion than size. We only graphed PC1 scores against tooth position, as the other PCs represented under 5% of the variance each and were not considered biologically relevant to tooth position (for a justification, see Supplemental Information). Alligatoroids and crocodyloids both had mesial teeth that were typically the most caniniform in the mouth, and distal teeth the most molariform (Figure 5D-E). In cranial teeth P1-M4 tend to exist primarily between PC1 scores of -0.25 and 0.00, followed by a gradual increase in score values as positions become more distal. Dentary teeth represented a more uniformly gradual caniniform-to-molariform

transition. Both superfamilies were highly variable. Alligatoroidea had teeth generally more molariform, with upper outliers almost entirely represented by *Alligator prenasalis*, *Alligator sinensis*, and *Brachychampsa* sp. (Figure 5D). Crocodyloidea was generally more caniniform, with mesial upper outliers represented by “*Crocodylus*” *affinis* and lower outliers represented primarily by *Tomistoma schlegelii* (Figure 5E). Both *Borealosuchus sternbergii* tooth rows had PC1 scores between -0.22 and 0.20, and *Hamadasuchus* ranged between -0.19 and 0.23 (Figure 5F). Both taxa showed a similar progression from caniniformy to molariformy as the alligatoroids and crocodyloids. *Gavialis gangeticus* deviated from the others the most, where most teeth had scores of < -0.20 with a steep increase towards the average in the distal-most fifth of the arcade (Figure 5F).

Tooth shape was strongly influenced by tooth position (Figure 6). When each modern individual’s PC1 values were regressed against position, all linear regressions were significant (Supplemental Information Table S2). The vast majority of tooth row regressions had r^2 values above 80%. *Gavialis gangeticus* had the lowest r^2 values (cranium=0.495, mandible=0.616), followed by the crania of the fossil *Caiman crocodilus* ($r^2=0.728$) and *Tomistoma schlegelii* ($r^2=0.747$). Both cranial and dentary tooth rows typically had slopes between 0.25-0.55 (Figure 6). More shape heterodont taxa typically had greater slopes, with *Crocodylus siamensis* specimens having some of the steepest slopes (0.39-0.68). All the slender-snouted specimens had the y-intercepts between -0.25 and -0.14, indicating strong caniniformy at the median position. Living members of *Alligator* had y-intercepts between 0.029 and 0.085, indicating molariformy at the median (Figure 6). *Alligator prenasalis*, *Brachychampsa* sp., and “*Crocodylus*” *affinis* had the shallowest slopes (0.22-0.32) and the greatest y-intercepts (0.15-0.24) in our

sample, indicating molariform teeth are consistent along the tooth row. *Hamadasuchus rebouli*'s regression characteristics are similar to members of *Caiman* and *Osteolaemus tetraspis*. The slope of the fossil *Caiman crocodilus* differed from modern members of *Caiman* by being much shallower (Figure 6).

DISCUSSION

Defining heterodonty within Crocodylia

The methods proposed here offer a multi-faceted approach to quantifying heterodonty in Crocodylia. As was first proposed in D'Amore (2015), outlining the margin of the tooth is a comprehensive method for measuring two-dimensional tooth shape. This type of semilandmark analysis is ideal for any cylindrical, conical, caniniform, or ziphodont dentition, and would include many archosaurs, squamates, sauropterygians, ichthyosaurs, teleosts, sharks, etc. As tooth morphology is often compared between taxonomically disparate groups (examples in Ciampaglio et al. 2005; Foffa et al., 2018), future studies should use semilandmark analyses to compare crocodylians to these groups to answer numerous phylogenetic and ecomorphological questions.

Foote's morphological disparity allows for a continuous and quantitative measure of heterodonty that may be used for comparison between taxa, or compared with other variables (as was done here with skull length). This measure is ideal if one is interested in *how much* heterodonty is apparent. Alternatively, if one is interested in what shape characteristics make up tooth heterodonty, ordination approaches suffice in describing shape variability. Although plotting PC scores as Cartesian coordinates in a morphospace is traditionally done to visualize

shape variability (as in Figure 2B), overlap due to shape-heterodonty makes specimens, species, and even superfamilies almost indistinguishable from one another. This exemplifies why methods such as box plots and linear regressions may be preferable over the more ‘standard’ morphospace depiction when heterodonty is concerned. It is convenient that only PC1 accounted for over 90% of the variance, allowing for us to use it as the sole measure of shape here. If more PCs accounted for over 5% of the shape variance, it would be appropriate to depict those other PCs in the same manner as PC1 for a comprehensive understanding of shape.

Regression analysis of shape against position generally yielded strong correlations (Supplemental Information Table S2), and the resulting coefficients were useful for comparison between individuals. Certain caveats should be considered though. Regression may be more appropriate for the dentary than the cranium, because in the cranial arcade the mesial-most teeth do not appear to differ from one another as much as the remainder. In most crocodylians this effect is mild, and r^2 values are still high. The effect is very pronounced in *Gavialis gangeticus* though, as both the premaxillary and most maxillary teeth are similar in shape. It is also interesting that this happens in the dentary as well. Future studies should consider this when applying this method to Gavialoidea or dentally analogous taxa.

Although the task of assigning a singular dental morphotype to any one species of crocodylian is beyond the scope of the study, our data suggest that it would be potentially difficult. Heterodonty seems to vary within species, making the assignment of a singular heterodonty measure to an entire species dubious. As far as biological explanations for this,

tooth form is almost certainly influenced by allometry. Ontogenetic shifts in feeding niche have been documented in modern crocodylian species (e.g. Groombridge, 1982; Webb, Manolis, & Buckworth, 1982; Pooley & Gans, 1976; Pooley, 1989; Delany, 1990; Santos et al., 1996; Da Silveira and Magnusson, 1999; Subalusky, A. L., Fitzgerald, L. A., & Smith, 2009 Wallace and Leslie, 2008; Borteiro et al., 2009; Hanson et al., 2014), and allometric changes in the feeding apparatus with size are often explained as a structural consequence of this (e.g. Dodson, 1975; Webb and Messel, 1978; Hutton, 1987; Erickson, Lappin, & Vliet, 2003; Verdade, 2000; Wu et al., 2006; Watanabe & Slice, 2014; Gignac and Erickson, 2016; Gignac & O'Brien, 2016). Concerning teeth, a qualitative increase in overall molariformy was observed in *Alligator mississippiensis*, as it functioned to meet the mechanical demands of increased durophagy (Erickson, Lappin, & Vliet, 2003; Gignac & Erickson, 2014). Although our sample size is too low to confidently assess dental ontogeny within each species, we did see a similar general trend in conspecifics of different sizes. In particular, the larger of our two *Crocodylus porosus* had a greater y -intercepts indicating greater molariformy.

Although there was no significant effect of captive rearing on our specimens, we believe this principle should still be investigated further. Some cases of captive rearing have resulted in very different, and easily distinguishable, cranial morphologies, but there is also quite a bit of overlap concerning others (Drumheller, Wilberg & Sadleir, 2016). This may, or may not, happen with teeth. A larger data set, looking at multiple ontogenetic stages, is necessary to determine if rearing condition has any measurable effects on teeth. The method proposed here would allow for the rigorous comparison between these two rearing conditions, and determine if any changes do occur as well as other factors may correlate to said changes.

Morphological trends within Crocodylia

All crocodylian specimens measured here were heterodont to varying degrees, and these data showed significant variability of morphotypes along the dental arcade for all specimens (Figure 7). Although dentition varied between species, certain consistencies were seen throughout the clade:

1. Similar teeth occurred on both the cranial and dentary dental arcades.
2. As body size increased, size-heterodonty increased reliably with it. Shape-heterodonty shows a much less reliable negative correlation with body size.
3. The vast majority of shape variance from the labial perspective occurred along a single shape axis, representing the transition from caniniform to molariform.
4. There was serial homology in tooth shape from-mesial-to-distal along the tooth row, and molariformy increased in this direction. The transition was significantly linear for both dental arcades in all specimens.
5. Size variability consisted of a non-linear, undulating pattern with three peaks that adjoin with the opposing row, with enlarged crowns interspersed within smaller crowns. This corresponded with the festooning pattern seen in the tooth bearing bones, and was less apparent in slender-snouted taxa.

Size- and shape-heterodonty were very loosely coupled in Crocodylia as they changed in dramatically different, and primarily independent, fashions along the arcade. Some correlation did occur; the regression's significance was probably the result of the fact that the distal-most crowns were typically both the smallest crowns as well as the most molariform. Nevertheless,

the undulating pattern of tooth size did not align with linear shape heterodonty for the vast majority of the tooth row, as indicated by the very low r^2 .

The low degree of coupling begs the question; do developmental agents influence size and shape separately? Although quite a bit of research has looked at how crocodylian teeth grow and replace themselves (Edmund, 1962; Westergaard and Ferguson, 1986, 1987, 1990; LeBlanc et al., 2017), surprisingly little has been done on what developmental influences affect tooth size and shape. Modern crocodylians replace their teeth in waves, or Zahnreihe (Edmund, 1962; Westergaard and Ferguson, 1990; Osborn, 1998), but it is unclear how the nature of these waves relate to the morphological variables investigated here. Keiser et al., (1993) compartmentalized the dentition along the tooth row for *Crocodylus niloticus*, grouping teeth into ‘incisor,’ ‘premolar,’ and ‘molar’ regions. These designations attempted to account for both size and shape heterodonty; each was defined by an enlarged tooth, and each become progressively more molariform. They did not offer a developmental mechanism that differentiated these categories though. Fruchard (2012, p.7) suggested that the only difference between enlarged teeth and their smaller counterparts was that the former was “programmed to be bigger,” suggesting some sort of additional developmental signaling to enlarge teeth. More research is needed on how tooth shape and size are established developmentally in order to truly understand what generates heterodonty.

The fact that *Hamadasuchus rebouli* showed similar trends in heterodonty to crown crocodylians was particularly revealing. This indicated the methods proposed here may be transferable to at least some crocodyliforms outside of Crocodylia. It should also be noted that

this consistency exists in spite of the numerous craniodental characteristics that differ between *Hamadasuchus rebouli* and the crocodylians, including a deep-snout and ziphodont teeth (Larsson & Sues, 2007). The characteristic heterodonty may be convergently derived or homologous with what is seen in this peirosaurid, and further research should investigate how frequent it is seen in Crocodyliformes as a whole.

Adaptive explanations for morphological variability in modern taxa

There is a wide range of tooth morphologies present in modern Crocodylia, and, as teeth are anatomical units used for feeding and aggression, functional inferences may be drawn based on our present understanding of behavior and performance. Bite force in crocodylians is primarily influenced by size (Erickson et al., 2012, 2014), and our data set shows that similarly sized crocodylians may have very different tooth dimensions. This rules out adductor-generated maximum bite force as the sole limiting factor dictating tooth form. Although we are reluctant to associate specific prey items with specific tooth forms, size and shape will influence how a tooth interacts with food items possessing certain physical properties. We therefore suggest that a biomechanical link should exist between the structural limits imposed by tooth form and the material properties of the substrates with which it interacts.

As with all jawed vertebrates, crocodylian teeth will succumb to different speeds and pressures based on their respective position along the arcade. Caniniform mesial teeth are ideal for the initial acquisition of prey. Pointed apices reduce surface area to puncture compliant foods that deform under pressure, such as muscle, fat, and fibrous connective tissue (Frazetta, 1988). Being farther from the hinge, these teeth move faster during a strike and are more likely

to contact prey trying to escape (Busbey, 1989). They will also endure less pressure during a bite based on their position (Erickson et al., 2012), and can afford to be relatively elongate and gracile. On the other end, distal teeth need to withstand greater tooth pressures due to their close proximity to the hinge (Cleuren, Aerts, & Vree, 1995; Erickson, Lappin, & Vliet, 2003; McHenry et al., 2006; Erickson et al., 2012). This explains why these teeth are typically on the molariform half of the shape spectrum; the larger base-to-height ratio gives them greater relative bending strengths to withstand said pressures (Van Valkenburgh and Ruff, 1987; Gignac & Erickson, 2014; Monfroy, 2017). Because force is highest in this region, it is ideal for processing food items after they are acquired (Busbey, 1989; Davenport et al., 1990; Cleurens and de Vree, 2000). The reduced height of these teeth also ensures they do not impede jaw closure. This necessity is very apparent in our representative member of *Gavialis gangeticus*, and provides a functional explanation for the poor linear shape relationship along the tooth row in this individual. Having all the teeth be highly caniniform except for the distal-most region may be interpreted as an attempt to reduce heterodonty as much as possible (Grigg and Gans, 1993), while ensuring the distal crowns do not impede jaw closure or break when processing food.

Particular attention should be paid to the relative size of the distal-most crowns, as they vary considerably within our sample. Most modern alligatoroids and crocodyloids have a single enlarged tooth followed distally by several smaller teeth on the caudal half of their jaw. These teeth typically had positive PC1 scores, especially within *Alligator mississippiensis* and *Crocodylus siamensis*, and were also some of the smallest teeth in their arcades (Figure 7A). Members of *Alligator sinensis* differed from this though, in that they had a row of 4-5 relatively

large, high-molariform crowns (followed by only one crown reduced in size). Probably the most extreme condition, *Osteolaemus tetraspis* specimens had distal crowns that were exceptionally large; the largest relative crowns at positions M10-12 and D11-13 for modern taxa all belonged to members of this species. These two species also have the lowest number of teeth for modern alligatoroids and crocodyloids respectively, a reduction potentially based on the need to fit these enlarged teeth. Aoki (1989) qualitatively noted these unique conditions, and suggested they facilitated durophagy. All alligatoroids and crocodyloids sampled here have been recorded to consume at least some hard prey items though (e.g. Brazaitis, 1973; McIlhenny, 1976; Taylor, 1979; Groombridge, 1982; Ross and Magnusson, 1989; Santos et al., 1996; Selvaraj, 2012; Nifong & Silliman, 2013), so it is unclear what selection pressure resulted in these particular morphologies. It may be a result of body size. Bite force tests of *Alligator mississippiensis* showed the pressure produced at its enlarged M11 to be adequate to crush its harder prey items (Erickson, Lappin, & Vliet, 2003; Gignac & Erickson, 2014). If this is the case in most of the large crocodylians, enlarging the distal-most crowns would be unnecessary. *Alligator sinensis* and *Osteolaemus tetraspis*, on the other hand, may need more extreme dentition closer to the hinge; their smaller size would make it more difficult to process foods with similar mechanical properties. Another explanation for this may be the frequency of consuming hard prey. Although both these species have broad diets, studies have shown certain (but not all) populations of these species to consume disproportionately large numbers of shelled mollusks and crustaceans (Cheng-Kuan, 1957; Groombridge, 1982; Ross and Magnusson, 1989; Luiselli, Akani, & Capizzi, 1999; Pauwels et al., 2007).

All taxa measured here also have two sets of enlarged mesial teeth on both arcades. These teeth are well built for puncturing, likely making first contact with prey during jaw closure, and are resilient against struggling prey (Iordansky, 1964). An apparent trade-off to enlarging these teeth is the need to reduce the size of teeth on the opposing tooth row. This character played a large role in size-heterodonty, with different crocodylians undulating their tooth sizes to different degrees. High relative size-heterodonty in specimens found within Caimaninae was typically a consequence of the dramatic size difference between the enlarged teeth and the small remaining crowns, (Figure 7B). Their dentary crowns in particular became so large they often grew entirely through the cranial rostrum in adults (as mentioned in Brazaitis, 1973), which suggests securing prey takes priority. The remaining crowns were rather small by comparison, including the distal crowns: the teeth with the greatest mechanical advantage when processing hard prey. This overall condition may be specialized for hunting more mobile and/or compliant prey, as these types of prey may be punctured quickly and securely with the enlarged, pointed crowns (Sampaio et al., 2013). The *Crocodylus porosus* specimens had the largest M5 crowns in our sample, which may also show a prioritization for puncturing and securing soft-bodied prey in a larger context (Figure 7B). This species is notorious for actively hunting large vertebrates such as sharks, cattle, horses, and humans (e.g. Taylor, 1979; Kar & Bustard, 1981; Groombridge, 1982; Doody, 2009; Hanson et al., 2015), and these teeth are ideal for puncturing and securing such prey. Similar to the caimanine specimens, this species atrophies position P2 to make room for its enlarged D1 crowns (Brown et al., 2015)

The slender-snouted species possessed generally more caniniform teeth, which may be a consequence of feeding habitat and prey preference. These taxa have a reputation for eating small, aquatic prey with a focus on fish (Peyer, 1968; Webb, Manolis, & Buckworth, 1982; Erickson et al., 2012), and multiple lines of evidence suggest the feeding apparatus is well suited for this function. The slender shape reduces resistance during both lateral motion and jaw adduction when feeding underwater, and the increased snout length allows for a faster strike (Taylor, 1987; Pooley, 1989; Thorbjarnarson, 1990; McHenry et al., 2006; Pierce et al., 2008). Highly caniniform teeth can quickly puncture fast-moving, compliant prey, and their elongate shape may also lower their mechanical resistance (Figure 7C). The longirostrine condition, defined as a snout that is both slender and elongate (Brochu, 2001), resulted in increased tooth positions; *Tomistoma schlegelii* had more teeth than any other crocodyloid, and *Gavialis gangeticus* has the most teeth out of all crocodylians sampled. This cranio-dental morphotype may be prey-size prohibitive though, as larger prey could damage the slender rostrum while struggling. Their elongate mandibular symphysis results in a mechanical disadvantage against the forces produced by shaking and twisting prey (Walmsley et al., 2013). The gracile nature of the dentition means a lower bending strength, making them more susceptible to breakage from larger and/or harder prey as well. On rare occasions, large individuals have been known to take land-based, vertebrate prey (Thorbjarnarson, 1990; Selvaraj, 2012). This is most likely because the overwhelming size of these crocodylians allows their feeding apparatus to withstand the forces exerted by said prey.

The slender-snouted taxa had some of the lowest size- and shape-heterodonty of modern crocodylians, which is reminiscent of several other clades of aquatic predators. They

share certain traits with the anisodont plesiosauiromorphs (Sassoon et al., 2015; Kear et al., 2017). Although these crocodylians are not anisodont in the strict sense (they all have some shape heterodonty), both taxa have elongate mesial crowns transitioning to smaller distal ones. These taxa also reflect similarities with the ‘homodont’ condition apparent in odontocete whales (Rommel, 1990), where all the teeth in the arcade possess a similar, peg-like shape. This condition is believed to be ideal for catching and holding, but not processing, small aquatic prey (MacLeod et al., 2007), as most prey items consumed are under 10% of their body length (MacLeod et al., 2006). A convergent reduction in size- and shape-heterodonty within these independently aquatic groups may indicate a transition from a multi-functional dental arcade to one almost exclusively for prey capture. This morphological condition is best exemplified by *Gavialis gangeticus*, as it is almost entirely caniniform along its tooth row and eats primarily fish (Groombridge, 1982, Figure 7C). Members of *Mecistops cataphractus* and *Tomistoma schlegelii*, although also primarily caniniform, still displayed the linear shape change typical of other crocodyliids. These species may consume prey that require relatively more processing with their distal crowns, and there are numerous reports of them eating prey such as crustaceans, turtles, and immature primates (Brazaitis, 1973; Groombridge, 1982; Galdikas and Yeager, 1984; Selvaraj, 2012).

Tooth shape may indicate differences in feeding behavior and processing ability, even though overlap exists in prey selection. *Alligator mississippiensis* and *Crocodilus niloticus* both consume a wide variety of prey, including both large and small mammals, crustaceans, fish, water fowl, snakes, turtles, and conspecifics (McIlenny, 1976; Pooley & Gans, 1976; Groombridge, 1982; Delany and Abercrombie, 1986; Hutton, 1987; Shoop & Ruckdeschel, 1990;

Rootes & Chabreck, 1993; Elsey, Trosclair III, & Linscombe, 2004; Wallace and Leslie, 2008; Gabrey, 2010). A comparison of controlled feedings of each of these species showed *Alligator mississippiensis* to fracture and consume noticeably more bovine skeletal elements than *Crocodylus niloticus* (Njau & Blumenschine, 2006; Drumheller & Brochu, 2014; 2016). Our *Alligator mississippiensis* specimens was generally more molariform than *Crocodylus niloticus*. These teeth would have greater bending strengths to resist breakage when processing hard material such as bone.

Fossil taxa and the appropriateness of analogues

Certain fossil taxa were reminiscent of modern counterparts. We expected the fossil *Caiman crocodilus* to be similar to its congeners, due to the fact that these specimens are closely related and all consume insects, crustaceans, and fish (Brazaitis, 1973; Groombridge, 1982; Da Silveira and Magnusson, 1999). Any differences in size and shape ranges appear to simply be a consequence of the former's incomplete arcades; no distal maxillary or dentary crowns were available (see **Limitations** below). *Alligator mississippiensis* specimens have similar shape regression statistics to our *Leidyosuchus canadensis* specimen, but, unlike members of *Alligator*, this specimen lacked enlarged distal teeth (Figure 7D). This caused size heterodonty to differ noticeably, and may be indicative of a difference in the degree these taxa process hard materials (although no taphonomic evidence for this currently exists associated with *Leidyosuchus canadensis*). The two specimens of *Borealosuchus sternbergii* differed from one another in median shape as indicated by y-intercepts, which may due to an allometric increase

in molariformy. The best analogue for this species may be a member of *Crocodylus* with similar slopes such as *Crocodylus palustris*, but more data are necessary to confirm this (Figure 7D).

Hamadasuchus rebouli had similar relative size-heterodonty and relative maximum tooth size to the larger *Crocodylus porosus* specimen, which indicates it may have dealt with similar prey from a mechanical standpoint (Figure 7E). The greatly enlarged mesial teeth would puncture vertebrate tissue with similar effectiveness (Figure 7B). *Hamadasuchus rebouli* differed in that it had very large distal crowns, which, unlike *Osteolaemus tetraspis*, are laterally flattened (Larsson & Sidor, 1999). This suggests potential differences in prey processing. Peirosaurids are believed to be primarily terrestrial crocodyliforms (Tavares et al., 2017), and they most likely did not occupy the semi-aquatic, sit-and-wait predator niche dominated by modern crocodylians (Larsson & Sues, 2007). It may have used these for either sheering soft tissue or breaking bone similar to modern mammalian carnassials, as rolling on land is not an effective means of dismemberment (Fish et al., 2007).

Several authors have stated that modern taxa do not have, or have secondarily lost, an extreme degree of molariformy commonly found in extinct representatives. ‘Globidonty’ describes the enlarged, highly molariform crowns in fossil taxa potentially used for durophagy (Norell, Clark, & Hutchison, 1994; Brochu, 1999; 2001; Ósi & Barrett, 2011). Species of *Brachychampsia* are textbook examples of a globidont taxa (Case, 1925; Carpenter and Lindsey, 1980, Figure 7F), and our specimen is the only one in the sample with distal teeth so molariform their PC1 scores exceed 0.349. Although we agree with Brochu (2001, 2004) that *Osteolaemus tetraspis* is not as extreme, the PC1 scores of its enlarged distal teeth are closer to our

Brachychampsa sp. than any other taxon sampled (0.322-0.341). *Alligator prenasalis* and “*Crocodylus*” *affinis* distal crowns are similar to *Alligator sinensis* in shape, and also create a ridge of robust teeth (Mook, 1932). The mechanical capabilities of these particular crowns in modern taxa should be similar to the extinct, which suggests similar processing abilities in the distal regions of the skull. The similarities break down when the rest of the jaw is considered though. In addition to these highly molariform teeth, modern taxa also possess caniniform mesial teeth suggesting a division of labor along the tooth row. Contrarily, almost all teeth of members of *Alligator prenasalis*, *Brachychampsa* sp., and “*Crocodylus*” *affinis* are on the molariform half of the shape-spectrum (Figure 7F), making both their size- and shape-heterodonty rather low. These extinct taxa probably did not need to do as much puncturing of compliant substrate, which supports the argument that they may have foraged for mollusks and slow moving turtles (Carpenter and Lindsey, 1980; similar to Salas-Gismondi et al., 2015) rather than being ambush predators.

Limitations and future work

A complete tooth row with all positions represented would be the most thorough way to assess heterodonty in any specimen. Nevertheless, complete tooth rows may not be available under many circumstances. Although we cannot propose a threshold for what number of teeth is ‘enough’ to accurately assess heterodonty, there are factors that influence some of these methods more than others. Foote’s morphological disparity relies on, among other things, the grand mean and the sample size. Size-heterodonty may be underrepresented if, for example, an enlarged tooth is missing. This tooth would deviate greatly from the grand mean if present, so

its exclusion would deflate size heterodonty. Due to their greater frequency, small teeth would typically be closer to the grand mean. Therefore, if a single small tooth was missing heterodonty would slightly inflate. It should also be noted that if the majority of small teeth were missing their absence would end up decreasing heterodonty, as the grand mean would approach the value of the remaining large teeth. Shape-heterodonty will not be as influenced by enlarged teeth missing, but more so by a lack of the mesial- or distal-most teeth. Missing many of the caniniform or molariform teeth will deflate shape-heterodonty, as the overall variance would be reduced. This would also influence regression statistics, as a lack of either extreme would raise or lower the slope and/or y-intercept.

Even though our data set included several specimens with tooth rows with less than 70% completeness, we feel our data is reliable enough for the morphological and functional conclusions we draw. The similarity between the heterodonty regressions representing all specimens, versus those with more complete specimens only, suggests that incompleteness did not influence our heterodonty values very much. This is most likely because the factors that would strongly influence size- and shape-heterodonty mentioned above were relatively rare in our data set. Few specimens sampled lacked enlarged teeth. The teeth that were missing were typically spread throughout the tooth row, and not localized to the mesial or distal extremes. There were several specimens whose heterodonty results were probably strongly influenced. The very low size-heterodonty in *Alligator prenasalis* may be a consequence of the loss of enlarged teeth, but the relatively small P4 crown suggests this value should be on the low-end regardless. The fossil *Caiman crocodilus* was also affected by missing teeth. It shared almost identical tooth morphology with modern congeners at similar positions. Because the distal

30% of its teeth were missing, Foote's disparity of shape was reduced. This also affected the shape regression, as the lack of high PC1 scores on the distal end reduced the slope. Although both *Crocodylus siamensis* specimens have very high shape-heterodonty due to having both very caniniform and molariform crowns along their arcade, one specimen (AMNH 49231) yielded a very high shape disparity value. This was most likely partially influenced by missing teeth.

The two-block PLS test did not factor in heterodonty. Although this was not the goal of this particular analysis, it should be noted that the averaged tooth used for one block essentially eliminates variability of tooth shape along the arcade. Specimens with both low and high shape-heterodonty could produce very similar averages. This highlights the pitfalls of simply averaging all the teeth in the arcade together for the purposes of understanding dental morphology, and why it is avoided in our assessments of heterodonty here.

We did not consider all three dimensions. Living crocodylian teeth are often described as conical (Edmund, 1969) or conodont (Hendrickx, Mateus, & Araújo, 2015b). Studies of bending strengths show variation between mesial-distal and labial-lingual axes (Monfrey, 2017), indicating that functional information may be drawn from the dimension not measured here. This is especially important concerning fossil taxa, as pronounced lateral compression is commonplace. *Hamadasuchus rebouli* distal teeth have been referred to as ziphodont (Larsson & Sidor, 1999), but, as this is defined by lateral flattening, our method did not register this character. Future studies should consider this third dimension at least qualitatively, in order to avoid conflating disparate tooth morphotypes such as these.

Principal component scores as shape measurements are very much dependent on the nature of the sample. Although they are very revealing concerning shape variability, they are not transferable between different data sets. A potential method for creating transferable shape metrics is using our PC1 axis as a guide to derive linear distance measures that would account for the serial shape homology seen in Crocodylia. Since PC1 essentially represents molariformy vs. caniniformy from the labial perspective, it could possibly be simplified into a comparison of linear distance measures such as maximum mesial-distal widths and apical-basal heights. These metrics would be not only easy to collect, but also transferable between data sets.

These limitations aside, future researchers may apply aspects of this method to a host of non-mammalian taxa. As stated above the semilandmark analysis is very versatile, especially for single-cusped teeth. Foote's disparity can be applied to any measurable taxon with a complete enough tooth row, and is transferable between even disparate groups. Mesial-to-distal linear regressions may be directly applied to any crocodylian, and perhaps certain crocodyliform, specimens with an intact enough tooth row. This could also be applied to PC scores in other non-mammalian taxa, to determine what degree (if any) shape change is linear.

We limit our evaluation of interspecific differences, and make no attempt to analyze other factors such as ontogenetic changes (Erickson, Lappin, & Vliet, 2003; Erickson et al., 2004; Gignac & Erickson, 2014; Drumheller, Wilberg, & Sadleir, 2016). These variables may be investigated in the future using our method, as there is nothing to suggest that crocodylian individuals of most species and/or ages could not be be quantified in a similar manner. This

method could be very useful in dealing with incomplete fossils. It is common for fossil crocodylian specimens to be lacking many, or even most, of their teeth. The linear nature of tooth shape can predict the shape of these missing teeth. A record of the ranges of slopes may be accumulated for fossil specimens with intact teeth. These slopes may then be used as a reference, and be applied to a fossil with the missing teeth. The preserved teeth can be plugged into the linear equation, and the shapes of missing teeth may be predicted with a high degree of certainty. This would result in a more complete representation of the extinct animal's anatomy, useful from the standpoint of both anatomical science and paleontological reconstruction.

Quantifying the teeth of Crocodylia will add rigor to future life history studies of the clade. First and foremost, values may be applied to the plethora of qualitative terms used by researchers (see **Introduction**). This would allow for stricter definitions of the terms when used in the future. As a quantifiable trait, both tooth shape in a single position and heterodonty as a whole may be incorporated into character matrices for phylogenetic analyses. Quantitative descriptors of dentition can describe a numerical range of morphology as opposed to cherry-picking an average tooth or single position. The teeth of fossil taxa can be compared statistically to modern taxa to determine the best analogue, and rigorous hypotheses about paleobehavior and paleoecology may be drawn. Crocodylia, both living and extinct, may be grouped into dental categories, allowing for species and specimens to be compared to one another (similar to snouts in Brochu, 2001). Frequency, size, and hardness of food items may be compared to these categories to determine if a link exists between dental morphotypes and dietary patterns (similar to Aoki, 1989). Crocodylians are used in both performance and actualistic taphonomy

studies frequently (Njau & Blumenschine, 2006; Erickson et al., 2012, 2014; Drumheller & Brochu, 2014; 2016), and the output of these studies could be correlated with tooth dimensions. Tooth shape may also be compared to bite-force, death-rolling, bone-modification, and prey preferences and mechanical properties.

CONCLUSION

Multiple measures of morphology have allowed us to describe heterodonty in a thorough manner across a number of both extinct and extant crocodylian specimens. Through a combination of Foote's morphological disparity and regression analysis along the tooth row, our data indicates that crocodylians are indeed heterodont with a number of dental morphotypes available spanning from extreme cases of caniniform to molariform. This variability may be functional in nature, and relate to the size, frequency, and compliance of certain prey in their typically generalist diets. The methods used here should be applied in the future to most crocodylian specimens, as well as other non-mammalian tetrapods, to investigate dental morphology in the context of a number of natural history related questions.

Acknowledgements

The American Museum of Natural History Department of Herpetology, Royal Ontario Museum Vertebrate Paleontology, and University of California Museum of Paleontology curatorial staff allowed on-site access to dry skull specimens. We would like to particularly thank D. Evans, P. Holroyd, D. Kizirian, C. Raxworthy, K. Seymour for their assistance.

References:

- Adams TL, Noto CR, Drumheller S. 2017. A large neosuchian crocodyliform from the Upper Cretaceous (Cenomanian) woodbine formation of North Texas. *Journal of Vertebrate Paleontology* 37(4):e1349776.
- Aoki R. 1989. The jaw mechanics in the heterodont crocodilians. *Current Herpetology in East Asia* 1:17-21.
- Bennett GE. 2012. Community structure and paleoecology of crocodyliforms from the upper Hell Creek Formation (Maastrichtian), eastern Montana, based on shed teeth. *Jeffersoniana* 28:1-15.
- Berkovitz BK, Shellis RP. 2017. *The Teeth of Non-mammalian Vertebrates*. Cambridge, MA: Academic Press.
- Bookstein FL. 1997. *Morphometric tools for landmark data: geometry and biology*. Cambridge: Cambridge University Press.
- Borteiro C, Gutiérrez F, Tedros M, Kolenc F. 2009. Food habits of the Broad-snouted Caiman (*Caiman latirostris*: Crocodylia, Alligatoridae) in northwestern Uruguay. *Studies on Neotropical Fauna and Environment* 44(1):31-36.
- Brazaitis P. 1973. *The Identification of Living Crocodilians*. New York: New York Zoological Society.

- 856 Britt EJ, Clark AJ, Bennett AF. 2009. Dental morphologies in gartersnakes (*Thamnophis*) and
857 their connection to dietary preferences. *Journal of Herpetology* 43(2):252-259.
- 858 Brochu CA. 1999. Phylogenetics, taxonomy, and historical biogeography of Alligatoroidea.
859 *Journal of Vertebrate Paleontology* 19(S2):9-100.
- 860 Brochu CA. 2001. Crocodylian snouts in space and time: phylogenetic approaches toward
861 adaptive radiation. *American Zoologist* 41(3):564-585.
- 862 Brochu CA. 2004. Alligatorine phylogeny and the status of *Allognathosuchus* Mook, 1921.
863 *Journal of Vertebrate Paleontology* 24(4):857-873.
- 864 Brochu CA, Storrs W. GW. 2012. A giant crocodile from the Plio-Pleistocene of Kenya, the
865 phylogenetic relationships of Neogene African crocodylines, and the antiquity of
866 *Crocodylus* in Africa. *Journal of Vertebrate Paleontology* 32(3): 587-602.
- 867 Brown CM, VanBuren CS, Larson DW, Brink KS, Campione NE, Vavrek MJ, Evans DC. 2015. Tooth
868 counts through growth in diapsid reptiles: implications for interpreting individual and
869 size-related variation in the fossil record. *Journal of Anatomy*, 226(4):322-333.
- 870 Buckley LG, Currie PJ. 2014. Analysis of intraspecific and ontogenetic variation in dentition of
871 *Coelophysis bauri* (Late Triassic), and implications for the systematics of isolated
872 theropod teeth. *New Mexico Museum of Natural History and Science Bulletin* 63.
- 873 Busbey AB. 1995. The structural consequences of skull flattening in crocodilians. *Functional*
874 *Morphology in Vertebrate Paleontology* 173-192.

- 875 Busbey AB. 1989. Form and function of the feeding apparatus of *Alligator mississippiensis*.
876 *Journal of Morphology* 202(1):99-127.
- 877 Carpenter K, Lindsey D. 1980. The dentary of *Brachychampsia montana* Gilmore (Alligatorinae;
878 Crocodylidae), a Late Cretaceous turtle-eating alligator. *Journal of Paleontology*
879 54(6):1213-1217.
- 880 Case EC. 1925. Note on a new species of the Eocene crocodilian *Allognathosuchus*, *A. wartheni*.
881 Ann Arbor, MI: University of Michigan.
- 882 Cheng-kuan C. 1957. Observations on the life history of Chinese alligator (*Alligator sinensis*
883 Fauvel). *Acta Zoologica Sinica* 2(004).
- 884 Ciampaglio CN, Wray GA, Corliss BH. 2005. A toothy tale of evolution: convergence in tooth
885 morphology among marine Mesozoic–Cenozoic sharks, reptiles, and mammals. *The*
886 *Sedimentary Record* 3(4):1-2.
- 887 Cleuren J, Aerts P, Vree FD. 1995. Bite and joint force analysis in *Caiman crocodilus*. Belgian
888 *Journal of Zoology* 125(1):79-94.
- 889 Cleuren J, de Vree F. 2000. Feeding in crocodilians. In Schwenk K. ed. *Feeding: Form, Function,*
890 *and Evolution in Tetrapod Vertebrates*, Cambridge, MA: Elsevier, 359-394.
- 891 Da Silveira R, Magnusson WE. 1999. Diets of spectacled and black caiman in the Anavilhanas
892 Archipelago, Central Amazonia, Brazil. *Journal of Herpetology* 33(2):181-192.

- 893 D'Amore DC. 2009. A functional explanation for denticulation in theropod dinosaur teeth. *The*
894 *Anatomical Record* 292(9):1297-1314.
- 895 D'Amore DC. 2015. Illustrating ontogenetic change in the dentition of the Nile monitor lizard,
896 *Varanus niloticus*: a case study in the application of geometric morphometric methods
897 for the quantification of shape–size heterodonty. *Journal of Anatomy* 226(5):403-419.
- 898 D'Amore DC, McHenry C, Doody J, Clulow S, Rhind D. 2018. Claw morphometrics in monitor
899 lizards: Variable substrate and habitat use correlate to shape diversity within a predator
900 guild. *Ecology & Evolution* <https://doi.org/10.1002/ece3.4185>
- 901 Daniel WJT, McHenry C. 2001. Bite force to skull stress correlation-modelling the skull of
902 *Alligator mississippiensis*. In Grigg GC, Seebacher F, Franklin C. (Eds.), *Crocodylian Biology*
903 *And Evolution*, New South Wales: Surrey Beatty and Sons, Chipping Norton, 135-143.
- 904 Davenport J, Grove DJ, Cannon J, Ellis TR, Stables R. 1990. Food capture, appetite, digestion rate
905 and efficiency in hatchling and juvenile *Crocodylus porosus*. *Journal of Zoology*
906 220(4):569-592.
- 907 Delany MF. 1990. Late summer diet of juvenile American alligators. *Journal of Herpetology*
908 24(4):418-421.
- 909 Delany MF, Abercrombie CL. 1986. American alligator food habits in northcentral Florida. *The*
910 *Journal of Wildlife Management* 50(2):348-353.
- 911 Dodson P. 1975. Functional and ecological significance of relative growth in *Alligator*. *Journal of*
912 *Zoology* 175(3):315-355.

- 913 Doody JS. 2009. Eyes bigger than stomach: prey caching and retrieval in the saltwater crocodile,
914 *Crocodylus porosus*. *Herpetological Review* 40(1):26.
- 915 Drake AG, Klingenberg CP. 2008. The pace of morphological change: historical transformation of
916 skull shape in St. Bernard dogs. *Proceedings of the Royal Society B* 275:71–76.
- 917 Drumheller SK, Brochu CA. 2014. A diagnosis of *Alligator mississippiensis* bite marks with
918 comparisons to existing crocodylian datasets. *Ichnos* 21(2):131-146.
- 919 Drumheller SK, Brochu CA. 2016. Phylogenetic taphonomy: a statistical and phylogenetic
920 approach for exploring taphonomic patterns in the fossil record using crocodylians.
921 *Palaio* 31(10):463-478.
- 922 Drumheller SK, Wilberg EW, Sadleir RW. 2016. The utility of captive animals in actualistic
923 research: a geometric morphometric exploration of the tooth row of *Alligator*
924 *mississippiensis* suggesting ecophenotypic influences and functional constraints. *Journal*
925 *of Morphology* 277(7):866-78.
- 926 Edmund AG. 1962. Sequence and rate of tooth replacement in the Crocodilia. *Royal Ontario*
927 *Museum, Life Science Division Contributions* 56: 1-42.
- 928 Edmund AG. 1969. Dentition. In: Gans C. d'A. Bellairs A, Parsons TS, eds. *Biology of the Reptilia*,
929 *Volume 1: Morphology A*. Cambridge, MA: Academic Press, 117-200.
- 930 Elsey RM, Trosclair III PL, Linscombe JT. 2004. The American alligator as a predator of mottled
931 ducks. *Southeastern Naturalist* 3(3), 381-390.

- 932 Erickson GM, Lappin AK, Vliet KA. 2003. The ontogeny of bite-force scaling among Crocodylia.
933 *Journal of Zoology* 260(3):317-327.
- 934 Erickson GM, Lappin AK, Parker T, Vliet KA. 2004. Comparison of bite-force performance
935 between long-term captive and wild American alligators (*Alligator mississippiensis*).
936 *Journal of Zoology* 262(1):21-28.
- 937 Erickson GM, Gignac PM, Steppan SJ, Lappin AK, Vliet KA, Brueggen JD, Inouye BD, Kledzik D,
938 Webb GJ. 2012. Insights into the ecology and evolutionary success of crocodilians
939 revealed through bite-force and tooth-pressure experimentation. *PLoS One* 7(3):e31781.
- 940 Erickson GM, Gignac PM, Lappin AK, Vliet KA, Brueggen JD, Webb GJW. 2014. A comparative
941 analysis of bite-force scaling among Crocodylia. *Journal of Zoology* 292(1):48-55.
- 942 Farlow JO, Hurlburt GR, Elsey RM, Britton AR, Langston Jr2005. Femoral dimensions and body
943 size of *Alligator mississippiensis*: estimating the size of extinct mesoeucrocodylians.
944 *Journal of Vertebrate Paleontology* 25(2):354-69.
- 945 Farrugia P, Polly PD, Njau JK. 2016. An analysis of shape differences in crocodylian dentition
946 using geometric morphometrics. *Journal of Vertebrate Paleontology*, Program and
947 Abstracts 133.
- 948 Ferguson MWJ. 1981. The structure and development of the palate in *Alligator mississippiensis*.
949 *Archives of Oral Biology* 26(5):427-443.
- 950 Fish FE, Bostic SA, Nicastro AJ, Beneski JT. 2007. Death roll of the alligator: mechanics of twist
951 feeding in water. *Journal of Experimental Biology* 210(16):2811-2818.

- 952 Foffa D, Young MT, Stubbs TL, Dexter KG, Brusatte SL. 2018. The long-term ecology and
953 evolution of marine reptiles in a Jurassic seaway. *Nature Ecology & Evolution* 2(10).
- 954 Foote M. 1993 Contributions of individual taxa to overall morphological disparity. *Paleobiology*
955 19(4):403-19.
- 956 Frey E, Monninger S. 2010. Lost in action—the isolated crocodilian teeth from Enspel and their
957 interpretive value. *Palaeobiodiversity and Palaeoenvironments* 90(1):65-81.
- 958 Fruchard C. 2012. The Nile crocodile, a new model for investigating heterodonty and dental
959 continuous renewal in vertebrates. *BioSciences Master Reviews*
- 960 Multivariate and cladistic analyses of isolated teeth reveal sympatry of theropod dinosaurs in
961 the Late Jurassic of northern Germany. Frazzetta TH. 1988. The mechanics of cutting and
962 the form of shark teeth (Chondrichthyes, Elasmobranchii). *Zoomorphology* 108(2):93-
963 107.
- 964 Fukuda Y, Saalfeld K, Lindner G, Nichols T. 2013. Estimation of total length from head length of
965 saltwater crocodiles (*Crocodylus porosus*) in the Northern Territory, Australia. *Journal of*
966 *Herpetology* 47(1):34-40.
- 967 Gabrey SW. 2010. Demographic and geographic variation in food habits of American alligators
968 (*Alligator mississippiensis*) in Louisiana. *Herpetological Conservation and Biology*
969 5(2):241-250.
- 970 Galdikas BM, Yeager CP. 1984. Brief report: Crocodile predation on a crab-eating macaque in
971 Borneo. *American Journal of Primatology* 6(1):49-51.

- 972 Gerke O, Wings O. 2016.*PloS One* 11(7):e0158334.
- 973 Gignac PM, Erickson GM. 2014. Ontogenetic changes in dental form and tooth pressures
974 facilitate developmental niche shifts in American alligators. *Journal of Zoology*
975 295(2):132-142.
- 976 Gignac PM, Erickson GM. 2016. Ontogenetic bite-force modeling of *Alligator mississippiensis*:
977 implications for dietary transitions in a large-bodied vertebrate and the evolution of
978 crocodylian feeding. *Journal of Zoology* 299(4):229-38.
- 979 Gignac P, O'Brien H. 2016. Suchian feeding success at the interface of ontogeny and
980 macroevolution. *Integrative and Comparative Biology* 56(3):449-458.
- 981 Grigg G, Gans C. 1993. Morphology and physiology of the Crocodylia. *Fauna of Australia Volume*
982 *2A, Amphibia and Reptilia*. Canberra: Australian Government Publishing Service, 326-
983 336.
- 984 Groombridge B. 1982. *The IUCN Amphibia-Reptilia Red Data Book, Part 1: Testudines,*
985 *Crocodylia, Rhynchocephalia*. Gland, Switzerland: IUCN.
- 986 Gunz P, Mitteroecker P. 2013. Semilandmarks: a method for quantifying curves and surfaces.
987 *Hystrix, the Italian Journal of Mammalogy* 24(1):103-109.
- 988 Hammer Ø, Harper DAT, Ryan PD. 2001. PAST: Paleontological statistics software package for
989 education and data analysis. *Palaeontologia Electronica* 4(1):9pp.

- 990 Hanson JO, Salisbury SW, Campbell HA, Dwyer RG, Jardine TD, Franklin CE. 2014. Feeding across
991 the food web: The interaction between diet, movement and body size in estuarine
992 crocodiles (*Crocodylus porosus*). *Austral Ecology* 40(3):275-286.
- 993 Hendrickx C, Mateus O. 2014. Abelisauridae (Dinosauria: Theropoda) from the Late Jurassic of
994 Portugal and dentition-based phylogeny as a contribution for the identification of
995 isolated theropod teeth. *Zootaxa* 3759(1):1-74.
- 996 Hendrickx C, Mateus O, Araújo R. 2015a The dentition of megalosaurid theropods. *Acta*
997 *Palaeontologica Polonica*. A proposed terminology of theropod teeth (Dinosauria,
998 Saurischia). *Journal of Vertebrate Paleontology* 35(5):e982797.
- 999 Hendrickx C, Mateus O, Araújo R. 2015b. 60(3):627-642.
- 1000 Hutton JM. 1987. Growth and feeding ecology of the Nile crocodile *Crocodylus niloticus* at
1001 Ngezi, Zimbabwe. *The Journal of Animal Ecology* 56(1):25-38.
- 1002 Iordansky NN. 1964. The jaw muscles of the crocodiles and some relating structures of the
1003 crocodilian skull. *Anatomischer Anzeiger* 115:256-280.
- 1004 Juarez H, D'Amore, D. 2018. Tooth morphology and function in the snake tribe Thamnophini.
1005 Abstracts 2018 Joint Meeting of Ichthyologists and Herpetologists. Rochester. New York.
- 1006 Kar SK, Bustard HR. 1983. Attacks on domestic livestock by juvenile saltwater crocodile,
1007 *Crocodylus porosus*, in Bhitarkanika Wildlife Sanctuary, Orissa India. *Amphibia-Reptilia*
1008 4(1):81-83.

- 1009 Kear BP, Larsson D, Lindgren J, Kundrát M. 2017. Exceptionally prolonged tooth formation in
1010 elasmosaurid plesiosaurs. *PLoS One* 12(2):e0172759.
- 1011 Kieser JA, Klapsidis C, Law L, Marion M. 1993. Heterodonty and patterns of tooth replacement
1012 in *Crocodylus niloticus*. *Journal of Morphology* 218(2): 195-201.
- 1013 Klingenberg CP. 2011. MorphoJ: an integrated software package for geometric morphometrics.
1014 *Molecular Ecology Resources* 11(2):353-357.
- 1015 Langston W. 1973. The crocodilian skull in historical perspective. *Biology of the Reptilia* 4:263-
1016 284.
- 1017 Larson DW, Brown CM, Evans DC. 2016. Dental disparity and ecological stability in bird-like
1018 dinosaurs prior to the end-Cretaceous mass extinction. *Current Biology* 26(10):1325-
1019 1333.
- 1020 Larson DW, Currie PJ. 2013. Multivariate analyses of small theropod dinosaur teeth and
1021 implications for paleoecological turnover through time. *PLoS One* 8(1):e54329.
- 1022 Larsson HCE, Sidor CA. 1999. Unusual crocodyliform teeth from the Late Cretaceous
1023 (Cenomanian) of southeastern Morocco. *Journal of Vertebrate Paleontology* 19(2):398-
1024 401.
- 1025 Larsson HC, Sues HD. 2007. Cranial osteology and phylogenetic relationships of *Hamadasuchus*
1026 *rebouli* (Crocodyliformes: Mesoeucrocodylia) from the Cretaceous of Morocco.
1027 *Zoological Journal of the Linnean Society* 149(4):533-67.

- 1028 LeBlanc AR, Brink KS, Cullen TM, Reisz RR. 2017. Evolutionary implications of tooth attachment
1029 versus tooth implantation: a case study using dinosaur, crocodilian, and mammal teeth.
1030 *Journal of Vertebrate Paleontology* 37(5):e1354006.
- 1031 Lecuona A, Pol D. 2008. Tooth morphology of *Notosuchus terrestris* (Notosuchia:
1032 Mesoeucrocodylia): new evidence and implications. *Comptes Rendus Palevol* 7(7):407-
1033 417.
- 1034 Luiselli L, Akani GC, Capizzi D. 1999. Is there any interspecific competition between dwarf
1035 crocodiles (*Osteolaemus tetraspis*) and Nile monitors (*Varanus niloticus ornatus*) in the
1036 swamps of central Africa? A study from south-eastern Nigeria. *Journal of Zoology*
1037 247(1):127-131.
- 1038 MacLeod CD, Reidenberg JS, Weller M, Santos MB, Herman J, Goold J, Pierce GJ. 2007. Breaking
1039 symmetry: The marine environment, prey size, and the evolution of asymmetry in
1040 cetacean skulls. *The Anatomical Record* 290(6):539-545.
- 1041 MacLeod CD, Santos MB, Lopez A, Pierce GJ. 2006. Relative prey size consumption in toothed
1042 whales: implications for prey selection and level of specialisation. *Marine Ecology*
1043 *Progress Series* 326:295-307.
- 1044 Martin JE. 2007. New material of the Late Cretaceous globidontan *Acynodon iberoccitanus*
1045 (Crocodylia) from southern France. *Journal of Vertebrate Paleontology* 27(2):362-372.

- 1046 McHenry CR, Clausen PD, Daniel WJ, Meers MB, Pendharkar A. 2006. Biomechanics of the
- 1047 rostrum in crocodilians: a comparative analysis using finite-element modeling. *The*
- 1048 *Anatomical Record* 288(8):827-849.
- 1049 McIlhenny EA. 1976. *The Alligator's Life History*. Society for the Study of Amphibians and
- 1050 Reptiles.
- 1051 Mitteroecker P, Gunz P, Windhager S, Schaefer K. 2013. A brief review of shape, form, and
- 1052 allometry in geometric morphometrics, with applications to human facial morphology.
- 1053 *Hystrix, the Italian Journal of Mammalogy* 24(1):59-66.
- 1054 Monfroy QT. 2017. Correlation between the size, shape and position of the teeth on the jaws
- 1055 and the bite force in Theropoda. *Historical Biology* 29(8):1089-1105.
- 1056 Mook CC. 1932. A study of the osteology of *Alligator prenasalis* (Loomis). *Bulletin of the*
- 1057 *Museum of Comparative Zoology* 74(2).
- 1058 Narváez I, Brochu CA, Escaso F, Pérez-García A, Ortega F. 2015. New crocodyliforms from
- 1059 southwestern Europe and definition of a diverse clade of European Late Cretaceous
- 1060 basal eusuchians. *PloS One* 10(11):e0140679.
- 1061 Nifong JC, Silliman BR. 2013. Impacts of a large-bodied, apex predator (*Alligator mississippiensis*
- 1062 Daudin 1801) on salt marsh food webs. *Journal of Experimental Marine Biology and*
- 1063 *Ecology* 440:185-191.

- 1064 Njau JK, Blumenschine RJ. 2006. A diagnosis of crocodile feeding traces on larger mammal
1065 bone, with fossil examples from the Plio-Pleistocene Olduvai Basin, Tanzania. *Journal of*
1066 *Human Evolution* 50(2):142-162.

- 1067 Norell M, Clark JM, Hutchison JH. 1994. The Late Cretaceous alligatoroid *Brachychampsa*
1068 *montana* (Crocodylia): new material and putative relationships. *American Museum*
1069 *Novitates* 3116.

- 1070 Novas FE, Pais DF, Pol D, Carvalho IDS, Scanferla A, Mones A, Riglos, MS. 2009. Bizarre
1071 notosuchian crocodyliform with associated eggs from the Upper Cretaceous of Bolivia.
1072 *Journal of Vertebrate Paleontology* 29(4):1316-1320.

- 1073 Osborn JW. 1998. Relationship between growth and the pattern of tooth initiation in alligator
1074 embryos. *Journal of Dental Research* 77(9):1730-1738.

- 1075 Ósi A. 2014. The evolution of jaw mechanism and dental function in heterodont crocodyliforms.
1076 *Historical Biology* 26(3):279-414.

- 1077 Ósi A, Barrett PM. 2011. Dental wear and oral food processing in *Caiman latirostris*: analogue
1078 for fossil crocodylians with crushing teeth. *Neues Jahrbuch für Geologie und*
1079 *Paläontologie-Abhandlungen* 261(2):201-207.

- 1080 Ósi A, Clark JM, Weishampel DB. 2007. First report on a new basal eusuchian crocodyliform
1081 with multicusped teeth from the Upper Cretaceous (Santonian) of Hungary. *Neues*
1082 *Jahrbuch für Geologie und Paläontologie-Abhandlungen* 243(2):169-177.

- 1083 Pauwels OS, Barr B, Sanchez ML, Burger M. 2007. Diet records for the dwarf crocodile
1084 (*Osteolaemus tetraspis tetraspis*) in Rabi Oil Fields and Loango National Park,
1085 Southwestern Gabon. *Hamadryad* 31(2):258-264.

- 1086 Perez SI, Bernal V, Gonzalez PN. 2006. Differences between sliding semi-landmark methods in
1087 geometric morphometrics, with an application to human craniofacial and dental
1088 variation. *Journal of Anatomy* 208(6):769-784.

- 1089 Peyer B. 1968. *Comparative odontology*. Chicago, IL: University of Chicago Press.

- 1090 Pierce SE, Angielczyk KD, Rayfield EJ. 2008. Patterns of morphospace occupation and
1091 mechanical performance in extant crocodilian skulls: a combined geometric
1092 morphometric and finite element modeling approach. *Journal of Morphology*
1093 269(7):840-864.

- 1094 Pooley AC. 1989. Food and feeding habits. In Ross CA, and Garnet S. eds. *Crocodiles and*
1095 *Alligators* New York, NY: Facts on File, 76-91.

- 1096 Pooley AC, Gans C. 1976. The Nile crocodile. *Scientific American* 234(4):114-125.

- 1097 Rohlf FJ. 2010. Tps Series. Department of Ecology and Evolution, State University of New York,
1098 Stony Brook.

- 1099 Rohlf FJ. 2013. TpsRelw 1.53. Dept. of Ecology and Evolution, State Univ. of New York at Stony
1100 Brook, Stony Brook.

- 1101 Rootes WL, Chabreck RH. 1993. Cannibalism in the American alligator. *Herpetologica* 49(1):99-
1102 107.
- 1103 Rommel S. 1990. Osteology of the bottlenose dolphin. In Leatherwood S, Reeves RR. Eds, *The*
1104 *Bottlenose Dolphin*, Cambridge, MA: Elsevier, 29-49.
- 1105 Ross CA, Magnusson WE. 1989. Living crocodilians. In Ross CA, and Garneteds. *Crocodiles and*
1106 *Alligators* New York, NY: Facts on File, 58-73.
- 1107 Sadleir RW, Makovicky PJ. 2008. Cranial shape and correlated characters in crocodilian
1108 evolution. *Journal of Evolutionary Biology* 21(6):1578-1596.
- 1109 Salas-Gismondi R, Flynn JJ, Baby P, Tejada-Lara JV, Wesselingh FP, Antoine, PO. 2015. A
1110 Miocene hyperdiverse crocodylian community reveals peculiar trophic dynamics in
1111 proto-Amazonian mega-wetlands. *Proceedings of the Royal Society of London B:*
1112 *Biological Sciences* 282(1804):20142490.
- 1113 Salas-Gismondi R, Flynn JJ. Baby P, Tejada-Lara JV, Claude J, Antoine PO. 2016. A new 13 million
1114 year old gavialoid crocodylian from proto-Amazonian mega-wetlands reveals parallel
1115 evolutionary trends in skull shape linked to longirostry. *PloS One* 11(4):e0152453.
- 1116 Sampaio PRM, da Silva MN, de Matos SA, de Matos LRA, Acosta M. 2013. First report of
1117 predation by a caiman (*Paleosuchus trigonatus*, Crocodylia: Alligatoridae) on a caecilian
1118 (*Caecilia marcusii*, Gymnophiona: Caecilidae). *Salamandra* 49(4):227-228.

- 1119 Santos SA, Nogueira MS, Pinheiro MS, Campos Z, Magnusson WE, Mourao GM. 1996. Diets of
- 1120 *Caiman crocodilus yacare* from different habitats in the Brazilian pantanal.
- 1121 *Herpetological Journal* 6:111-117.
- 1122 Sassoon J, Foffa D, Marek R. 2015. Dental ontogeny and replacement in Pliosauridae. *Royal*
- 1123 *Society Open Science* 2(11):150384.
- 1124 Selvaraj G. 2012. Herpetological notes: *Tomistoma schlegelii* (False Gharial). Diet.
- 1125 *Herpetological Review*, 43:608-609.
- 1126 Schwarz-Wings D, Rees J, Lindgren J. 2009. Lower cretaceous mesoeucrocodylians from
- 1127 Scandinavia (Denmark and Sweden). *Cretaceous Research* 30(5):1345-1355.
- 1128 Sheets HD. 2012. IMP software series. Computer software and manual. Buffalo, NY: Canisius
- 1129 College.
- 1130 Sheets HD, Kim K, Mitchell CE. 2004. A combined landmark and outline-based approach to
- 1131 ontogenetic shape change in the Ordovician trilobite *Triarthrus becki*. In *Morphometrics*
- 1132 Berlin: Springer, 67-82.
- 1133 Sheets HD, Zelditch ML. 2013. Studying ontogenetic trajectories using resampling methods and
- 1134 landmark data. *Hystrix, the Italian Journal of Mammalogy* 24(1):67-73.
- 1135 Shimada, K. 2001. On the concept of heterodonty. *Journal of Fossil Research* 34(2):52-54.
- 1136 Shimada K. 2002. Dental homologies in lamniform sharks (Chondrichthyes: Elasmobranchii).
- 1137 *Journal of Morphology* 251(1):38-72.

- 1138 Shimada K. 2004. The relationship between the tooth size and total body length in the sandtiger
1139 shark, *Carcharias taurus* (Lamniformes: Odontaspidae). *Journal of Fossil Research*
1140 37:76–81.
- 1141 Shimada K, Seigel JA. 2005. The relationship between the tooth size and total body length in the
1142 goblin shark, *Mitsukurina owstoni* (Lamniformes: Mitsukurinidae). *Journal of Fossil*
1143 *Research* 38:49–56.
- 1144 Shoop CR, Ruckdeschel CA. 1990. Alligators as predators on terrestrial mammals. *American*
1145 *Midland Naturalist* 124(2):407-412.
- 1146 Smith JB, Dodson P. 2003. A proposal for a standard terminology of anatomical notation and
1147 orientation in fossil vertebrate dentitions. *Journal of Vertebrate Paleontology* 23(1):1-
1148 12.
- 1149 Smith JB, Vann DR, Dodson P. 2005. Dental morphology and variation in theropod dinosaurs:
1150 implications for the taxonomic identification of isolated teeth. *The Anatomical Record*
1151 285(2):699-736.
- 1152 Subalusky AL, Fitzgerald LA, Smith LL. 2009. Ontogenetic niche shifts in the American Alligator
1153 establish functional connectivity between aquatic systems. *Biological Conservation*
1154 142(7):1507-1514.
- 1155 Tavares SAS, Branco FR, de Souza Carvalho I, Maldanis L. 2017. The morphofunctional design of
1156 *Montealtosuchus arrudacamposi* (Crocodyliformes, Upper Cretaceous) of the Bauru
1157 Basin, Brazil. *Cretaceous Research* 79:64-76.

- 1158 Taylor JA. 1979. The foods and feeding habits of subadult *Crocodylus porosus* Schneider in
1159 northern Australia. *Wildlife Research* 6(3):347-359.
- 1160 Thorbjarnarson JB. 1990. Notes on the feeding behavior of the gharial (*Gavialis gangeticus*)
1161 under semi-natural conditions. *Journal of Herpetology* 24(1):99-100.
- 1162 Tinius A, Russell AP. 2017. Points on the curve: An analysis of methods for assessing the shape
1163 of vertebrate claws. *Journal of Morphology* 278(2):150-69.
- 1164 Torices A, Reichel M, Currie PJ. 2014. Multivariate analysis of isolated tyrannosaurid teeth from
1165 the Danek Bonebed, Horseshoe Canyon Formation, Alberta, Canada. *Canadian Journal*
1166 *of Earth Sciences* 51(11):1045-1051.
- 1167 Valkenburgh BV, Ruff CB. 1987. Canine tooth strength and killing behaviour in large carnivores.
1168 *Journal of Zoology* 212(3):379-397.
- 1169 Verdade LM. 2000. Regression equations between body and head measurements in the broad-
1170 snouted caiman (*Caiman latirostris*). *Revista Brasileira de Biologia* 60(3):469-482.
- 1171 Vullo R, Allain R, Cavin L. 2016. Convergent evolution of jaws between spinosaurid dinosaurs
1172 and pike conger eels. *Acta Palaeontologica Polonica* 61(4):825-828.
- 1173 Wallace KM, Leslie AJ. 2008. Diet of the Nile crocodile (*Crocodylus niloticus*) in the Okavango
1174 Delta, Botswana. *Journal of Herpetology* 42(2):361-368.

- 1175 Walmsley CW, Smits PD, Quayle MR, McCurry MR, Richards HS, Oldfield CC, ... & McHenry CR.
1176 2013. Why the long face? The mechanics of mandibular symphysis proportions in
1177 crocodiles. *PLoS One* 8(1):e53873.
- 1178 Watanabe A, Slice DE. 2014. The utility of cranial ontogeny for phylogenetic inference: a case
1179 study in crocodylians using geometric morphometrics. *Journal of Evolutionary Biology*
1180 27(6):1078-1092.
- 1181 Webb GJW, Manolis SC, Buckworth R. 1982. *Crocodylus johnstoni* in the McKinlay river area, NTI
1182 Variation in the diet, and a new method of assessing the relative importance of prey.
1183 *Australian Journal of Zoology* 30(6):877-899.
- 1184 Webb GJW, Messel H. 1978. Movement and dispersal patterns of *Crocodylus porosus* in some
1185 rivers of Arnhem Land, Northern Australia. *Wildlife Research* 5(2):263-283.
- 1186 Westergaard B, Ferguson MWJ. 1986. Development of the dentition in *Alligator*
1187 *mississippiensis*. Early embryonic development in the lower jaw. *Journal of Zoology*
1188 210(4):575-597.
- 1189 Westergaard B, Ferguson MWJ. 1987. Development of the dentition in *Alligator*
1190 *mississippiensis*. Later development in the lower jaws of embryos, hatchlings and young
1191 juveniles. *Journal of Zoology* 212(2):191-222.
- 1192 Westergaard B, Ferguson MWJ. 1990. Development of the dentition in *Alligator*
1193 *mississippiensis*: upper jaw dental and craniofacial development in embryos, hatchlings,

- 1194 and young juveniles, with a comparison to lower jaw development. *American Journal of*
1195 *Anatomy* 187(4):393-421.
- 1196 Wilberg EW. 2017. Investigating patterns of crocodyliform cranial disparity through the
1197 Mesozoic and Cenozoic. *Zoological Journal of the Linnean Society* 181(1):189-208.
- 1198 Wu XB, Xue H, Wu LS, Zhu JL, Wang RP. 2006. Regression analysis between body and head
1199 measurements of Chinese alligators (*Alligator sinensis*) in the captive population. *Animal*
1200 *Biodiversity and Conservation* 29(1):65-71.
- 1201 Young MT, Brusatte SL, Beatty BL, De Andrade MB, Desojo JB. 2012. Tooth-on-tooth
1202 interlocking occlusion suggests macrophagy in the Mesozoic marine crocodylomorph
1203 *Dakosaurus*. *The Anatomical Record* 295(7):1147-1158.
- 1204 Zahradnicek O, Buchtova M, Dosedelova H, Tucker AS. 2014. The development of complex
1205 tooth shape in reptiles. *Frontiers in Physiology* 5:74.
- 1206 Zelditch ML, Sheets HD, Fink WL. 2003. The ontogenetic dynamics of shape disparity.
1207 *Paleobiology* 29(1):139-156.
- 1208 Zelditch M, Swiderski D, Sheets DH, Fink W. 2004. *Geometric Morphometrics for Biologists: A*
1209 *Primer*. Waltham, MA: Elsevier Academic Press.

1210 **FIGURE LEGENDS**

1211 **Figure 1: Data collection methods.** A) We numbered teeth based on position and host bone
 1212 (only the left teeth are labeled). Teeth P4, M5, and M10 are defined as the enlarged teeth in
 1213 this specimen. B) We photographed each tooth individually, and traced the margins. The
 1214 software converted each outline into 30 equidistant coordinates. Three coordinates were
 1215 transformed into landmarks (magenta) and the rest into semilandmarks (green). C) For skulls,
 1216 we produced an outline from the dorsal perspective, with 50 coordinates on each margin that
 1217 were transformed into landmarks (magenta) and semilandmarks (green). (Specimen depicted:
 1218 *Crocodylus palustris* AMNH 96134.) [Half page width]

1219 **Figure 2: Variability within the first principal component for teeth.** A) Vector diagrams indicate
 1220 the maximum range of variance (vectors) from the mean (points) for both cranial and dentary
 1221 teeth. Landmarks are in magenta and semilandmarks are in green. B) Scores from the first and
 1222 second principal components are plotted in a morphospace, with major taxonomic groupings
 1223 labeled. [Full page width]

1224 **Figure 3: Partial Least Squared (PLS) two-block analysis of shape.** A) Vector diagrams indicate
 1225 shape variance of PLS1 for skull shape (Block 1) and average tooth shape (Block 2). B) PLS1
 1226 scores for both blocks were regressed, with colors and shapes representing species. Regression
 1227 information is listed. [Full page width]

1228 **Figure 4: Heterodonty represented by Foote's morphological disparity.** Ln scaling of
 1229 Morphological Disparity (MD) for size (A) and shape (B) are plotted against the Ln of skull length.
 1230 Colors and shapes represent species, and regression information is listed. [Half page width]

1231 **Figure 5: Heterodonty by tooth position.** Centroid Size (CS) and principal component one (PC1)
 1232 for extant Alligatoroidea (A,D), Crocodyloidea (B,E) , and remaining taxa (C,F), plotted against
 1233 position along the arcade. Colors represent major taxonomic groups. See Figure 2 for a visual
 1234 representation of shape change depicted by PC1 scores. [Full page width]

1235 **Figure 6: Regression information for shape heterodonty.** Slope (m) and y-intercept (b) data for
 1236 regressions of the first principal component plotted against tooth position for individuals. Error
 1237 bars indicate 95% confidence intervals, and colors and shapes represent species. Regression
 1238 statistics are available in Table S2. [Full page width]

1239 **Figure 7: Direct comparisons between selected extant and extinct taxa.** The size axis
 1240 represents normalized centroid size (ranging from 0.00 to 0.20), and the shape axis represents
 1241 scores from the first principal component (ranging from -0.04 to 0.04). Taxa are grouped by A)
 1242 modern specimens with high molariform distal teeth, B) modern specimens that display high
 1243 size heterodonty, C) slender-snouted specimens, D) *Hamadasuchus rebouli*, E) *Borealosuchus*
 1244 *sternbergii* and *Leidyosuchus canadensis*, and F) fossil globidont specimens. (Note:
 1245 *Borealosuchus sternbergii* teeth were not size normalized by its own skull length, as indicated
 1246 by hollow bars.) Scale = five cm. [Full page width]

Figure 1

Data collection methods

A) We numbered teeth based on position and host bone (only the left teeth are labeled). Teeth P4, M5, and M10 are defined as the enlarged teeth in this specimen. B) We photographed each tooth individually, and traced the margins. The software converted each outline into 30 equidistant coordinates. Three coordinates were transformed into landmarks (magenta) and the rest into semilandmarks (green). C) For skulls, we produced an outline from the dorsal perspective, with 50 coordinates on each margin that were transformed into landmarks (magenta) and semilandmarks (green). (Specimen depicted: *Crocodylus palustris* AMNH 96134.) [Half page width]




Figure 2

Variability within the first principal component for teeth.

A) Vector diagrams indicate the maximum range of variance (vectors) from the mean (points) for both cranial and dentary teeth. Landmarks are in magenta and semilandmarks are in green. B) Scores from the first and second principal components are plotted in a morphospace, with major taxonomic groupings labeled. [Full page width]




Figure 3

Partial Least Squared (PLS) two-block analysis of shape

A) Vector diagrams indicate shape variance of PLS1 for skull shape (Block 1) and average tooth shape (Block 2). B) PLS1 scores for both blocks were regressed, with colors and shapes representing species. Regression information is listed. [Full page width]






Figure 4

Heterodonty represented by Foote's morphological disparity

Ln scaling of Morphological Disparity (MD) for size (A) and shape (B) are plotted against the Ln of skull length. Colors and shapes represent species, and regression information is listed.

[Half page width]



ln(Skull Length)




Figure 5

Heterodonty by tooth position

Centroid Size (CS) and principal component one (PC1) for extant Alligatoroidea (A,D), Crocodyloidea (B,E), and remaining taxa (C,F), plotted against position along the arcade. Colors represent major taxonomic groups. See Figure 2 for a visual representation of shape change depicted by PC1 scores. [Full page width]




Figure 6

Regression information for shape heterodonty

Slope (m) and y-intercept (b) data for regressions of the first principal component plotted against tooth position for individuals. Error bars indicate 95% confidence intervals, and colors and shapes represent species. Regression statistics are available in Table S2. [Full page width]




Figure 7

Direct comparisons between selected extant and extinct taxa

The size axis represents normalized centroid size (ranging from 0.00 to 0.20), and the shape axis represents scores from the first principal component (ranging from -0.04 to 0.04). Taxa are grouped by A) modern specimens with high molariform distal teeth, B) modern specimens that display high size heterodonty, C) slender-snouted specimens, D) *Hamadasuchus rebouli*, E) *Borealosuchus sternbergii* and *Leidyosuchus canadensis*, and F) fossil globidont specimens. (Note: *Borealosuchus sternbergii* teeth were not size normalized by its own skull length, as indicated by hollow bars.) Scale = five cm. [Full page width]

