

Revision of the Afro-Madagascan genus *Costularia* (Schoeneae, Cyperaceae): infrageneric relationships and species delimitation (#33066)

1

First submission

Editor guidance

Please submit by **17 Dec 2018** for the benefit of the authors (and your \$200 publishing discount).



Structure and Criteria

Please read the 'Structure and Criteria' page for general guidance.



Custom checks

Make sure you include the custom checks shown below, in your review.



Raw data check

Review the raw data. Download from the [materials page](#).



Image check

Check that figures and images have not been inappropriately manipulated.

Privacy reminder: If uploading an annotated PDF, remove identifiable information to remain anonymous.

Files

Download and review all files from the [materials page](#).

20 Figure file(s)
2 Table file(s)
2 Raw data file(s)

! Custom checks

DNA data checks

- ! Have you checked the authors [data deposition statement](#)?
- ! Can you access the deposited data?
- ! Has the data been deposited correctly?
- ! Is the deposition information noted in the manuscript?

Field study

- ! Have you checked the authors [field study permits](#)?
- ! Are the field study permits appropriate?

New species checks

- ! Have you checked our [new species policies](#)?
- ! Do you agree that it is a new species?
- ! Is it correctly described e.g. meets ICZN standard?




Structure and Criteria

Structure your review

The review form is divided into 5 sections. Please consider these when composing your review:

1. BASIC REPORTING
2. EXPERIMENTAL DESIGN
3. VALIDITY OF THE FINDINGS
4. General comments
5. Confidential notes to the editor






 You can also annotate this PDF and upload it as part of your review

When ready [submit online](#).





Editorial Criteria

Use these criteria points to structure your review. The full detailed editorial criteria is on your [guidance page](#).





BASIC REPORTING

-  Clear, unambiguous, professional English language used throughout.
-  Intro & background to show context. Literature well referenced & relevant.
-  Structure conforms to [PeerJ standards](#), discipline norm, or improved for clarity.
-  Figures are relevant, high quality, well labelled & described.
-  Raw data supplied (see [PeerJ policy](#)).

EXPERIMENTAL DESIGN

-  Original primary research within [Scope of the journal](#).
-  Research question well defined, relevant & meaningful. It is stated how the research fills an identified knowledge gap.
-  Rigorous investigation performed to a high technical & ethical standard.
-  Methods described with sufficient detail & information to replicate.

VALIDITY OF THE FINDINGS

-  Impact and novelty not assessed. Negative/inconclusive results accepted. *Meaningful* replication encouraged where rationale & benefit to literature is clearly stated.
-  Data is robust, statistically sound, & controlled.
-  Speculation is welcome, but should be identified as such.
-  Conclusions are well stated, linked to original research question & limited to supporting results.

Standout reviewing tips

3



The best reviewers use these techniques

Tip

Support criticisms with evidence from the text or from other sources

Example

Smith et al (J of Methodology, 2005, V3, pp 123) have shown that the analysis you use in Lines 241-250 is not the most appropriate for this situation. Please explain why you used this method.

Give specific suggestions on how to improve the manuscript

Your introduction needs more detail. I suggest that you improve the description at lines 57- 86 to provide more justification for your study (specifically, you should expand upon the knowledge gap being filled).

Comment on language and grammar issues

The English language should be improved to ensure that an international audience can clearly understand your text. Some examples where the language could be improved include lines 23, 77, 121, 128 – the current phrasing makes comprehension difficult.

Organize by importance of the issues, and number your points

1. Your most important issue
2. The next most important item
3. ...
4. The least important points

Please provide constructive criticism, and avoid personal opinions

I thank you for providing the raw data, however your supplemental files need more descriptive metadata identifiers to be useful to future readers. Although your results are compelling, the data analysis should be improved in the following ways: AA, BB, CC

Comment on strengths (as well as weaknesses) of the manuscript

I commend the authors for their extensive data set, compiled over many years of detailed fieldwork. In addition, the manuscript is clearly written in professional, unambiguous language. If there is a weakness, it is in the statistical analysis (as I have noted above) which should be improved upon before Acceptance.

Revision of the Afro-Madagascan genus *Costularia* (Schoeneae, Cyperaceae): infrageneric relationships and species delimitation

Isabel Larridon^{Corresp., 1, 2}, Linah Rabarivola³, Martin Xanthos¹, A. Muthama Muasya⁴

¹ Identification and Naming, Royal Botanic Gardens Kew, Richmond, Surrey, United Kingdom

² Department of Biology, Research Group Spermatophytes, Ghent University, Gent, Belgium

³ Kew Madagascar Conservation Centre, Antananarivo, Madagascar

⁴ Department of Biological Sciences, Bolus Herbarium, University of Cape Town, Rondebosch, South Africa

Corresponding Author: Isabel Larridon

Email address: i.larridon@kew.org

A recent molecular phylogenetic study revealed four distinct evolutionary lineages in the genus *Costularia* s.l. (Schoeneae, Cyperaceae, Poales). Two lineages are part of the *Oreobolus* clade of tribe Schoeneae: the first being a much-reduced genus *Costularia* s.s., and the second a lineage endemic to New Caledonia for which a new genus *Chamaedendron* was erected. The other two lineages were shown to be part of the *Tricostularia* clade of tribe Schoeneae. Based on morphological and molecular data, the genus *Costularia* is here redelimited to represent a monophyletic entity including 15 species, which is restricted in distribution to southeastern Africa (Malawi, Mozambique, South Africa, Swaziland, Zimbabwe), Madagascar, the Mascarenes (La Réunion, Mauritius), and the Seychelles (Mahé). Molecular phylogenetic data based on two nuclear markers (ETS, ITS) and a chloroplast marker (*trnL-F*) resolve the studied taxa as monophyletic where multiple accessions could be included (except for *C. laxa* and *C. purpurea*, which are now considered conspecific), and indicate that the genus dispersed once to Africa, twice to the Mascarenes, and once to the Seychelles. Two endemic species from Madagascar are here described and illustrated as new to science, as is one additional species endemic to La Réunion. Two taxa previously accepted as varieties of *C. pantopoda* are here recognised at species level (*C. baronii* and *C. robusta*). We provide a taxonomic revision including an identification key, species descriptions and illustrations, distribution maps, and assessments of conservation status for all species.

Revision of the Afro-Madagascan genus *Costularia* (Schoeneae, Cyperaceae): infrageneric relationships and species delimitation

Isabel Larridon^{1,2}, Linah Rabarivola³, Martin Xanthos¹, A. Muthama Muasya⁴

¹ Identification and Naming, Royal Botanic Gardens Kew, Richmond, Surrey, United Kingdom

² Department of Biology, Research Group Spermatophytes, Ghent University, Gent, Belgium

³ Kew Madagascar Conservation Centre, Antananarivo, Madagascar

⁴ Department of Biological Sciences, Bolus Herbarium, University of Cape Town, Rondebosch, South Africa

Corresponding Author:

Isabel Larridon¹

Royal Botanic Gardens Kew, Richmond, Surrey, TW9 3AE, United Kingdom

Email address: i.larridon@kew.org

Abstract

A recent molecular phylogenetic study revealed four distinct evolutionary lineages in the genus *Costularia* s.l. (Schoeneae, Cyperaceae, Poales). Two lineages are part of the *Oreobolus* clade of tribe Schoeneae: the first being a much-reduced genus *Costularia* s.s., and the second a lineage endemic to New Caledonia for which a new genus *Chamaedendron* was erected. The other two lineages were shown to be part of the *Tricostularia* clade of tribe Schoeneae. Based on morphological and molecular data, the genus *Costularia* is here redelimited to represent a monophyletic entity including 15 species, which is restricted in distribution to southeastern Africa (Malawi, Mozambique, South Africa, Swaziland, Zimbabwe), Madagascar, the Mascarenes (La Réunion, Mauritius), and the Seychelles (Mahé). Molecular phylogenetic data based on two nuclear markers (ETS, ITS) and a chloroplast marker (*trnL-F*) resolve the studied taxa as monophyletic where multiple accessions could be included (except for *C. laxa* and *C. purpurea*, which are now considered conspecific), and indicate that the genus dispersed once to Africa, twice to the Mascarenes, and once to the Seychelles. Two endemic species from Madagascar are here described and illustrated as new to science, as is one additional species endemic to La Réunion. Two taxa previously accepted as varieties of *C. pantopoda* are here recognised at species level (*C. baronii* and *C. robusta*). We provide a taxonomic revision including an identification key, species descriptions and illustrations, distribution maps, and assessments of conservation status for all species.

Introduction

The genus *Costularia* C.B. Clarke (Cyperaceae tribe *Schoeneae*) was previously circumscribed as including 25 species (Govaerts *et al.*, 2018). However, a recent molecular phylogenetic study firmly established the polyphyly of the genus as previously circumscribed (Larridon *et al.*, 2018a), which was already hinted at in previous works (Seberg, 1986, 1988a, b; Browning & Gordon-Gray, 1995; Bruhl, 1995; Zhang *et al.*, 2004; Verboom, 2006; Viljoen *et al.*, 2013) and supported in the most recent family-wide study (Semmour *et al.*, 2018). Larridon *et al.* (2018a) showed that *Costularia* s.l. included four distinct lineages: (1) *Costularia* s.s. (11 spp.), (2) *Chamaedendron* Larridon (5 spp.), (3) a group largely conforming to *Costularia* subgenus *Lophoschoenus* sensu Kükenthal (1939) (8 spp.) that is now considered to be part of a redelimited genus *Tetraria*, nom. cons. prop. (Larridon *et al.*, 2017a, 2018a, b), and (4) the species *Xyroschoenus hornei* (C.B. Clarke) Larridon (basionym: *Schoenus hornei* C.B. Clarke, nom. cons. prop.; Larridon *et al.*, 2017b, 2018a). Only the latter species and species of *Costularia* s.s. are found in Africa and/or on the islands in the Indian Ocean (Henriette *et al.*, 2015; Larridon *et al.*, 2018a). Three earlier publications revised species of *Costularia* s.s. (Chermeson, 1937; Kükenthal, 1939; Henriette *et al.*, 2015) since Clarke (1898) erected the genus based on the species *Costularia natalensis* C.B. Clarke, as well as a species now included in *Capeobolus* Browning (*Costularia brevicaulis* C.B. Clarke; Browning & Gordon-Gray, 1999). Table 1 gives an overview of the seven species of *Costularia* s.s. treated by Chermeson (1937), the nine species treated by Kükenthal (1939), and the 11 currently recognised species (Govaerts *et al.*, 2018). *Costularia* s.s. as here accepted more or less equates to *Costularia* subgenus *Costularia* sensu Kükenthal (1939) (Larridon *et al.*, 2018a). The *Catalogue of the Vascular Plants of Madagascar* states that there may still be a number of new Madagascan endemic species to describe (Tropicos.org, 2018). This study is part of a wider effort to revise genera of Cyperaceae from Africa and Madagascar (Bauters *et al.*, 2018, *accepted*; Galán Díaz *et al.*, *submitted*). In this paper, (1) the genus *Costularia* is redelimited as a monophyletic entity, (2) relationships between the species and species limits are investigated based on molecular sequenced data, and (3) previously overlooked species are placed in a phylogenetic context and formally described. A taxonomic treatment including an identification key to all species, species descriptions and illustrations, distribution maps, and assessments of conservation status are provided.

Materials & Methods

Ethics statement

The specimens studied were collected as a part of field expeditions before the 2010 AETFAT conference held in Antananarivo, Madagascar funded by a grant from the Research Foundation - Flanders (FWO) (K204910N), and with support of the Department of Biology, Ghent University, Belgium. Permits to collect and export these specimens were issued by the Madagascar authorities: a collecting permit for Cyperaceae in Madagascar

(N°082/10/MEF/SG/DGF/DCB.SAP/SLRSE - Isabel Larridon) was provided by ANGAP Madagascar National Parks authority.

Taxonomy

The electronic version of this article in Portable Document Format (PDF) will represent a published work according to the International Code of Nomenclature for algae, fungi, and plants (ICN), and hence the new names contained in the electronic version are effectively published under that Code from the electronic edition alone. In addition, new names contained in this work which have been issued with identifiers by IPNI will eventually be made available to the Global Names Index. The IPNI LSIDs can be resolved and the associated information viewed through any standard web browser by appending the LSID contained in this publication to the prefix "http://ipni.org/". The online version of this work is archived and available from the following digital repositories: PeerJ, PubMed Central, and CLOCKSS.

Molecular study

All known *Costularia s.s.* species, except *C. microcarpa* (Cherm.) Kük. which is only known from its type and *C. brevifolia* Cherm. which is rare in collections were sampled using multiple accessions per taxon where possible. Additionally, samples were included from several taxa potentially representing new species. The outgroup taxa, selected based on Larridon *et al.* (2018a), consist of nine species representing the other four genera of the *Oreobolus* clade of tribe Schoeneae. A total of 36 samples (15 newly sequenced) from 24 different taxa were used for this study. The samples with species names, voucher information, origin and GenBank accession numbers for the sequences, are given in Supplemental Information File Table S1. The DNA extraction protocol, markers (ETS, ITS and *trnL-F*), and material and methods for PCR amplification and sequencing and for obtaining alignments follow Larridon *et al.* (2018a). Sequences were assembled and edited in Geneious R8 (<http://www.geneious.com>, Kearse *et al.*, 2012), aligned using MAFFT 7 (Katoh *et al.*, 2009; Katoh & Standley, 2013) with 'maxiterate' and 'tree rebuilding number' set to 100 (long run), afterwards, alignments were checked manually in PhyDE 0.9971 (Müller *et al.*, 2010). The alignments used to produce the phylogenies are available as a Supplemental Information File Data S2.

We first inferred the gene trees for each of the three regions separately to identify potential incongruence. As there were no instances of conflict at well-supported nodes (Supplemental Information Files Figs. S3–S8), the matrices of the three regions were concatenated for the downstream analyses. PartitionFinder 2.1.1 (Lanfear *et al.*, 2012) was used to determine an appropriate data-partitioning scheme from potential partitions that were defined *a priori* (in this case, each marker was treated as a separate partition), as well as the best-fitting model of molecular evolution for each partition, using the Bayesian Information Criterion. PartitionFinder confirmed the *a priori* data-partitioning scheme, and the GTR+I+Γ (invgamma) model of sequence evolution was determined to be the best-fitting model for the two nrDNA

markers, while the GTR+ Γ (gamma) model of sequence evolution was determined to be the best-fitting model for the *trnL-F* partition in the concatenated data set.

Maximum likelihood (ML) analyses of the optimally partitioned data were performed using RAxML 8.2.10 (Stamatakis, 2014). The search for an optimal ML tree was combined with a rapid bootstrap analysis of 1000 replicates. Partitioned analyses were conducted using Bayesian Inference (BI) in MrBayes 3.2.6 (Ronquist et al., 2012). Rate heterogeneity, base frequencies, and substitution rates across partitions were unlinked. The analysis was allowed to run for 100 million generations across four independent runs with four chains each, sampling every 10,000 generations. Convergence, associated likelihood values, effective sample size (ESS) values and burn-in values of the different runs were verified with Tracer 1.5 (Rambaut & Drummond, 2007). The first 25% of the trees from all runs were excluded as burn-in before making a majority-rule consensus of the 30,000 posterior distribution trees using the “sumt” function. All phylogenetic analyses were run using the CIPRES portal (<http://www.phylo.org/>; Miller et al., 2011), and were executed for both full and reduced sampling alignments. Trees were drawn using TreeGraph2 (Stöver & Müller, 2010).

Morphological study

Herbarium specimens of BR, G, GENT, K, L, MAU, P, REU, TAN and UPOS (Thiers, continuously updated) were studied morphologically using a Leica (Leica Microsystems, Wetzlar, Germany) binocular microscope. Where possible, links to imaged type specimens are provided (Catalogue des herbiers de Genève, 2018; HerbCat, 2018; Muséum national d'Histoire naturelle, 2018).

Species distributions and conservation assessments

Information on locality data was obtained from the studied herbarium records (see Taxonomic Treatment and Supplemental Information File Data S3). Georeferenced localities were used to map the distribution of the *Costularia* species studied in SimpleMappr (Shorthouse & David, 2010). The extent of occurrence (EOO) and area or occupancy (AOO) of the species were calculated in GeoCAT (Bachman et al., 2011), where the AOO was based on a user defined cell width of 2 km in line with IUCN Red List criteria (IUCN, 2012). Conservation assessments were prepared according to the guidelines to the IUCN Red List categories and criteria (IUCN, 2012; IUCN Standards and Petitions Subcommittee, 2014).

Results

Molecular study

The multiple-locus BI topology (Fig. 1) did not differ from the multiple-locus ML tree (Supplemental Information File Fig. S9), except for the sister relationship of clade B. Clade B is sister to clade A in multiple-locus BI topology (Fig. 1), but sister to clade C in the multi-locus ML-analysis (Supplemental Information File Fig. S9). This relationship is not supported in either result. Four subclades are well supported in the phylogenetic hypothesis (Fig. 1) of the

Oreobolus clade of tribe Schoeneae: *Costularia* (1, 100), *Chamaedendron* (1, 100), *Capeobolus* + *Cyathocoma* Nees (1, 100), and *Oreobolus* R.Br. (0.81). In *Costularia*, four main clades are well supported: clade A (1, 100), and clade B (1, 100), clade C (1, 100) and clade D (1, 98). In clade A, two species *C. leucocarpa* (Ridl.) H.Pfeiff. + *C. andringitrensis* (formally described in the Taxonomic Treatment) form a supported clade (88) in which *C. leucocarpa* is well supported as a monophyletic lineage (1, 100). These two species are sister to a monophyletic *Costularia natalensis* (1, 99). In turn, *Costularia itremoensis* (formally described in the Taxonomic Treatment) is sister to these three species. Clade B consists of the *C. pantopoda* (Baker) C.B.Clarke ex Cherm. species complex with each of the taxa: *C. baronii* C.B.Clarke (1, 95) and *C. robusta* (0.99, 80) (formally recognised at species level in the Taxonomic Treatment) forming well supported monophyletic lineages separate from the typical *C. pantopoda* (Fig. 1). In all analyses, the *C. baronii* and *C. robusta* appear more closely related to each other then to *C. pantopoda* s.s. (Fig. 1; Supplemental Information Files Figs. S3–S9). A last taxon part of this clade, sister to the rest, is a taxon currently identified as *Costularia* cf. *pantopoda*. Clade C contains two well supported subclades, one of which (1, 98) includes specimens identified as *C. laxa* Cherm. and as *C. purpurea* Cherm. The latter taxa are supported as monophyletic in some but not all analyses. The second well supported subclade (1, 100) consists of individuals of *C. melicoides* (Poir.) C.B.Clarke. Clade D includes four species: a well supported *C. xipholepis* (Baker) Henriette & Senterre (1, 100), a single accession of *C. melleri* (Baker) C.B.Clarke ex Cherm., and a well supported subclade (1, 90) including *C. cadetii* (formally described in the Taxonomic Treatment) and *C. humbertii* Bosser.

Morphological study, species distributions and conservation assessments

Morphological results, species distributions and conservation assessments are elaborated in the Taxonomic Treatment. The additional herbarium specimens studied per taxon are listed in Supplemental Information File Data S3.

Discussion

Four clades are here retrieved in the *Oreobolus* clade of tribe Schoeneae (Fig. 1): *Costularia*, *Chamaedendron*, *Capeobolus* + *Cyathocoma*, and *Oreobolus*, in line with recent studies (Larridon et al., 2018a; Semmouri et al., 2018). Viljoen et al. (2013) reconstructed the ancestral areas for tribe Schoeneae but did not obtain a clear result for the ancestral area of the *Oreobolus* clade. Both *Capeobolus* and *Cyathocoma* are found in the Cape Floristic Region, while *Chamaedendron* is endemic to New Caledonia, and *Oreobolus* has a wider distribution in the southern hemisphere (Malesia to Australasia, Hawaiian Islands, Costa Rica to Falkland Islands; Govaerts et al., 2018).

Of the four main clades in *Costularia*, only clade B is restricted to Madagascar, while the others include Madagascar endemics and species found on the Indian Ocean islands and/or mainland Africa (Fig. 1). In clade A, the Madagascan endemic species *C. leucocarpa* and *C. andringitrensis* are sister to *C. natalensis* from southeastern Africa. *Costularia itremoensis* from

South Central Madagascar is sister to these three species (Fig. 1). Clade B consists of the *C. pantopoda* species complex with *C. baronii* and *C. robusta* forming well supported monophyletic lineages separate from the typical *C. pantopoda* (Fig. 1). *Costularia robusta* was first described as *Costularia baronii* var. *robusta* Cherm. This concurs with our results in which *C. baronii* and *C. robusta* are sister species (Fig. 1). A last taxon part of this clade, sister to the others, is currently identified as *Costularia cf. pantopoda*. This taxon needs further study since it is only known from a single collection with little metadata information. Potentially related to clade B is *C. microcarpa*, a species first described by Chermezon (1937) under *C. baronii* (as *C. baronii* C.B. Clarke var. *microcarpa* Cherm.), and later raised to species level by Kükenthal (1939). Clade C contains two well supported subclades, one of which includes specimens identified as *C. laxa* and *C. purpurea*. These taxa were not always recovered as monophyletic (Supplemental Information Files Figs. S3–S8). Morphological study confirmed that the delimitation between these taxa is unclear, resulting in the decision to combine the two species under a single species name: *C. purpurea* (see Taxonomic Treatment). The second well supported subclade of Clade C consists of individuals of *C. melicoides* (Fig. 1). *Costularia melicoides* is endemic to the Mascarenes where it is found on both the islands of La Réunion and Mauritius. Clade D includes four species: *C. xipholepis*, a recently rediscovered species endemic to the Seychelles (Henriette et al., 2015), a single accession of *C. melleri* from Central Madagascar, and a subclade including *C. cadetii* and *C. humbertii*. The newly discovered *C. cadetii* and the species *C. humbertii* stand out due to their smaller stature and shorter leaves. Both are restricted to high-elevation zones, but what is remarkable is that while *C. humbertii* is found in the northeast of Madagascar (Marojejy National Park), *C. cadetii* is endemic to La Réunion where it is limited to peaks of the island's volcanoes. This sister relationship points at a long-distance dispersal event likely from the mountain tops of northeastern Madagascar to those of La Réunion. A species potentially related to *C. humbertii* is *C. brevifolia* with which it shares characters such as a robust caudex, short stature, and short broad leaves, although it is biogeographically (southeastern Madagascar) and ecologically (low-mid elevation) isolated from it (Fig. 2).

Of the 15 species of *Costularia* recognised here, three-quarters are threatened with extinction because of their restricted distribution ranges and human impact (see Taxonomic Treatment). In Madagascar, habitat destruction and deterioration are the major threats. Additional threats may relate to climate change as some species exclusively occur at (very) high elevation (e.g. *C. cadetii*, *C. humbertii*, *C. robusta*), or to invasive species (e.g. in the Mascarenes). Two species were assessed as Critically Endangered (CR), six as Endangered (EN) and three as Vulnerable (VU) according to IUCN Red List categories and criteria (IUCN, 2012; IUCN Standards and Petitions Subcommittee, 2014). Two endemic but widely distributed species from Madagascar (*C. leucocarpa*, *C. purpurea*) were assessed as Least Concern (LC), as was *C. natalensis*, the only species occurring in mainland Africa. A final species (*C. microcarpa*) could not be assessed at this time due to lack of information and is considered Data Deficient (DD). Further research and fieldwork are needed to study the species of *Costularia*, their

populations and the threats they face.

Taxonomic treatment

Costularia C.B.Clarke in W.H.Harvey & auct. suc. (eds.), Fl. Cap. 7: 274. 1898.

Type: *Costularia natalensis* C.B.Clarke (lectotype designated by Goetghebeur, 1986).

Perennial herbs, small to tall, tufted or more rarely shortly rhizomatous, caudex sometimes present. *Culms* scapose or with few nodes. *Leaves* usually both basal and caudal; basal leaves with poorly defined sheaths; cauline leaves enveloping up to ½ internode length; margins scabrid, spirodistichous, eligulate, blade sometimes deciduous. *Inflorescence* terminal, (contracted) paniculate with few to numerous spikelets; primary bracts ± leaf-like, sheathing. *Spikelets* with several distichous, deciduous glumes, of increasing length, the upper (1–)2 glumes each subtending a flower, enclosed by the wings of the next glume. *Flowers*, lower one (functionally) male (rarely bisexual or absent), upper one bisexual or functionally female (rarely functionally male). *Perianth bristles* 6, fimbriate to ciliate, mostly longer than the nutlet and deciduous with it. *Stamens* 3. *Style* trifid, style base often distinct (at anthesis), thickened, persistent, often scabrid. *Nutlet* ovoid or oblong, rounded trigonous, often 3-ribbed, ± stipitate, beaked, surface smooth or rugulose.

Includes: 15 species.

Distribution: southeastern Africa (Malawi, Mozambique, South Africa, Swaziland, Zimbabwe), Madagascar, the Mascarenes (La Réunion, Mauritius), and the Seychelles (Mahé).

Key to the species of *Costularia*

- 1 Small plants <30 cm tall with flowering culm scarcely exceeding the basal leaves; cauline leaves absent.2
- 1 Plants >30 cm tall with flowering culm exceeding the leaves; cauline leaves present.....3
- 2 Inflorescence a contracted panicle, composed of few to several spikelets; spikelets with lower flower male, upper flower bisexual (endemic to Andringitra Mountains, Madagascar).
.....1. *C. andringitrensis*
- 2 Inflorescence a somewhat contracted panicle, composed of numerous spikelets; spikelets with two bisexual flowers (endemic to La Réunion).....4. *C. cadetii*
- 3 Basal leaves much shorter than the flowering culm; leaf blades 7–15 cm long, apex rounded-obtuse.4
- 3 Basal leaves not conspicuously short compared to the flowering culm; leaf blades longer, apex generally long tapering.....5
- 4 Caudex 4–5 cm wide; basal leaves spirodistichous; leaf blades 7–12 mm wide; pedicels of the spikelets 5–20 mm long (endemic to SE Madagascar).....3. *C. brevifolia*
- 4 Caudex 1–2 cm wide; basal leaves distichously and flabellately inserted on the caudex; leaf blades 5–8 mm wide, sickle-shaped; pedicels of the spikelets 1–4 mm long. (endemic to NE Madagascar).....5. *C. humbertii*

278	5 Spikelets up to 3.8–5 mm long.	7. <i>C. leucocarpa</i>
279	5 Spikelets >5.5 mm long.	6
280	6 Flowers 2, lower bisexual, upper male (or rarely only 1 flower) (Madagascar, Mascarenes).	7
281	6 Flowers 2, lower male, upper bisexual (Africa, Madagascar, Seychelles).	8
282	7 Pedicels of the spikelet erect; glumes reddish-black, with colourless-whitish margins; nutlet	
283	smooth (La Réunion, Mauritius).	8. <i>C. melicoides</i>
284	7 Pedicels of the spikelet generally curved; glumes (dark) purple; nutlet rugulose- reticulate	
285	(Madagascar).	13. <i>C. purpurea</i>
286	8 Glumes 16–18.	9. <i>C. melleri</i>
287	8 Glumes 5–14.	9
288	9 Culm <1 mm wide; leaf blades ≤1.5 mm wide.	12b. <i>C. pantopoda</i> var. <i>gracilenscens</i>
289	9 Culm ≥ 1.5 mm wide; leaf blades wider than 1.5 mm.	10
290	10 Very robust and tall perennial herbs with culms c. 6 mm wide.	11
291	10 Plants less robust with culms ≤5 mm wide.	12
292	11 Caudex not present; glumes 8–12, straw-coloured to purplish striate (endemic to SE	
293	Madagascar).	10. <i>C. microcarpa</i>
294	11 Caudex strongly developed and long; glumes 12–14, purplish black (endemic to N	
295	Madagascar).	14. <i>C. robusta</i>
296	12 Medium sized to tall perennial herb; vegetative culm 17–70 cm × 1.7–3.5 mm; cauline leaves	
297	1–2.	13
298	12 Plants generally taller and more robust; vegetative culm 50–150 cm × 2.5–5 mm; cauline	
299	leaves 2–5.	14
300	13 Peduncles (main inflorescence branches measured from base of primary inflorescence bract to	
301	second order bract) longest 5.5–11 cm; empty glumes 6–11.	6. <i>C. itremoensis</i>
302	13 Peduncles longest 4–5 cm; empty glumes 3–6.	12a. <i>C. pantopoda</i> var. <i>pantopoda</i>
303	14 Leaf blades 30–80 cm long × 2–8 mm (Madagascar).	15
304	14 Leaf blades 70–125 cm × 7–10 mm (Seychelles).	15. <i>C. xipholepis</i>
305	15 Pedicels of the spikelets ≥5 mm long; glumes largest 4–5.5 mm long.	13. <i>C. purpurea</i>
306	15 Pedicels of the spikelets 1–6 mm long; glumes largest 5.5–7 mm long.	16
307	16 Peduncles long (longest up to c. 15 cm); spikelets oblong; glumes largest 6–7 mm long (SE	
308	Africa).	11. <i>C. natalensis</i>
309	16 Peduncles short (longest c. 5–8 cm); spikelets lanceolate; glumes largest 5.5–6 mm long	
310	(endemic to Madagascar).	2. <i>C. baronii</i>
311		
312	1. <i>Costularia andringitrensis</i> Larridon sp. nov. —Figs. 2–4	
313	<i>Type.</i> Madagascar, Fianarantsoa, Haute Matsiatra, Andringitra National Park, Diavolana	
314	Trail, 22°07'28.0"S, 46°52'32.7"E, 2063 m, 18 April 2010, <i>I. Larridon</i> , <i>W. Huygh</i> , <i>M. Reynders</i> ,	
315	<i>A.M. Muasya</i> & <i>Vonona</i> <i>Randrianasolo</i> 2010-0140 (holotype TAN!, isotypes BOL!, GENT!).	
316	<i>Diagnosis:</i> <i>Costularia andringitrensis</i> differs from all other <i>Costularia</i> species from	
317	Madagascar by its small stature with the flowering culm scarcely exceeding the leaves. In this	

aspect it mostly resembles *Costularia cadetii* from La Réunion from which it can easily be distinguished by the latter maturing two nutlets per spikelet.

Small perennial herb, flowering culm up to 24 cm, scarcely exceeding the leaves. *Caudex* absent. *Culm* (excluding the inflorescence) short and slender, 5–7.2 cm × 1.1–1.2 mm. *Basal leaves* distichous, bases of old burnt leaves can be present; leaf sheaths 1.5–2 cm × up to 4 mm, only slightly wider than the leaf blade, indistinct, straw-coloured to green; leaf blades linear, flat, 8–34 cm × 1.2–2.6 mm, margins scabrid. *Cauline leaves* absent. *Inflorescence* a contracted panicle, 12–19 × 0.5 cm, composed of few to several spikelets; inflorescence bracts 6, unequal, sheathing, dark reddish brown, margins scabrid; longest bract 12.5–15 cm × 2.5 mm. *Peduncles* unequal, up to 2.6 cm long, margins smooth to scabrid. *Pedicels of the spikelets* unequal, 1–5 mm long, minutely papillose, margins scabrid. *Spikelets* lanceolate, (4–)5–5.5 × 1.1–2 mm, dark purple. *Glumes* distichous, narrowly ovate, boatshaped, acuminate (upper glumes) to long mucronate (up to c. 1 mm, lower glumes), 3–4 × 1.5–2 mm, dark purple on upper part including mucro if present and pale brown on lower part, margins scabrid; 3 lower glumes empty, 2 upper glumes fertile. *Flowers* 2, lower male, upper bisexual. *Perianth bristles* 6, pale, thin, antrorsly ciliate, up to 13 mm long. *Stamens* 3. *Style* deeply trifid. *Immature nutlet* (see Fig. 3D) rounded trigonous with distinct bulbous style base remaining; ripe nutlets not studied as they were already shed from plants in all available specimens.

Distribution

The species is only known from south-central Madagascar, where it was found in the Andringitra National Park, Haute Matsiatra region, Fianarantsoa province (Fig. 2).

Ecology

This species is found in near rocks in grassland to ericoid shrubland vegetation at 2000–2500 m in elevation.

Phenology

Immature inflorescence observed in November, while the specimen collected in April had already shed its ripe nutlets.

Etymology

The species is named for the Andringitra National Park in Madagascar.

Conservation status

Costularia andringitrensis is a small perennial herb endemic to Madagascar, where it is only known from two specimens and occurs in a restricted area in the Andringitra National Park. It is only known from a single location and a minimum AOO of 8 km². However, there are other potential areas of occurrence for the species that have not yet been explored. The species is threatened by cattle grazing and by fires started for pastoral reasons which can easily get out of

control and enter the National Park (I. Larridon, pers. obs. 2010; F. Rakotonasolo, pers. obs. 2017). Therefore, it is assessed as Critically Endangered: CR B2ab(ii,iii).

Notes

As is common with high elevation Cyperaceae species (I. Larridon, pers. obs.), *Costularia andringitrensis* is characterised by very dark spikelets. In the molecular phylogenetic hypothesis (Fig. 1), it is retrieved as sister to *C. leucocarpa*.

Although species of tribe Schoeneae are adapted to natural fire, if fire frequency is increased, especially by herders, this can threaten their regeneration (A.M. Muasya, personal observations). However, complete absence of fire can also be a threat as most species occur in habitats where open/forest are alternative states. Forests are kept out by the fire, whose absence could lead to forest encroachment. Most species of tribe Schoeneae are shade intolerant and thus would die if shaded.

2. *Costularia baronii* C.B.Clarke in W.H.Harvey & auct. suc. (eds.), Fl. Cap. 7: 274 (1898) = *Costularia pantopoda* var. *baronii* (C.B.Clarke) Kük., Repert. Spec. Nov. Regni Veg. 41: 67 (1939)—Figs. 5, 6

Type (lectotype designated here). Madagascar, Central Madagascar, R. Baron 3316 (holotype: [K000244885!](#), isotype: [MNHN-P-P00459989!](#)).

Robust perennial herb. Culms 20–80 cm × c. 5 mm, generally quite robust. *Basal leaves* with leaf blades 40–80 cm × 2–6 mm wide, flat. *Cauline leaves* 2. *Inflorescence* a narrow, tight, very upright panicle with numerous spikelets; inflorescence bracts 8–11. *Peduncles* erect, the longest 5–8 cm. *Pedicels of the spikelets* erect, 1–5 mm long. *Spikelets* lanceolate, 6–8 × 1.5–2 mm. *Glumes* 8–12, reddish brown to black, lanceolate, subobtuse, *strongle* distichous, the largest 5.5–6 mm long, lower 6–10 empty; empty glumes much smaller than the fertile glumes. *Nutlet* subglobose, weakly trigonous, 2.25 mm long, rugolose, greyish green; beak 0.75 mm long, obtuse, not depressed at the base, almost as wide as the nutlet.

Distribution

Costularia baronii occurs in the Antananarivo, Fianarantsoa and Toliara provinces of Madagascar (Fig. 5).

Ecology

It has been found growing in rocky areas (e.g. rock crevices along a stream bank), ericoid shrubland at elevations of 1300 to almost 2200 m.

Phenology

Flowering specimens were collected in March to May, fruiting plants in October, while plants collected in December and January had either shed their nutlets or bore very young inflorescences.

Conservation status

Costularia baronii is distributed in the Antananarivo, Fianarantsoa and Toliara provinces of Madagascar, and occurs in at least four protected areas, i.e. Andringitra, Ankaratra Massif, Andohahela, Ibity Massif and Pic d'Ivohibe. Threats to this taxon need further investigation but in the Andringitra National Park, its habitat and area of occupancy are impacted negatively by cattle grazing and by fires started for pastoral reasons which can easily get out of control and enter the National Park (*I. Larridon, pers. obs. 2010; F. Rakotonasolo, pers. obs. 2017*). Based on ten georeferenced herbarium specimens, the species occurs in at least seven locations and has an estimated AOO of 36 km² and an EOO of 16292 km². Using IUCN criteria, it can be assessed as VU B1ab(ii,iii)+2ab(ii,iii).

Notes

Chermezon (1937) identified Humbert 7008 as *Costularia pantopoda* var. *pantopoda*. However, we believe this specimen better fits with the description of *C. baronii*.

3. *Costularia brevifolia* Cherm., Bull. Soc. Bot. France 69: 723. 1922 publ. 1923. \equiv *Tetraria brevifolia* (Cherm.) T.Koyama, J. Fac. Sci. Univ. Tokyo, Sect. 3, Bot. 8: 74. 1961—Figs. 2, 7
Type (lectotype designated here). Madagascar, Toliara, Mananara Bassin, 700 m, June 1919, *H. Perrier de la Bâthie* 12643 (holotype: [MNHN-P-P00459974](#)!; isotype: [MNHN-P-P00459972](#)!, [MNHN-P-P00459973](#)!).

Robust perennial herb. Caudex 10–12 cm \times 4–5 cm. *Culm* (appearing) lateral, robust, 50–80 cm \times 5–8 mm, smooth, with obtuse edges, slightly compressed. *Basal leaves* spirodistichously inserted on the caudex, leaf sheaths, 3–4 cm \times 3–4 cm, brown, shiny, margins scarious, at the apex abruptly contracted, old sheaths fibrous, leaf blades 7–10 cm \times 7–12 mm, flat, leathery, margins scabrid, revolute, apex rounded-obtuse. *Cauline leaves* 1–3, far apart, sheathing, sheaths brown. *Inflorescence* a panicle c. 45 cm long, loosely compound. *Peduncles* unequal, up to 7.5 cm long. *Pedicels of the spikelets* suberect or curved, 5–20 mm long. *Spikelets* oblong-lanceolate, compressed, apex subacute, 7–8 mm \times 1.5–2 mm. *Glumes* distichous, oblong-lanceolate, 5–6 mm long, densely imbricate, straw-coloured to brown, purple-tinged, edges only from the keel up sparsely ciliolate, prominently acute or mucronate, lower 3–4 glumes empty, 2 upper glumes fertile. *Flowers* 2, lower male, upper bisexual. *Perianth bristles* 6, pale brown, plumose, three times longer than the nutlet. *Stamens* 3, filaments reddish-brown, anthers linear, connective conical-subulate, purple. *Style* long, deeply trifid, pale, with a triangular thickly cone-shaped persistent base. *Nutlet* 1.5 mm long, brown, obovate-oblong, with an attenuate base.

Distribution

Endemic to southeastern Madagascar and only known from the Atsimo Atsinana and Anosy regions in the Fianarantsoa and Toliara provinces (Fig. 2).

Ecology

It has been found growing on humid rocks in peatlands, on laterite and granite in tropical forest, and in faults of gneiss rock escarpments, at elevations of (200–)600–900 m.

Phenology

Flowering specimens were collected from in March. Young inflorescences can be observed on the specimens collected in February, while old inflorescences remain on the plants until October–November.

Conservation status

Costularia brevifolia is a robust perennial herb, limited in distribution to the forested mountain ranges of south-eastern Madagascar at mid-elevation. It is known from only four locations. The estimated extent of occurrence (EOO) is 2463 km² and the area of occupancy is 20 km². According to the limited metadata available this species likely occurs in the protected areas of Midongy du Sud and Andohahela. Fire (natural or man-made) and disturbance or elimination as a result of deforestation for agricultural extension are the major threats which affect this species. Hence, it is assessed as Endangered B1ab(i,ii,iii,iv)+B2ab(i,ii,iii,iv).

Notes

One of only two short-leaved *Costularia* species in Madagascar; the other being *C. humbertii*. *Costularia brevifolia* is endemic to southeastern Madagascar, while *C. humbertii* is endemic to the Marojejy National Park in northeastern Madagascar. Although both are likely related based on morphological resemblance, amplification of DNA extracted from the limited material available of *C. brevifolia* was unsuccessful, so a close relationship between the two short leaved species remains unconfirmed.

4. *Costularia cadetii* Larridon sp. nov. —Figs. 8–10

Type. LA RÉUNION, Saint-Benoît, Sainte-Rose, Pas de Bellecombe, 21°13'21.38"S, 55°41'17.27"E, 2328 m, 6 March 2017, J.I. Marquez-Corro et al. 04JMC17 (holotype K!, isotypes UPOS!).

Diagnosis: This species is closely related to *C. humbertii* from northern Madagascar, from which it differs in its smaller habit, absence of a caudex, the basal leaves equaling or overtopping the flowering culm, and having two bisexual flowers. It can be distinguished from the only other species of *Costularia* on La Réunion by its much smaller habit and having two bisexual flowers.

Small perennial herb, flowering culm up to 28 cm, scarcely exceeding the leaves. *Caudex* absent or short (c. 0.5 mm wide). *Culm* slender, 4–12.5 cm × 1.7–1.9 mm. *Basal leaves* distichous; leaf sheaths 2.5–2.8 cm × 6–7 mm, reddish-purplish brown; leaf blades linear, flat, 8.5–29 cm × 1.4–4 mm, scabrid on the margins. *Cauline leaves* absent. *Inflorescence* a

somewhat contracted panicle, $9\text{--}15.5 \times 1$ cm, composed of numerous spikelets; inflorescence bracts 5, unequal, sheathing, dark reddish brown, scabrid on the margins; longest bract $8.5\text{--}13$ cm \times $2\text{--}3$ mm. *Peduncles* unequal, up to 4 cm long, margins scabrid at least near the apex. *Pedicels of the spikelets* unequal, $1\text{--}12$ mm long, minutely papillose, margins scabrid. *Spikelets* lanceolate, $4.5\text{--}5 \times 1.1\text{--}2$ mm, dark purple. *Glumes* distichous, narrowly ovate, boatshaped, acuminate to long mucronate (up to c. 1 mm), $3.5\text{--}4.5 \times 1.8$ mm, dark purple with pale lower third and pale mucro, scabrid to minutely ciliate on the margins, keel and top half of abaxial surface; 2–3 lower glumes empty, 2 upper glumes fertile. *Flowers* 2, both bisexual. *Perianth bristles* 6, pale, antoresly ciliate. *Stamens* 3, anthers linear, $1\text{--}2$ mm long with short conical connective. *Style* deeply trifid. *Nutlet* rounded trigonous, obovate, dark brown with 3 pale bands on the ridges, base attenuate $1.3\text{--}1.5 \times 0.8\text{--}0.9$ mm.

Distribution

Costularia cadetii is a small perennial herb, endemic to La Réunion and found only in the Parc National de La Réunion at elevations of 1700–2400 m (Fig. 10).

Ecology

Found growing in rocky areas, montane grasslands and ericoid vegetation close to volcanic crater edges at high elevation.

Phenology

Flowering specimens were collected in January, fruiting specimens in February and March. The specimens collected by Cadet in May had shed their glumes and nutlets, while the plants collected in November and December were vegetative or immature.

Etymology

The first record of this species (*Cadet 454*) was collected by in 1965, and on its label the following note is written “*Costularia* sp. Further material needed!”. Thérésian Cadet (1937–1987) was a botanist from La Réunion specialised in the vegetation from the Mascarene Islands. He taught plant biology at the University of La Réunion and was one of the main authors of the *Flore des Mascareignes*. This species is named in his honour.

Conservation status

Costularia cadetii is a small perennial herb, endemic to La Réunion. It is known only from three locations within the Parc National de La Réunion. The area, extent and quality of habitat of this species is threatened by fire, volcanic activity and climate change. Based on the seven known herbarium collections, the minimum estimated area of occupancy is 20 km² and the minimum estimated extent of occurrence is 250 km². It is hence categorised as Endangered B1ab(iii)+B2ab(iii).

Notes

Although not closely related to it, morphologically, *C. cadetii* most closely resembles the Madagascan endemic species *C. andringitrensis*, from which it can easily be distinguished by the former maturing two nutlets per spikelet.

5. *Costularia humbertii* Bosser, Naturaliste Malgache 7: 121. 1955—Figs. 2, 11

Type. Madagascar, Antsiranana, Marojejy, 1850-2137 m, 26 March 1949 – 2 April 1949, H. Humbert & G. Cours 23708 (holotype: [MNHN-P-P00459980](#)!; isotypes: [MNHN-P-P00459978](#)!, [MNHN-P-P00459979](#)!, [G00406272](#)!).

Robust perennial herb. Caudex robust, 5–10 cm × 1–2 cm. *Culm* 30–70 cm × 2–3 mm, compressed, smooth. *Basal leaves* distichous, flabellately arranged; leaf sheaths densely imbricate, 2–3 cm long, reddish brown to chestnut coloured; leaf blades leathery, falciform (sickle-shaped), flat, canaliculate, pale green, minutely papillose above, 7–15 cm × 5–8 mm, much shorter than the culm, apex subacute to rounded-obtuse, margins scabrid. *Cauline leaves* 1–3, sheathing. *Inflorescence* a somewhat lax and compound panicle, foliate, 15–25 cm long, composed of 5–7 erect to flexuous fascicles. *Peduncles* unequal, at most 7 cm long, margins scabrid, papillose above. *Pedicels of the spikelets* 1–4 mm long, green. *Spikelets* lanceolate, 5–7.5 mm long, dark purple. *Glumes* 4–6, ovate, distichous, 1-veined, 4–5 × 1 mm, margins minutely ciliate, keel somewhat scabrid, apex acute to mucronate, 2–4 lower glumes empty, 2 upper glumes fertile. *Flowers* 2, lower male, upper bisexual. *Perianth bristles* 6, longer than the nutlet, shortly ciliate. *Stamens* 3, anthers long and linear, apiculate, 3 mm long. *Style* deeply trifid. *Nutlet* 2.5 mm long, smooth, castaneous, trigonous, base attenuate, beak pale, 1 mm, ciliate.

Distribution

Endemic to the Antsiranana province of Madagascar where it is restricted to the high-elevation zone of the Marojejy National Park (Fig. 2).

Ecology

Found growing in swamps in high elevation ericoid vegetation, and on gneiss and quartzite rocks of the mountain ridge, at elevations of 1400–2200 m.

Phenology

Flowering specimens were collected in March to early April. Young inflorescences can be observed on the specimens collected in November-December.

Conservation status

Costularia humbertii is endemic to the Antsiranana province of Madagascar and is limited in distribution to the high-elevation zone of the Marojejy National Park. The minimal area of

occupancy was calculated as 24 km², the estimated extent of occurrence is 17 km² and the species is only known from one location. Fire (natural and man-made) and disturbance of its habitat as a result of logging, firewood collection and charcoal are the major threats which may affect this species. *Costularia humbertii* is only known from seven herbarium collections and has not been collected since 1989. Research is needed to investigate its current status at the single known location. Here, we assess the species as Critically Endangered B1ab(i,ii,iii).

Notes

One of two short leaved *Costularia* species in Madagascar, the other being *C. brevifolia*. In the molecular phylogenetic hypothesis (Fig. 1), *C. humbertii* appears to be closely related with a small high-elevation species from La Réunion (*C. cadetii*).

6. *Costularia itremoensis* Larridon sp. nov. —Figs. 5, 12

Type. Madagascar, Fianarantsoa, Isalo Plateau, W of Ranohira, sandstone rocks, 800–1000 m, 30 July 1928, *H. Humbert & C.F. Swingle 4995* (holotype: MNHN-P-P0318446!, isotypes: K!, TAN).

Diagnosis: This species resembles most closely *Costularia pantopoda* var. *pantopoda* from which it can be distinguished by having longer peduncles (longest 5.5–11 cm vs. 4–5 cm) and more empty glumes (6–11 vs. 3–6).

Medium-sized to tall perennial herb, up to c. 1.4 m. *Culm* 17–68 cm × 1.7–3.5 mm. *Basal leaves* distichous; leaf sheaths 2–6 cm × 7–11 mm, reddish-brown, sometimes burnt old leaf bases present; 20–70 cm × 2.5–5.5 mm, flat, margins scabrid. *Cauline leaves* 1–2, margins scabrid, sheaths brownish. *Inflorescence* a panicle, somewhat contracted when young, but more lax at maturity, 24–68 cm long; inflorescence bracts 6–8, unequal, up to 4 mm wide, sheathing, reddish, margins scabrid. *Peduncles* longest 5.5–11 cm, unequal, flattened, margins scabrid. *Pedicels of the spikelets* erect, 2–11 mm, margins scabrid. *Spikelets* oblanceolate, (4.5–)5.5–10 × 1.2–2.8 mm. *Glumes* 8–13, distichous, the largest 4–6.5 mm long, dark purple above pale below; lower 6–11 glumes empty, acute, increasing in length; upper 2 glumes fertile, more obtuse. *Flowers* 2, lower male, upper bisexual. *Perianth bristles* 6, plumose, long antrorsly ciliate. *Stamens* 3; anthers 6–6.5 mm, linear. *Style* trifid, long. *Nutlet* rounded trigonous, 2.4 × 1.2 mm; beak c. 0.5 mm, pale, ciliate.

Distribution

Costularia itremoensis is endemic to Madagascar and is found in the highlands of South Central Madagascar, in the Fianarantsoa province (Fig. 5).

Ecology

The habitat in which this species is found consists of bare rocks and/or grassland in the Itremo massif (*L. Rabarivola, pers. obs.*). In Isalo, its habitat is dominated by wooded grassland-

bushland mosaic and/or plateau grassland-wooded grassland mosaic (Moat & Smith, 2007) between 800 and 1700 m in elevation.

Phenology

Flowering/fruiting specimens were collected from July to September, plants collected in January to April were immature.

Conservation status

Costularia itremoensis is endemic to Madagascar and is found in the highlands of South Central Madagascar, in the Fianarantsoa province. Based on the limited metadata available it likely occurs in the Itremo new protected area and Isalo National Park. The estimated extent of occurrence was calculated as 7169 km² and the minimal area of occupancy is 20 km². This species is only known from three locations and is threatened by grazing and uncontrolled fire from pastures fire. Its habitat is also threatened by deforestation from logging, firewood collection and mining. Therefore, this species is assessed as Endangered: EN B2ab(i,ii,iii).

Notes

Costularia itremoensis is sister to a clade including *C. leucocarpa* + *C. andringitrensis* and *C. natalensis* (Fig. 1).

7. *Costularia leucocarpa* (Ridl.) H.Pfeiff., Repert. Spec. Nov. Regni Veg. 23: 346. 1927 ≡ *Rhynchospora leucocarpa* Ridl., J. Linn. Soc., Bot. 20: 335. 1883 ≡ *Costularia recurva* C.B.Clarke, Ill. Cyper.: t. LXXXVIII (1909), nom. superfl. ≡ *Tetraria leucocarpa* (Ridl.) T.Koyama, J. Fac. Sci. Univ. Tokyo, Sect. 3, Bot. 8: 75. 1961—Fig. 13, 14

Type (lectotype designated here). Madagascar, Central Madagascar, *R. Baron* 399 (hololectotype [K000244883](#)!; isolectotypes BM, K!, [MNHN-P-P00459985](#)!).

= *Cladium fimbristylloides* Baker, J. Linn. Soc., Bot. 22: 531. 1887. *Type* (lectotype designated here). Madagascar, Central Madagascar, *R. Baron* 4193 (hololectotype [K000244884](#)!; isolectotype [MNHN-P-P00459986](#)!).

Perennial herb up to c. 1 m tall with a woody rhizome (c. 4 mm diam.), caudex sometimes present (c. 7 mm diam.) covered in old leaf sheaths. *Culm* strong but slender towards the apex, 38–60 cm × 1.9–2.6 mm diam., compressed to obtuse angled, grooved, minutely papillose. *Basal leaves* many, distichous; leaf sheaths brown-purplish, 3.5–4.5 cm long; leaf blades long acuminate, flat, margins scabrid. *Cauline leaves* 2, longest up to c. 35 cm × 3 mm, keeled, sheaths long somewhat enlarged, purplish, mouth obliquely cut. *Inflorescence* a semi-compound panicle, 40–70 cm long, narrow, lax, built up out of 8–9 widely spaced fascicles; inflorescence bracts leafy and much overtopping the fascicles, sheath long and brown-purplish. *Peduncles* unequal, up to c. 10 cm long, flattened, scabrid. *Pedicels of the spikelets* (2–)4–10 mm long, arched recurved, scabrid. *Spikelets* oblong-lanceolate, subterete, 3.8–5 × 2 mm. *Glumes* (5–)6(–7), distichous, ovate, subobtuse, above dark purplish, below straw-coloured, nerveless except

the keel, finely ciliate, $3-3.5 \times 1.7-2.4$ mm; 3–5 lower glumes empty, increasing in size; 2 upper glumes fertile. *Flowers* 2, lower male, upper bisexual. *Perianth bristles* 6, \pm as long as the nutlet including its beak, tender, pale brown, antrorsely dense and shortly ciliate, not plumose. *Stamens* 3, filaments and anthers reddish, anthers linear, connective short, wide pyramidal, dark purplish. *Style* rigid, brown, trifid, thickened at base, swollen in the middle, triquetrous, dark-purple, hairy, persistent. *Nutlet* $2.3-2.7 \times 1.5-1.7$ mm swollen-trigonous, pale, bright, smooth, hardly furrowed; beak narrow, 2–2.5 mm long.

Distribution

Endemic to Madagascar, found in the provinces Antananarivo, Antsiranana, Fianarantsoa, Toamasina and Toliara (Fig. 14).

Ecology

The species occurs at mid to (very) high elevation, and has been collected along mountain ridges, from thickets on rock formations, and in open forest.

Phenology

Flowering specimens were collected in December-January, while fruiting specimens were collected in February and March.

Conservation status

Costularia leucocarpa is endemic to Madagascar and found in Antsiranana, Antananarivo, Toamasina, Fianarantsoa and Toliara provinces, where it has been collected along mountain ridges, from thickets on rock formations. The species occurs in Ranomafana National Park, Tsaratanana Reserve Naturelle Intégrale and Manongarivo Special Reserve. The species has a large distribution range (AOO=124 km²) and its estimated EOO is 76,36 km², which is much larger than the threshold for a threatened category. Despite its habitat being under various anthropogenic pressures, *Costularia leucocarpa* is here assessed as Least Concern because (1) no specific threats to its survival have been observed, (2) it is widely distributed in Madagascar, and (3) occurs in several protected areas.

Notes

Since *Costularia recurva* shares syntypes with the older name *C. leucocarpa*, both can be lectotypified to the same specimen (Baron 399 [K000244883](#)) rendering *C. recurva* superfluous.

Previously, the number and position of flowers has been unclear. Chermeson (1937) (in general for the genus) and Kükenthal (1939) (for *C. leucocarpa*) described the male flower to be born by the third glume from the top of the spikelet, the bisexual flower to be born by the second glume from the top, and the topmost glume to be empty and reduced. At first glance, this appears correct, but when comparing *C. leucocarpa* spikelets with those of the other *Costularia* species where the topmost glumes are fertile and the lower glumes are sterile, and taking in consideration

the common metatopic displacement (epicaulescence) of the glumes and flowers on the rachilla in spikelets with distichous glumes of species of Cyperaceae subfamily Cyperoideae (*Vrijdaghs et al., 2010, 2011*), we believe that *C. leucocarpa* represents the common pattern observed in the rest of the genus.

8. *Costularia melicoides* (Poir.) C.B. Clarke, Bull. Misc. Inform. Kew, Addit. Ser. 8: 48 (1908).
 ≡ *Cyperus melicoides* Poir. in J.B.A.M. de Lamarck, Encycl. 7: 273 (1806) ≡ *Machaerina melicoides* (Poir.) Bojer, Hortus Maurit.: 386 (1837) ≡ *Asterochaete elongata* Kunth, Enum. Pl. 2: 312 (1837) ≡ *Schoenus elongatus* Willd. ex Kunth, Enum. Pl. 2: 312 (1837), nom. inval. ≡ *Carpha elongata* (Kunth) Boeckeler, Linnaea 38: 273 (1874) ≡ *Cyclocampe elongata* (Kunth) Benth. & Hook.f., Gen. Pl. 3: 1063 (1883) ≡ *Lophoschoenus elongatus* (Kunth) H. Pfeiff., Beih. Bot. Centralbl. 44(1): 133 (1927) ≡ *Costularia elongata* (Kunth) Kük., Repert. Spec. Nov. Regni Veg. 44: 187 (1938), nom. illeg. ≡ *Tetraria elongata* (Kunth) T. Koyama, J. Fac. Sci. Univ. Tokyo, Sect. 3, Bot. 8: 74 (1961)—Fig. 10

Type. Mauritius, *L.M.A. du Petit Thouars s.n.* (herb. Willd. 1115 fol. 1) (holotype [MNHN-P-P00552880!](#), isotype [MNHN-P-P02284597!](#)).

= *Carpha costularioides* C.B. Clarke, Bull. Misc. Inform. Kew, Addit. Ser. 8: 43 (1908) (earlier as *Carpha aubertii* Nees var. *explicatior* C.B. Clarke, Consp. Fl. Afr. 655 (1894), nom. inval. with mention of type but no description) ≡ *Costularia explicatior* Cherm., Bull. Soc. Bot. France 69: 722 (1922). *Lectotype (designated here)*. Mauritius, Flacq, Le Grand Fond, 280 m, 17 June 1890, *H.H. Johnston s.n.* (holotype [K000244879!](#), isotype MAU0003574!).

Perennial herb with short rhizome with stiff fibres. *Culm* 35–100 cm × 1.5–4 mm, striate, minutely puncticulate. *Basal leaves* crowded, distichous; leaf sheaths 4–6 cm long, indistinct, straw-coloured to purple, multiveined; leaf blades c. 27–60 cm × 2.5–5 mm, flat, indistinctly keeled, tapered at the tip, edges minutely serrulate. *Cauline leaves* 3–4, very distant; leaf sheaths, long, green-purplish, mouth oblique. *Inflorescence* an elongate panicle, 30–85 cm long, with c. 9–11 partial inflorescences, distantly spaced; inflorescence bracts longer than the partial inflorescence they subtend, sheaths purplish. *Peduncles* unequal, up to c. 12 cm. *Pedicels of the spikelets* erect, flattened, margins slightly scabrid, 4–15 mm long. *Spikelets* oblong-lanceolate, 5.5–7.5 × 1.5–2 mm, somewhat flattened. *Glumes* 5–8, distichous, lanceolate-ovate, acuminate, reddish-black, with colourless-whitish margins; lower glumes empty, scabrid on the midvein, mucronatae-aristulate; 2 upper glumes fertile, barely mucronate; rachilla short and erect. *Flowers* 2, lower bisexual, upper male. *Perianth bristles* 6, longer than the nutlet, pale to rusty-coloured, antrorsely densely ciliate-scabrid. *Stamens* 3; anthers linear yellow; connective short, bent, purple. *Style* trifid, base elongate-conical, triquetrous, pale, margins hispidulous, persistent. *Nutlet* swollen-trigonal, longitudinally trisulcate, pale, smooth, 2–2.3 mm long, base long cuneate; beak narrow, 2–2.5 mm long.

Distribution

Endemic to the Mascarene Islands of La Réunion and Mauritius (Fig. 10).

Ecology

Costularia melicoides prefers mid to higher elevation on the island of La Réunion: (500–)900–1700 (–2000) m where it occurs in ericoid thickets (avounes), moist tropical forest, forest with *Acacia heterophylla* (tamarinaie), and humid tickets with *Pandanus* (C. Fontaine pers. comm.). However, in Mauritius, it is found on boulders or in clumps in seasonally-flooded upland marshes near Petrin in the Black River Gorges National Park at elevations of c. 600–700 m, in upland marshes and thickets in Perrier Nature Reserve at c. 550 m in elevation, and in the district Flacq it was found at an elevation of 280 m.

Phenology

Flowering specimens were collected in February (La Réunion) and June (Mauritius), fruiting specimens were collected in April and May and from October to January (La Réunion).

Conservation status

Costularia melicoides occurs in the four regions of La Réunion, and it has been recorded from two regions of Mauritius (Flacq and Plaines Wilhems). Likely, the location at Flacq does not exist anymore (C. Baider, pers. observ.). The species prefers mid to higher elevations on La Réunion, while it is found at lower elevations on Mauritius. It grows in ericoid thickets, forests, on boulders or in clumps in seasonally-flooded upland marshes. Its area of occupancy was estimated as 64 km² and its extent of occurrence as 6805 km², and it occurs at four locations (the Parc National de La Réunion, and in the Black River Gorges National Park, the Perrier Nature Reserve and the protected areas of the Bambou Mountains on Mauritius). The habitat of the species in Le Réunion is threatened by invasive alien species, disturbance due to human activities, and climate change. In Mauritius, similar threats to the habitat of the species exist, in particular due to invasive alien species and the patchiness of the remaining native vegetation. Therefore, *Costularia melicoides* is here assessed as Endangered EN B2ab(i,ii,iii,iv).

Notes

In *Costularia melicoides*, the lower fertile flower is bisexual and the upper fertile flower is male (or sterile), in contrast with the mainland African and Madagascan *Costularia* species (with lower fertile flower male or sterile, and upper fertile flower bisexual), and in contrast with *C. cadetii* from La Réunion with two bisexual flowers.

Notes

All specimens included in the molecular phylogenetic study were collected in La Réunion.

9. *Costularia melleri* (Baker) C.B.Clarke ex Cherm., Cat. Pl. Madag., Cyper. 40. 1931 (*Costularia melleri* C.B.Clarke, Consp. Fl. Afr. 5: 658. 1894, nom. inval.) ≡ *Cladium melleri* Baker, J. Linn. Soc., Bot. 21: 451. 1885 ≡ *Mariscus melleri* (Baker) Fernald, Rhodora 25: 54.

1923 \equiv *Machaerina melleri* (Baker) T.Koyama, Bot. Mag. (Tokyo) 69: 64. 1956 \equiv *Tetraria melleri* (Baker) T.Koyama, J. Fac. Sci. Univ. Tokyo, Sect. 3, Bot. 8: 75. 1961—Fig. 2
Type (*lectotype designated here*). Madagascar, Antananarivo, between Toamasina and Antananarivo, July–August 1862, *C.J. Meller s.n.* (hololectotype: [K000244888!](#), isolectotype: [MNHN-P-P00459987!](#))

Perennial herb up to 180 cm tall with a short, woody rhizome. *Culm* 80–100 cm \times 4–9 mm, robust, slightly compressed, smooth-grooved, tapering to the top. *Basal leaves* leathery; leaf blades 30–36 cm \times 7–15 mm, flat or with inrolled edges, margins scabrid, tapering strongly above the leaf sheaths, very acute; leaf sheaths much broader, 8–10 \times 3.5 cm, dark brown-purplish. *Cauline leaves* 3, up to c. 35 cm, widely spaced; sheaths scarcely enlarged brownish-green base brown, edge obliquely cut. *Inflorescence* a large panicle, 60–100 cm long, up to c. 5–7 cm wide; inflorescence bracts 9–11, sheathing, dark brown-purple. *Peduncles* unequal, up to 12 cm long, quite robust, flattened, margins scabrid. *Pedicels of the spikelets* 3–5 mm long, flattened, margins scabrid, \pm curved. *Spikelets* very numerous, linear-oblong, 7–10 \times 1–1.5 mm. *Glumes* 16–18, pale reddish or light reddish brown with hyaline margins, obtuse, lower 14–16 empty, upper 2 fertile; lower empty glumes very small, increasing in size towards top of spikelet; top glume somewhat reduced, pale, narrow. *Flowers* 2, lower male or sterile, upper bisexual. *Perianth bristles* 6, 2–3 times as long as the nutlet including its beak, rust-coloured, long ciliate, plumose. *Stamens* 3; anthers linear, shortly apiculate. *Style* trifid, long, hispidulous, pale brown, base pyramidal or triangular persistent. *Nutlet* obovoid, quite strongly trigonous, with canaliculate ribs, 1.5 mm long, rugulose, reddish brown; beak 1 mm long.

Distribution

Endemic to Madagascar, occurring in the provinces Antananarivo, Fianarantsoa and Toamasina (Fig. 2).

Ecology

Marshes, humid areas in forest, an elevation of 1000–1500 m.

Phenology

Specimens with very young inflorescences were found in October, November and April, flowering specimens were collected in November and January, fruiting specimens in December. Specimens collected in March and April had already lost their ripe nutlets.

Conservation status

The conservation status of *Costularia melleri* was previously assessed by *Faranirina (2017)* as Endangered B2ab(i,ii,iii,iv,v) based on an estimated AOO of 45 km² (within the limits for Endangered status under the criterion B2) and five known locations. Only one subpopulation occurs in a protected area (Ranomafana National Park; *Larridon et al. 2010-0249*), the other subpopulations are known from unprotected areas subject to agriculture activity (*Faranirina,*

2017). *Faranirina* (2017) projected that the ongoing loss of its habitat will induce a strong continuous decline in the number of subpopulations and mature individuals in the next ten years as well as a continuing decline in its EOO and AOO.

Notes

Several specimens (i.e. *Baron 1026*, *Baron 4104*, *Bosser 122*, *Decary 5826*, *Du Petit Thouars s.n.* and *Meller s.n.*) have fewer glumes but represent very young plants. Clarke (1894) did not validly publish the combination *Costularia melleri*. He stated it to be a “sp. nov.”, although he cited the three syntypes of *Cladium melleri* Baker (*Baron 1026*, *Baron 2846* and *Meller s.n.*) and a 4th specimen (*Baron 4104*). The name lacks any reference to the basionym ICN Art 41.1 and lacks any form of description, so this does not constitute valid publication of the combination according to Art. 41.4 (Turland et al., 2018).

10. *Costularia microcarpa* (Cherm.) Kük., Repert. Spec. Nov. Regni Veg. 46: 69 (1939) ≡ *Costularia baronii* var. *microcarpa* Cherm., Bull. Soc. Bot. France 72: 617 (1925)—Fig. 5

Type: Madagascar, Fianarantsoa, Isalo, 1000 m, October 1924, *H. Perrier de la Bâthie 16704* (holotype: [MNHN-P-P00723561](#)!, isotypes: [MNHN-P-P00459969](#)!, [MNHN-P-P00459970](#)!, [MNHN-P-P00459971](#)!).

Very robust and tall perennial herb. Culm robust, c. 6 mm wide. *Basal leaves* firm, long, 5 mm wide, flat, edges denticulate, involute, long attenuated; leaf sheaths up to 9 cm × 8–10 mm, brownish. *Inflorescence* a long, dense and complex panicle, built up from multiple branched fascicles; inflorescence bracts setaceous, shorter than fascicles, sheaths long and brown. *Peduncles* longest c. 7.5 cm. *Pedicels of the spikelets* 2–4 mm long, curved. *Spikelets* very numerous, most individually pedicellate, less often sessile, oblong ± 6–7.5 × 1–1.5 mm, subterete, arcuate. *Glumes* subdistichous, coriaceous, straw-coloured to purplish-striate; lower 6–10 glumes empty, ovate, subobtusate, with sparsely ciliolate margins; upper 2 fertile glumes lanceolate, acute, the topmost glume somewhat reduced. *Flowers* 2, lower male, upper bisexual. *Perianth bristles* 6, overtopping the nutlet, plumose from base to tip. *Stamens* 3. *Style* long, trifold, base thickened, hispidulous apex persistent. *Nutlet* obovate swollen-trigonous, 2 mm long, base attenuate, reddish, slightly rugulose.

Distribution

Endemic to the Haute Matsiatra region of Fianarantsoa province in Madagascar (Fig. 5).

Ecology

Found growing on shaded, humid sandstone in Isalo National Park at an elevation of c. 1000 m.

Phenology

Only known specimen was collected in October as flowering.

Conservation status

Costularia microcarpa is endemic to Madagascar. It is only found in Ihorombe region of Fianarantsoa province at elevation 1000 m in Isalo National Park. There is insufficient information available to assess the conservation status of this species since it is only known from its type specimen. Therefore, it is categorised as Data Deficient. Research is needed to investigate whether the population of this species at the only known location in Isalo National Park is still present.

Notes

This is one of only two *Costularia* species that could not be sampled for this study, as it is only known from the type specimen. Although unsure at this time, this species is likely part of the *C. pantopoda* species complex. Chermezon (1937) originally published this as a variety under *C. pantopoda* subsp. *baronii* (as *C. baronii* var. *microcarpa*) though Kükenthal (1939) later recognised this taxon at species level.

11. *Costularia natalensis* C.B. Clarke, Consp. Fl. Afr. 5: 658 (1894)—Figs. 15, 16

Type (lectotype designated here). South Africa, KwaZulu-Natal, [without stated locality but probably Noodsberg (Burt, 1988; Browning & Gordon-Gray, 1996)], J. Buchanan 152 ([K000244893!](#)).

Adapted from Browning & Gordon-Gray (1996): *Perennial herb* up to 2.5 m tall, tufted; rhizome 1–1.5 mm in diameter, woody, erect, clothed in thick adventitious roots followed by coarse, persistent leaf bases up to 15 mm wide. *Culm* erect, 50–150 cm in length including inflorescence, 2.5–4.5 mm wide, clothed basally in persistent, brittle, dead, spirodistichously arranged leaf bases that grade into the basal leaves, nodose; nodes dark chestnut brown to blackish-red, occasionally light brown; internodes subtrigonal, slightly flattened or terete, hard, glabrous, glaucous-green. *Basal leaves* numerous with sheaths poorly defined, short in relation to blade length; leaf blades 30–60 cm × (1.5–)3–4 mm, gradually tapering to elongate curling apices ± 1 mm wide, tough, glabrous, margins scabrous. *Cauline leaves* 2–4, with sheaths closed, enveloping up to half of internode length, mostly green except for narrow brown membranous margin to long narrow V-shaped mouth; blades smaller than those of the basal leaves and size decreasing towards the apex of the culm. *Inflorescence* a panicle of closely packed, erect spikelets grouped in ± elongated irregular clusters or appearing interrupted with ± nodding clusters if inflorescence branches and peduncles are long and droop with weight of maturing spikelets and rainwater (robust plants), 55–95 cm long; inflorescence bracts 4–8(–12), reduced in size upwards so that most distal bract apices only shortly surpass spikelet clusters. *Peduncles* unequal, up to c. 16 cm long, flattened, scabrid on the margins. *Pedicels of the spikelets* 2.5–6 mm long, straight to curved, very scabrid. *Spikelets* oblong, 6–9 × 1.8–2.0 mm, dull dark brown. *Glumes* subdistichous, 6–12, lower 3–9 empty, of which lowest 1–3 frequently with apex attenuate, remainder increasing in length upwards, apices acuminate or acute, next 3 largest, 6–7 × 3 mm, boat-shaped, glabrous except for well-marked ciliate margin, apex obtuse, toothed, but

rolled so appearing narrow, and almost acute until unfolded, uppermost glume enclosed within the two preceding, slightly shorter. *Flowers* 2, lower male, upper bisexual. *Perianth bristles* 6, delicate, 6–7 mm long, white, villous in distal half. *Stamens* 3, filaments persistent 5–7 mm long after anthesis, ribbon-like; anthers linear-oblong, large, apiculate, early deciduous. *Style* trifid, dark brown, coarsely plumose, proximal portion of style persistent as short to long beak on fruit. *Nutlet* rounded trigonous, narrowed basally into funnel-shaped extension $\pm 1/4$ length of globose portion, 5×3 mm in total length and width, faintly 3-ridged longitudinally, whitish to pale fawn; surface smooth to slightly transversely rugose.

Distribution

Costularia natalensis is restricted in its distribution to southeastern Africa (Fig. 16). In particular, the species is present at higher elevation (1070–2130 m) along the chain of individually isolated highlands roughly paralleling part of the coastline, e.g. in South Africa the Wolkberg, Sabie and Graskop areas of the Mpumalanga Drakensberg (Browning & Gordon-Gray, 1996). Mount Mulanje in Malawi is the northernmost known locality, and the southernmost distribution of the species reaches the area of Pietermaritzburg in Kwazulu-Natal (South Africa).

Ecology

According to observations by Browning & Gordon-Gray (1996), populations are mostly very localised, often small, and in KwaZulu-Natal, frequently limited to a few scattered, solitary plants which grow on steep, rocky slopes, associated with coarse grasses in the zone between forest and grassland. A slightly more extensive population grows along banks of small streams and among boulders, where nutrients particularly phosphates are in short supply and other vegetation is scarce (Restionaceae and short grasses), in the Chimanimani National Park (Zimbabwe; Browning & Gordon-Gray, 1996). In Mozambique, several (small) subpopulations are also found on quartzite sandstone in the Chimanimani Mts, and on rocks in the submontane grasslands of Mt Gorongosa and Serra Choa. Plants of this species have been collected from Mount Mulanje in Malawi (which is composed of seynite, quartz-seynite and granite rock materials), in particular from the eastern zone of the Biosphere Reserve (Lichenya and Chambe). It is restricted to higher elevations.

Phenology

Flowering/fruitlet specimens were collected from November to May.

Conservation status

Costularia natalensis is restricted in its distribution to southeastern Africa (Malawi, Mozambique, Zimbabwe, Swaziland, South Africa). It is found at higher elevations in rocky areas in grassland and shrubland. Threats affecting part of the range of the species include fire, fuelwood collection, illegal logging of natural forests and plantation forestry, invasive species

and potential mining. Although the population of this species is believed to be decreasing (Browning & Gordon-Gray, 1996), it currently does not fall within the criteria for any of the threat categories, and is therefore assessed as Least Concern. However, further research is needed to investigate threats and population size.

Notes

In our molecular phylogenetic results (Fig. 1), *C. natalensis* is found in a clade with three other *Costularia* species, two of which are here described as new to science, i.e. *C. andringitrensis* and *C. itremoensis*. Although Burt (1988) indicated some morphological variety between plants of different localities, Browning & Gordon-Gray (1996), who studied specimens from the entire distribution range of *C. natalensis*, found no clear discontinuities that may provide a basis for subdivision of the species.

12. *Costularia pantopoda* (Baker) C.B. Clarke ex Cherm., Arch. Bot. Bull. Mens. 7 (Mém. 2): 80. 1936 \equiv *Cladium pantopodum* Baker, J. Linn. Soc., Bot. 21: 451. 1885 \equiv *Mariscus pantopodus* (Baker) Fernald, Rhodora 25: 54. 1923 \equiv *Machaerina pantopoda* (Baker) T. Koyama, Bot. Mag. (Tokyo) 69: 65. 1956 \equiv *Tetraria pantopoda* (Baker) T. Koyama, J. Fac. Sci. Univ. Tokyo, Sect. 3, Bot. 8: 75. 1961.

Type (implicitly lectotypified by Clarke 1894: 658). Madagascar, Central Madagascar, R. Baron 2072 (holotype: [K000244886!](#), isotypes: K!, [MNHN-P-P00459988!](#)).

Conservation status

Costularia pantopoda is restricted in its distribution to south-central Madagascar, and occurs in at least one protected area, i.e. the Andringitra National Park. Threats to this taxon need further investigation but in the Andringitra National Park, where most collections have been made, its habitat and area of occupancy are impacted negatively by cattle grazing and by fires started for pastoral reasons which can easily get out of control and enter the National Park (*I. Larridon, pers. obs. 2010; F. Rakotonasolo, pers. obs. 2017*). In other areas, fire (natural and man-made) and disturbance of its habitat as a result of logging, firewood collection and charcoal may also affect this species. Based on 10 georeferenced herbarium specimens, the taxon occurs in at least six locations and has an estimated AOO of 40 km² and an EOO of 9478 km². Using IUCN criteria, this variety can be assessed as VU B1ab(ii,iii)+2ab(ii,iii).

12a. *Costularia pantopoda* (Baker) C.B. Clarke ex Cherm. var. *pantopoda*—Figs. 5, 17, 18
Medium-sized perennial herb, up to c. 65 cm height. *Culm* 25–30 cm \times 2.5–3 mm. *Basal leaves* distichous; leaf sheaths 6–7 (–9) \times c. 2 cm, brownish-purple, very wide compared to the leaf blades; leaf blades usually enrolled and thus appearing much narrower than the leaf sheaths, 1–4 mm wide when enrolled, up to c. 7 mm when flattened, leathery, margins scabrid. *Cauline leaves* 1–2, 5–7 mm wide margins scabrid, sheaths brownish. *Inflorescence* a panicle 10–35 cm long, quite tight, narrow; inflorescence bracts 5–10, brown to dark purple. *Peduncles* longest 4–5

cm, erect to arching downwards, flattened, margins scabrid. *Pedicels of the spikelets* erect, 2–6 mm, margins scabrid. *Spikelets* lanceolate, 6–7.5 × 1.5–2.3 mm. *Glumes* 5–8, the largest 5–6.5 mm long, dark purplish-brown to nearly black, the lower 3–6 empty, ovate, scabrid on the keel, ciliate at the apex, increasing in length; 2 upper flowering glumes ovate-lanceolate. *Flowers* 2, lower male, upper bisexual. *Perianth bristles* 6, much longer than the nutlet, plumose, long ciliate. *Stamens* 3; anthers linear, shortly apiculate. *Style* trifid, long; style base hispidulous, triangular, persistent. *Nutlet* broad obovoid triangular, somewhat rugulose, 1.75 mm; beak 1 mm, almost as wide as the nutlet.

Distribution

Costularia pantopoda var. *pantopoda* occurs in the Fianarantsoa province and in the south of the Antananarivo province of Madagascar (Fig. 5).

Ecology

Rocky areas at high elevation (1300–2500 m).

Phenology

Flowering specimens were collected from December to April, fruiting specimens from September to November.

Notes

Baker (1885: 451) originally described *Cladium pantopodum* based on two specimens collected by Baron (2072 and 3316). In 1894, Clarke placed this species in *Costularia* and split it up into two species, i.e. *Costularia pantopoda* (Baron 2072) and *Costularia baronii* (Baron 3316, Baron 4517, Baron 5061, Scott Elliot 1989). However, and Clarke (1894: 658) failed to provide a description for *Costularia baronii*, this species was only made valid in Clarke (1898: 274) where he provides a short diagnosis for it at the end of his treatment of *C. natalensis*.

12b. *Costularia pantopoda* var. *gracilescens* Kük., Repert. Spec. Nov. Regni Veg. 41: 67 (1939) —Fig. 6

Type. Madagascar, Antananarivo, Antsirabe, 1600 m, January 1919, H. Perrier de la Bâthie 2729 (holotype: P; isotype: [K000244887!](#)).

Culms slender, 0.9 mm wide. *Basal leaves* with the leaf sheath little larger than the narrow leaf blades (up to c. 1.5 mm wide). *Inflorescence* fairly contracted panicle, with fewer spikelets, and composed of 4–5 fascicles. *Peduncles* longest 8.5 cm. *Pedicels of the spikelets* 2–8 mm long, flattened, margins scabrid. *Spikelets* 6–7 × 1.5 mm, purple. *Glumes* clearly distichous, lower 5–6 empty glumes mucronate to acute, upper 2 fertile glumes obtuse. *Perianth bristles* 6, 5.5 mm long, pale to rusty-coloured, antrorsely ciliate. *Stamens* 3; anthers 3.5 mm, linear, apiculate. *Nutlet* immature.

998

999 **Distribution**

1000 Known from a single collection made near Antsirabe in the Antananarivo province of
1001 Madagascar (Fig. 5).

1002

1003 **Ecology**

1004 The only known collection was found growing in a marsh at c. 1600 m in elevation.

1005

1006 **Phenology**

1007 The taxon was collected in flower in January.

1008

1009 **Notes**

1010 Kükenthal (1939) described this new variety based on a single specimen (*Perrier de la Bâthie*
1011 2729). Though likely present in P, the holotype could not be traced. This variety most closely
1012 resembles *Costularia pantopoda* var. *pantopoda*.

1013

1014 **12c. *Costularia* cf. *pantopoda***—Figs. 5, 19

1015 Specimen. Madagascar, Toamasina, Ambatofinandrahana-Amborompotsy, Mountains W
1016 of Itremo (W Betsileo), 1500–1700 m, 17–22 January & 18–22 April 1955, *H. Humbert* 30061
1017 ([MNHN-P-P01908604](#)!)

1018

1019 **Notes**

1020 A single specimen was collected from the mountains West of Itremo, at an elevation of 1500 to
1021 1700 m outside of the Itremo protected area delimitation. Grazing, fire (natural and man made)
1022 to renew cattle pasture and mining are the major threats which affect this habitat. This specimen
1023 appears as sister to *C. pantopoda* in the phylogenetic hypothesis (Fig. 1). This specimen shows
1024 some similarities with *C. itremoensis* (Figs. 12, 19).

1025

1026 **13. *Costularia purpurea*** Cherm., Bull. Soc. Bot. France 69: 722. 1922 publ. 1923 ≡ *Tetraria*
1027 *purpurea* (Cherm.) T.Koyama, J. Fac. Sci. Univ. Tokyo, Sect. 3, Bot. 8: 75. 1961—Fig. 14

1028 *Type (lectotype designate here)*. Madagascar, Antananarivo, Analamanga,
1029 Manjakandriana, forest E of Ambatolaona, 1300–1450 m, 11 November 1912, *R. Viguiet & H.*
1030 *Humbert* 1231 (holotype: [MNHN-P-P00459990](#)!; isotype: [MNHN-P-P00459991](#)!,
1031 [MNHN-P-P00459992](#)!).

1032 = *Costularia laxa* Cherm., Bull. Soc. Bot. France 69: 723. 1922 publ. 1923 ≡ *Tetraria*
1033 *laxa* (Cherm.) T.Koyama, J. Fac. Sci. Univ. Tokyo, Sect. 3, Bot. 8: 75. 1961. *Type (lectotype*
1034 *designated here)*. Madagascar, Antsiranana, Manongarivo, 1000 m, May 1909, *H. Perrier de la*
1035 *Bâthie* 2639 (holotype: [MNHN-P-P00459983](#)!; isotype: [MNHN-P-P00459984](#)!).

1036 *Perennial herb* up to 2.5 m tall. *Caudex* covered in lateral roots can be present (0.7–1.5
1037 cm in diam.). *Culms* more or less robust, 50–1.3 m × 2.5–4 mm. *Basal leaves* distichous; leaf

sheaths 3.5–8.5 cm × up to 9 mm, brownish-purple; leaf blades leathery, (28–)50–80 cm × 3–8 mm, flat or slightly inrolled, margins scabrid, tapering to a very acute tip. *Cauline leaves* 3–4, far apart; sheaths long tubular, purplish or brownish-green, mouth obliquely cut. *Inflorescence* a quite narrow panicle with lax partial inflorescences to a lax complex panicle, 50–90(–165) cm long; inflorescence bracts 8–14; sheaths purple. *Peduncles* unequal, up to 13 cm, flattened, margins scabrid. *Pedicels of the spikelets* 5–10(–25) mm flattened, margins scabrid, straight or curved. *Spikelets* oblong-lanceolate, very flattened, (4–)6–10 × (1.2–)2 mm. *Glumes* (dark) purple, ovate-lanceolate, (sub)acute, keel scabrid, edges minutely ciliate, (3–)5–9 lower glumes empty, 2 upper fertile, largest 4–5.5 mm long. *Flowers* (1–)2, either both bisexual (generally only lower perfecting a nutlet), or lower bisexual and upper functionally male, more rarely lower male and upper bisexual, or rarely a single bisexual flower. *Perianth bristles* 6, equalling or surpassing the nutlet, pale reddish-brown, plumose below, densely and shortly ciliolate above. *Stamens* 3; anthers linear, reddish, connective very shortly apiculate. *Style* long, deeply trifid, thin, brownish; style base triangular, hispidulous, pale, persistent. *Nutlet* rounded-trigonal, (1.5–)2–3 mm × 1–1.5 mm, greyish-brown, rugulose- reticulate, with an attenuate base; beak (1–)1.5–2.5 mm long, base as wide as the nutlet.

Distribution

Costularia purpurea is endemic to Madagascar, occurring in the Antananarivo, Antsiranana, Fianarantsoa, Toamasina and Toliara provinces (Fig. 14).

Ecology

The species is found infrequent on granitic formations in ericaceous shrubland, grassland and open forests at mid to high elevations (500–1850 m).

Phenology

Flowering/fruiting specimens were collected from November to May. Young inflorescences can be observed on the specimens collected in September-October, while old inflorescences remain on the plants until September.

Conservation status

The species occurs in a range of protected areas including: Analamazaotra (Périnet), Andohahela, Didy National Park (NP), Kalambatritra, Manjakatomp Ankaratra, Manongarivo Reserve, Marojejy NP, Masoala NP, and Ranomafana NP. Based on its known and projected distribution, it is likely also present in among others Midongy du Sud NP. Since no specific threats are known to the species, and because it has a wide distribution in Madagascar (AOO = 132 km², EOO = 218,948 km²) and occurs in a range of protected areas, *Costularia purpurea* is here assessed as Least Concern.

Notes

The specimen *Hildebrandt 3752a* was listed as a syntype of *C. recurva* (accepted name *C. leucocarpa*) but conforms to circumscription of *C. purpurea*. A lot of confusion existed between *C. leucocarpa* and *C. purpurea*, with many *C. purpurea* specimens at the G, K and P herbaria identified as *C. recurva*. However, these species are quite different in morphology, with *C. purpurea* characterised by longer, flatter, narrower, darker spikelets generally bearing more glumes compared to *C. leucocarpa*.

Most herbarium specimens listed as *C. laxa* by Chermeson (1937) and Kükenthal (1939) are very immature and difficult to identify. Although the clade with two accessions originally identified as *C. laxa* and three accessions identified as *C. purpurea* is well supported in the molecular phylogenetic hypothesis, the taxa themselves are not (Fig. 1). Chermeson (1937) and Kükenthal (1939) distinguished *C. laxa* from *C. purpurea* based on it laxer inflorescence, fewer empty glumes (3–4 vs. 5–9) and perianth bristles much overtopping the nutlets. However, this distinction does not hold as variation in inflorescence branching and number of spikelets per inflorescence is gradual, even in the specimens listed by Chermeson (1937) as *C. laxa* spikelets often have more than 4 empty glumes, and in *Perrier de la Bâthie 2639* (MNHN-P-P00459983), selected as holotype of *C. laxa*, the size of the nutlets varies from 1.6–2 mm plus a beak of 0.7–1.3 which is not that much shorter than the perianth bristles and similar to many specimens conforming to the description of *C. purpurea*.

This species is sister to *C. melicoides* of the Mascarenes. *Costularia melicoides* is unusual in perfecting a nutlet in lower of the two fertile glumes, while most *Costularia* species perfect a nutlet in the upper fertile glume. In *C. purpurea*, the number and sex of the flowers is variable with many of the collected specimens also perfecting a nutlet in the lower fertile glume. These sister species also share a similar build and size.

Costularia laxa var. *macrantha* Cherm. (1925: 21) is here excluded from *C. laxa* as we consider it to be synonymous with *C. robusta* (see more discussion under that taxon).

14. *Costularia robusta* (Cherm.) Larridon, **comb. et stat. nov.** \equiv *Costularia baronii* C.B. Clarke var. *robusta* Chermeson, Bull. Soc. Bot. France 69: 723 (1922) \equiv *Costularia pantopoda* var. *robusta* (Cherm.) Kük., Repert. Spec. Nov. Regni Veg. 41: 68 (1939)—Fig. 5

Type. Madagascar. Antsiranana, Diana, [Tsaratanana Reserve, Maromokotro], 2700 m, December 1912, *H. Perrier de la Bâthie 2503* (holotype: [MNHN-P-P00459966](#)!).

= *Costularia laxa* var. *macrantha* Cherm., Bull. Soc. Bot. France 72: 21. 1925. *Type:* MADAGASCAR, Antsiranana, Diana, [Tsaratanana Reserve, Maromokotro], 2000 m, Janaury 1923, *H. Perrier de la Bâthie 15652* (holotype: [MNHN-P-P00459967](#)!; isotype: [MNHN-P-P00459968](#)!).

Very robust and tall perennial herb with a strongly developed and long (c. 1 m) caudex. *Culms* 0.8–2 m \times c. 6 mm, robust. *Basal leaves* with very wide leaf sheaths (15–20 mm), persistent at the base of the culm above the caudex. *Inflorescence* an elongate, narrow panicle with very numerous, crowded spikelets; inflorescence branches erect, not more than 5 cm long.

Pedicels of the spikelets short, not patent. *Spikelets* 6–7 mm long. *Glumes* 12–14, up to 7 mm long, purplish black.

Distribution

Costularia robusta is only known from the Manongarivo, Marojejy and Tsaratanana protected areas and their environs in the Antsiranana province of Madagascar (Fig. 5).

Ecology

This taxon occurs in ericoid shrublands at (very) high elevations (1400–2800 m).

Phenology

Inflorescences are initiated in April and flower/fruit between October and January. Old inflorescences are still visible on the plants in April when the new inflorescence are formed.

Conservation

Costularia robusta is restricted in its distribution to the Antsiranana province of Madagascar, and occurs in at least three protected areas, i.e. Manongarivo, Marojejy and Tsaratanana. Threats to this taxon need further investigation but fire (natural and man-made) and disturbance of its habitat as a result of logging, firewood collection and charcoal may affect this species. Based on 11 georeferenced herbarium specimens, this species occurs in at least six locations and has an estimated AOO of 28 km² and an EOO of 2947 km². Using IUCN criteria, *C. robusta* can be assessed as VU B1ab(ii,iii)+2ab(ii,iii).

Notes

Kükenthal (1939) also listed the specimen *Humbert 3344* when creating the combination under *C. pantopoda*. We here exclude this specimen collected at Pic d'Ivohibe Reserve in the Fianarantsoa region from *C. robusta* and place it in *C. baronii*. Kükenthal (1939) listed specimen *Perrier de la Bâthie 16398* under *C. pantopoda* var. *baronii*. Although this specimen could not be found in the P herbarium, it is very likely to be *C. robusta* as it is from the same locality as the other positively identified specimens of *C. robusta* by the same collector at the same time.

Costularia laxa var. *macrantha* looks very similar to *C. robusta* but has paler glumes. Since its type specimen was collected at a somewhat lower elevation than the specimens identified as *C. robusta*, this is unsurprising since glume colour in Cyperaceae often darkens with elevation in the same species (*I. Larridon, pers. observ.*). Kükenthal (1939) discusses the presence of a caudex in *C. robusta*. Although this is not clearly visible in the specimens he cited, the type specimen of *C. laxa* var. *macrantha* clearly has a well developed and long caudex. We here consider *C. laxa* var. *macrantha* to be a synonym of *C. robusta*. Kükenthal (1939) did realise a potential relationship between *C. laxa* var. *macrantha* and *C. pantopoda* as he included a comment under *C. laxa* var. *macrantha* to the effect of “Much deviating from the typical form of *C. laxa* and approaching *C. pantopoda* in appearance, but the glumes have the colour of *C.*

laxa (purple and pale green) and the perianth bristles are more ciliate than plumose. Possibly, a hybrid between *C. laxa* and *C. pantopoda*.” Kükenthal (1939) listed a second specimen under *C. laxa* var. *macrantha*: *H. Humbert 6358* (not seen) collected in Beampingaratra, Toliara province. We here exclude this specimen from *C. robusta*.

15. *Costularia xipholepis* (Baker) Henriette & Senterre, *Phytotaxa* 231: 34 (2015). \equiv *Cladium xipholepis* Baker, *Fl. Mauritius*: 424 (1877). \equiv *Schoenus xipholepis* (Baker) Summerh., *Bull. Misc. Inform. Kew* 1928: 394 (1928), p.p. quoad holotypus sed excl. Horne 626—Fig. 20

Type. Seychelles, *Wright s.n.* (holotype K!).

Adapted from Henriette et al. (2015): *Perennial herb* up to 2.5 m tall, caespitose, forming dense clumps. *Culm* c. 80 cm \times 3.5–5 mm, cylindrical, robust. *Basal leaves* distichously arranged, densely set, numerous; dead leaves persistent, the older ones abscising above the leaf sheath; green leaves 7–12 on each side, arcuate; leaf-sheath 4–6 \times 2.9–4 cm, semi-cylindrical, thick, yellowish, margins dark red, ciliate distally; leaf blade 75–123 cm \times 7–10 mm, not pseudopetiolate, linear, gradually tapering towards apex, upwardly concave in section, coriaceous, glabrous, smooth, mid-green, margin entire, with tiny ascendant prickles, apex acute, slightly rounded, not apiculate, midrib not distinct, longitudinally striate. *Cauline leaves* 3–5; leaf-sheath 4.5–5.2 \times 1.2–1.5 cm, closed, dark red at base, yellowish distally; leaf-blade shorter than in basal leaves, decreasing in length towards the apex of the culm, 40–74 cm \times 8–10 mm. *Inflorescence* 55–140 cm, narrow (7–15 cm wide), with 4–5 orders of branching; inflorescence bracts 9–14, up to 17–27 cm long at basal nodes, 2.5–3.0 cm long at distal nodes. *Peduncles* unequal (longer in basal fertile nodes), 15–360 mm long, 1–7 per node, erect, compressed, slender, smooth. *Pedicels of the spikelets* 7.5–8.0 mm long, straight. *Spikelets* densely clustered, 7–8 \times 1.0–1.2 mm, lanceolate, reddish-brown; rachilla persistent, straight. *Glumes* 7–9, distichous, completely enclosing the rachilla at base, deciduous, lanceolate, smooth, reddish-brown on the sides and towards apex, margins glabrous, apices with a straight awn (longer in basal glume), midrib distinct; basal empty glumes 5–7, the lowest glume 2.5–3.7 \times 1.0–1.5 mm, subsequent glumes 3.3–6.8 \times 1.4–2.0 mm; lower fertile glume 6.0–6.5 mm long, slightly shorter than the last empty glume; upper fertile glume 6.1–6.5 mm long, enclosed in the previous glume. *Flowers* 2, lower male, upper bisexual. *Perianth bristles* 6, well developed, 5.5–7.3 mm long, 2–3 times longer than the nutlet (beak included), sparsely plumose. *Stamens* 3, 5.0–7.6 mm long, not protruding or slightly protruding; anthers oblong, 1.7–4.2 mm long, yellow. *Style* trifid, 7.5–10.3 mm long (including stigmas). *Nutlet* stalked at maturity, trigonous, wingless, obovoid, 2 mm long (excluding beak), 0.8–0.9 mm diam., golden brown, beak with a constriction at the junction with the nutlet, 1.5 mm long, long-acute, 0.4 mm wide at base, ciliate.

Distribution

Based on Henriette et al. (2015), *Costularia xipholepis* is endemic to the Seychelles and restricted to Mahé and has been found in three locations all situated in the Morne Seychellois National Park: Congo Rouge (B. Senterre & T. Stévant, observation record, 20 July 2014,

4.6512°S, 55.44126°E, 610 m), Copolia and Pérard (Fig. 20). Two additional locations were recently discovered at Mont Sébert and at Glacis Sarcelles (*B. Senterre, pers. comm.*) (Fig. 20).

Ecology

This species is restricted to the herbaceous fringe of lower montane inselbergs (*Henriette et al., 2015*). It has been observed from 500 to 821 m but was more abundant on the site at the higher elevation, which corresponds to an altitudinal belt named the tree fern lower montane belt (*Senterre, 2011; Senterre & Wagner, 2014; Senterre et al., 2009; Henriette et al., 2015*). At Copolia, it has a patchier distribution, growing on rock crevices and along fissures where the soil is damp. In all sites, it grows in association with the species previously known as *Costularia hornei* (basionym *Schoenus hornei*, nom. cons. prop.; *Larridon et al., 2017b*); which is now placed in the new genus *Xyroschoenus* (*Larridon et al., 2018a*). Since the exclusion of *Xyroschoenus hornei* from *Costularia*, only one species of *Costularia* is known to occur on the Seychelles.

Phenology

Flowering/fruiting specimens were collected between March to December.

Conservation status

Following *Henriette et al. (2015)*, *Costularia xipholepis* is rare and highly localised. Three sub-populations representing three locations, 1.4 to 2.4 km apart, separated from each other by unsuitable habitat (i.e. wet forests) are within the Morne Seychellois National Park and appear healthy, with limited risks from invasive species. The AOO for the Congo Rouge population is 10 m², Copolia 6,000 m², and Pérard 20,000 m² (*Henriette et al., 2015*). The two newly discovered sub-populations, at Mont Sébert and at Glacis Sarcelles are not well known, but the Mont Sébert one is about the same size as the one of Congo Rouge (small), while the Glacis Sarcelles population is comparable to the Copolia one (*Senterre, pers. comm.*) resulting in an estimated AOO totalling approx. 0.032 km². Its EOO was estimated at approximately 5.9 km² (*Bachman et al., 2011*). Both AOO and EOO fall within the limits of Critically Endangered status under criterion B. According to *Henriette et al. (2015)* and based on IUCN (2012) criterion B, with an EOO <5000 km², AOO <500 km², number of locations ≤5, and a projected decline of the quality of the habitat as a result of climate change, this species can be classified as Endangered EN B1ab(iii)+2ab(iii).

Notes

Henriette et al. (2015) noted that among the known species of *Costularia* s.s. only one presents some similarity with *Costularia xipholepis*, i.e. *Costularia baronii* from Madagascar, as both species have long leaves and hypogynous bristles much longer than the nutlet with relatively few empty glumes. However, our molecular phylogenetic results point at a sister relationship with *C.*

melleri. The sister pair *C. melleri* (Madagascar) and *C. xipholepis* (Seychelles) in turn are sister to a clade encompassing the species *C. humbertii* (Madagascar) and *C. cadetii* (La Réunion).

Conclusions

The genus *Costularia* is redelimited to represent a monophyletic entity including 15 species. Although the species diversity is largely found in Madagascar, our results indicate that the genus dispersed once to Africa (Malawi, Mozambique, South Africa, Swaziland, Zimbabwe), twice to the Mascarenes (La Réunion, Mauritius), and once to the Seychelles (Mahé). Three-quarters of the species are threatened with extinction, because of restricted distribution ranges and human impact. A full taxonomic treatment is provided, including an identification key to all species, formal descriptions of two new species from Madagascar (*C. andringitrensis* and *C. itremoensis*) and one new species from La Réunion (*C. cadetii*), and two taxa previously recognised as varieties of *C. pantopoda* are here recognised at species level (*C. baronii* and *C. robusta*).

Acknowledgements

We thank the curators of the BR, G, GENT, K, L, MAU, P, TAN, and UPOS herbaria for the loan of specimens, imaging of specimens, and/or permission to carry out destructive sampling. We thank Pieter Asselman and Viki Vandomme for their help with the molecular lab work at Ghent University. The ANGAP Madagascar National Parks authority, the general secretariat of the AETFAT congress 2010 and the staff of the MBG office in Antananarivo are acknowledged for their help in securing collecting permits (N°082/10/MEF/SG/DGF/DCB.SAP/SLRSE - Isabel Larridon) for Cyperaceae in Madagascar and their help organising the expedition. We thank Vonona Randrianasolo (Kew Madagascar Conservation Centre), and Franck Rakotonasolo and Jacqueline Razanatsoa (Herbier du Parc Botanique et Zoologique de Tsimbazaza) for aiding with fieldwork. Thank you to Modesto Luceño and his student José Ignacio Márquez-Corro for collecting additional material of the new species from La Réunion for this study. Jeremy Bruhl, Wim Huygh and Modesto Luceño are acknowledged for providing photos of *Costularia* species. Special thanks to Juliet Beentje and Jane Browning for making line drawings of many of the species.

References

- Bachman S, Moat J, Hill AW, de la Torre J, Scott B. 2011. Supporting Red List threat assessments with GeoCAT: geospatial conservation assessment tool, in: Smith, V., Penev, L. (Eds.), e-Infrastructures for data publishing in biodiversity science. *ZooKeys* 150:117–126 DOI 10.3897/zookeys.150.2109.
- Bauters K, Meganck K, Goetghebeur P, Larridon I. 2018. Molecular phylogenetic study of *Scleria* subgenus *Hypoporum* (Sclerieae, Cyperoideae, Cyperaceae) reveals several new species to science. *PLoS ONE* 13(9): e0203478 DOI 10.1371/journal.pone.0203478.

- 1274 **Bauters K, Larridon I, Goetghebeur P. Accepted.** A taxonomic study of *Scleria* subgenus
1275 *Hypoporum*: synonymy, typification and a new species-level identification key.
1276 *Phytotaxa*.
- 1277 **Browning J, Gordon-Gray KD. 1995.** Studies in Cyperaceae in southern Africa 26: Glume
1278 epidermal silica deposits as a character in generic delimitation of *Costularia* and
1279 *Cyathocoma* as distinct from *Tetraria* and other allies. *South African Journal of Botany*
1280 **61**:66–71 DOI [10.1016/S0254-6299\(15\)30481-6](https://doi.org/10.1016/S0254-6299(15)30481-6).
- 1281 **Browning J, Gordon-Gray KD. 1996.** Studies in Cyperaceae in southern Africa 29: *Costularia*
1282 *natalensis*, an endangered species. *South African Journal of Botany* **62**:155–159 DOI
1283 [10.1016/S0254-6299\(15\)30616-5](https://doi.org/10.1016/S0254-6299(15)30616-5).
- 1284 **Browning J, Gordon-Gray KD. 1999.** Studies in Cyperaceae in southern Africa 33: a new
1285 monotypic genus, *Capeobolus*. *South African Journal of Botany* **65**:218–222 DOI
1286 [10.1016/S0254-6299\(15\)30977-7](https://doi.org/10.1016/S0254-6299(15)30977-7).
- 1287 **Bruhl JJ. 1995.** Sedge genera of the world: relationships and a new classification of the
1288 Cyperaceae. *Australian Systematic Botany* **8**:125–305 DOI [10.1071/SB9950125](https://doi.org/10.1071/SB9950125).
- 1289 **Burt, B.L. 1988.** Cyperaceae. In: O.M. Hilliard & B.L. Burt (eds), Notes on some plants of
1290 southern Africa chiefly from Natal 14. *Notes of the Royal Botanic Garden Edinburgh*
1291 **45**:77–78.
- 1292 **Catalogue des herbiers de Genève. 2018.** Conservatoire & Jardin botaniques de la Ville de
1293 Genève. <http://www.ville-ge.ch/musinfo/bd/cjb/chg/> accessed 30.10.2018.
- 1294 **Chermeson H. 1937.** Cypéracées. In: H. Humbert (ed.), Flore de Madagascar 29: 1–335.
1295 Imprimerie officielle, Tananarive.
- 1296 **Clarke CB. 1894.** Cyperaceae. In: T. Durand & H. Schinz (eds), Conspectus Florae Africae 5:
1297 526–692. Jardin Botanique de l'Etat, Bruxelles.
- 1298 **Clarke CB. 1897-1898.** Cyperaceae. In: W.T. Thiselton-Dyer (ed.), Flora Capensis 7: 149–310.
1299 Reeve, London.
- 1300 **Faranirina L. 2017.** *Costularia melleri*. The IUCN Red List of Threatened Species 2017:
1301 e.T88508987A88509022. DOI [10.2305/IUCN.UK.2017-](https://doi.org/10.2305/IUCN.UK.2017-2.RLTS.T88508987A88509022.en)
1302 [2.RLTS.T88508987A88509022.en](https://doi.org/10.2305/IUCN.UK.2017-2.RLTS.T88508987A88509022.en).
- 1303 **Galán Díaz J, Bauters K, Rabarivola L, Xanthos M, Goetghebeur P, Larridon I.**
1304 **Submitted.** A revision of *Scleria* (Cyperaceae) in Madagascar. *Blumea*.
- 1305 **Goetghebeur P. 1986.** *Genera Cyperacearum. Een bijdrage tot de kennis van de morfologie,*
1306 *systematiek en fylogenesen van de Cyperaceae-genera*. Unpublished D. Phil. Thesis, Ghent
1307 University, Belgium.
- 1308 **Govaerts R, Simpson DA, Goetghebeur P, Wilson KL, Egorova T, Bruhl J. 2018.** *World*
1309 *checklist of Selected Plant Families*. Cyperaceae. The Board of Trustees of the Royal
1310 Botanic Gardens, Kew. Published on the Internet; <http://www.kew.org/wcsp/monocots/>
1311 accessed 01.06.2018.
- 1312 **Henriette E, Larridon I, Morel C, Goetghebeur P, Senterre B. 2015.** Revision of the genus
1313 *Costularia* (Cyperaceae: Schoeneae) for the flora of the Seychelles, including the

- rediscovery and resurrection of a rare endemic species. *Phytotaxa* **231**:31–41 DOI [10.11646/phytotaxa.231.1.3](https://doi.org/10.11646/phytotaxa.231.1.3).
- HerbCat. 2018.** The Herbarium Catalogue, Royal Botanic Gardens, Kew. Published on the Internet <http://www.kew.org/herbcat/> accessed 30.10.2018.
- IUCN. 2012.** IUCN red list categories and criteria: version 3.1, vol 4, 2nd edn. IUCN, Gland, Switzerland.
- IUCN Standards and Petitions Subcommittee. 2014.** Guidelines for Using the IUCN Red List Categories and Criteria. Version 11. Prepared by the Standards and Petitions Subcommittee. Downloadable from <http://www.iucnredlist.org/documents/RedListGuidelines.pdf>.
- IUCN. 2018.** The IUCN Red List of Threatened Species. Version 2018-2. <http://www.iucnredlist.org/> accessed 14.11.2018.
- Katoh K, Asimenos G, Toh H. 2009.** Multiple alignment of DNA sequences with MAFFT. *Methods in Molecular Biology* **537**:39–64 DOI [10.1007/978-1-59745-251-9_3](https://doi.org/10.1007/978-1-59745-251-9_3).
- Katoh K, Standley DM. 2013.** MAFFT multiple sequence alignment software version 7: improvements in performance and usability. *Molecular Biology and Evolution* **30**:772–780 DOI [10.1093/molbev/mst010](https://doi.org/10.1093/molbev/mst010).
- Kearse M, Moir R, Wilson A, Stones-Haves S, Cheung M, Sturrock S, Buxton S, Cooper A, Markowitz S, Duran C, Thierer T, Ashton B, Meintjes P, Drummond A. 2012.** Geneious Basic: an integrated and extendable desktop software platform for the organization and analysis of sequence data. *Bioinformatics* **28**:1647–1649 DOI [10.1093/bioinformatics/bts199](https://doi.org/10.1093/bioinformatics/bts199).
- Kükenthal G. 1939.** Vorarbeiten zu einer Monographie der Rhynchosporoideae 5. *Repertorium Specierum Novarum Regni Vegetabilis* **46**:65–76
- Lanfear R, Calcott B, Ho SYW, Guindon S. 2012.** PartitionFinder: combined selection of partitioning schemes and substitution models for phylogenetic analyses. *Molecular Biology and Evolution* **29**:1695–1701 DOI [10.1093/molbev/mss020](https://doi.org/10.1093/molbev/mss020).
- Larridon I, Verboom GA, Muasya AM. 2017a.** (2555) Proposal to conserve the name *Tetraria* (Cyperaceae) with a conserved type. *Taxon* **66**: 1226–1227 DOI [10.12705/665.22](https://doi.org/10.12705/665.22).
- Larridon I, Govaerts R, Goetghebeur P. 2017b.** (2554) Proposal to conserve the name *Schoenus hornei* (Cyperaceae) with a conserved type. *Taxon* **66**: 1225–1226 DOI [10.12705/665.21](https://doi.org/10.12705/665.21).
- Larridon I, Semmouri I, Bauters K, Viljoen JA, Prychid CJ, Muasya AM, Bruhl JJ, Wilson KA, Goetghebeur P. 2018a.** Molecular phylogenetics of the genus *Costularia* (Schoeneae, Cyperaceae) reveals multiple distinct evolutionary lineages. *Molecular Phylogenetics and Evolution* **126**:196–209 DOI [10.1016/j.ympev.2018.04.016](https://doi.org/10.1016/j.ympev.2018.04.016).
- Larridon I, Verboom GA, Muasya AM. 2018b.** Revised delimitation of the genus *Tetraria* (Cyperaceae, tribe Schoeneae, *Tricostularia* clade). *South African Journal of Botany* **118**: 18–22. DOI [10.1016/j.sajb.2018.06.007](https://doi.org/10.1016/j.sajb.2018.06.007).

- 1353 **Miller MA, Pfeiffer W, Schwartz T. 2011.** The CIPRES science gateway: a community
1354 resource for phylogenetic analyses. Proceedings of the 2011 TeraGrid Conference:
1355 Extreme Digital Discovery: 41. ACM, New York [DOI 10.1145/2016741.2016785](https://doi.org/10.1145/2016741.2016785).
- 1356 **Moat J, Smith P. 2012.** Atlas of the Vegetation of Madagascar. Royal Botanic Gardens, Kew.
- 1357 **Müller J, Müller K, Neinhuis C, Quandt D. 2010.** PhyDEPhylogenetic Data Editor, version
1358 0.9971. Available at <http://www.phyde.de/> (accessed on 10 January 2016).
- 1359 **Muséum national d'Histoire naturelle. 2018.** Vascular plants (P).
1360 <https://science.mnhn.fr/institution/mnhn/collection/p/item/search> accessed 30.10.2018.
- 1361 **Rambaut A, Drummond AJ. 2007.** Tracer, a MCMC Trace Analysis Tool. Institute of
1362 Evolutionary Biology, University of Edinburgh. <http://beast.bio.ed.ac.uk/>.
- 1363 **Ronquist F, Teslenko M, van der Mark P, Ayres DL, Darling A, Höhna S, Larget B, Liu L,
1364 Suchard MA, Huelsenbeck JP. 2012.** MrBayes 3.2: Efficient Bayesian phylogenetic
1365 inference and model choice across a large model space. *Systematic Biology* **61**:539–542
1366 [DOI 10.1093/sysbio/sys029](https://doi.org/10.1093/sysbio/sys029).
- 1367 **Seberg O. 1986.** *Schoenoides*, a new genus of Cyperaceae from Tasmania. *Willdenowia* **16**:181–
1368 186 <http://www.jstor.org/stable/3996315>.
- 1369 **Seberg O. 1988a.** Leaf anatomy of *Oreobolus* R.Br. and *Schoenoides* Seberg. *Botanische
1370 Jahrbücher für Systematik, Pflanzengeschichte und Pflanzengeographie* **110**:187–214.
- 1371 **Seberg O. 1988b.** Taxonomy, phylogeny, and biogeography of the genus *Oreobolus* R. Br.
1372 (Cyperaceae), with comments on the biogeography of South Pacific continents. *Botanical
1373 Journal of the Linnean Society* **96**:119–195 [DOI 10.1111/j.1095-8339.1988.tb00632.x](https://doi.org/10.1111/j.1095-8339.1988.tb00632.x).
- 1374 **Semmouri I, Bauters K, Lévillé-Bourret E, Starr JR, Goetghebeur P, Larridon I. 2018.**
1375 The phylogeny and systematics of Cyperaceae, the evolution and importance of embryo
1376 morphology. *Botanical Review* [DOI 10.1007/s12229-018-9202-0](https://doi.org/10.1007/s12229-018-9202-0).
- 1377 **Senterre B. 2011.** On the forest types of the Seychelles. *Kapisen* **12**:5–7.
- 1378 **Senterre B, Gerlach J, Mougil J, Matatiken DE. 2009.** Old growth mature forest types and
1379 their floristic composition along the altitudinal gradient on Silhouette Island (Seychelles)
1380 - the telescoping effect on a continental mid-oceanic island. *Phytocoenologia* **39**:157–174
1381 [DOI 10.1127/0340-269X/2009/0039-0157](https://doi.org/10.1127/0340-269X/2009/0039-0157).
- 1382 **Senterre B, Wagner M. 2014.** Mapping Seychelles habitat-types on Mahé, Praslin, Silhouette,
1383 La Digue and Curieuse. Consultancy Report. Government of Seychelles, United Nations
1384 Development Programme, Victoria, Seychelles, 119 pp.
- 1385 **Shorthouse, David P. 2010.** SimpleMapppr, an online tool to produce publication-quality point
1386 maps. Available at <http://www.simplermappr.net> (accessed 29 October 2018).
- 1387 **Stamatakis A. 2014.** RAXML Version 8: a tool for phylogenetic analysis and post-analysis of
1388 large phylogenies. *Bioinformatics* **30**:1312–1313 [DOI 10.1093/bioinformatics/btu033](https://doi.org/10.1093/bioinformatics/btu033).
- 1389 **Stöver BC, Müller KF. 2010.** TreeGraph 2: combining and visualizing evidence from different
1390 phylogenetic analyses. *BMC Bioinformatics* **11**:7 [DOI 10.1186/1471-2105-11-7](https://doi.org/10.1186/1471-2105-11-7).
- 1391 **Thiers B, continuously updated.** Index herbariorum. Available at
1392 <http://sweetgum.nybg.org/science/ih/> (accessed on 20 November 2018).

- 1393 **Turland NJ, Wiersema JH, Barrie FR, Greuter W, Hawksworth DL, Herendeen PS,**
- 1394 **Kusber W-H, Li De-Zhu, Marhold K, May TW, McNeill J, Monro AM, Prado J,**
- 1395 **Price MJ, Smith GF. 2018.** International Code of Nomenclature for algae, fungi, and
- 1396 plants (Shenzhen Code) adopted by the Nineteenth International Botanical Congress
- 1397 Shenzhen, China, July 2017. Koeltz Botanical Books.
- 1398 **Verboom GA. 2006.** A phylogeny of the schoenoid sedges (Cyperaceae: Schoeneae) based on
- 1399 plastid DNA sequences, with special reference to the genera found in Africa. *Molecular*
- 1400 *Phylogenetics and Evolution* **38**:79–89 [DOI 10.1016/j.ympev.2005.05.012](https://doi.org/10.1016/j.ympev.2005.05.012).
- 1401 **Viljoen J-A, Muasya AM, Barrett RL, Bruhl JJ, Gibbs AK, Slingsby JA, Wilson KL,**
- 1402 **Verboom GA. 2013.** Radiations and repeated transoceanic dispersal of Schoeneae
- 1403 (Cyperaceae) through the southern hemisphere. *American Journal of Botany* **100**:2494–
- 1404 2508 [DOI 10.3732/ajb.1300105](https://doi.org/10.3732/ajb.1300105).
- 1405 **Vrijdaghs A, Reynders M, Larridon I, Muasya AM, Smets E, Goetghebeur P. 2010.**
- 1406 Spikelet structure and development in Cyperoideae (Cyperaceae): a monopodial general
- 1407 model based on ontogenetic evidence. *Annals of Botany* **105**:555–571 [DOI](https://doi.org/10.1093/aob/mcq010)
- 1408 [10.1093/aob/mcq010](https://doi.org/10.1093/aob/mcq010).
- 1409 **Vrijdaghs A, Reynders M, Muasya AM, Larridon I, Goetghebeur P, Smets E. 2011.**
- 1410 Morphology and development of spikelets and flowers in *Cyperus* and *Pycneus*
- 1411 (Cyperaceae). *Plant Ecology and Evolution* **144**:44–63 [DOI 10.5091/plecevo.2011.436](https://doi.org/10.5091/plecevo.2011.436).
- 1412 **Zhang X, Marchant A, Wilson KL, Bruhl JJ. 2004.** Phylogenetic relationships of *Carpha* and
- 1413 its relatives (Schoeneae, Cyperaceae) inferred from chloroplast *trnL* intron and *trnL-trnF*
- 1414 intergenic spacer sequences. *Molecular Phylogenetics and Evolution* **31**:647–657 [DOI](https://doi.org/10.1016/j.ympev.2003.09.004)
- 1415 [10.1016/j.ympev.2003.09.004](https://doi.org/10.1016/j.ympev.2003.09.004).

Table 1(on next page)

Overview of the taxa of *Costularia* s.s. as accepted in literature.

Seven species of *Costularia* s.s. were treated by *Chermezon (1937)*, nine species were treated by *Kükenthal (1939)*, and 11 species are currently recognised (*Govaerts et al., 2018*).

<i>Chermezon (1937)</i>	<i>Kükenthal (1939)</i>	<i>Govaerts et al. (2018)</i>
<i>C. brevifolia</i> Cherm.	<i>C. brevifolia</i> Cherm.	<i>C. brevifolia</i> Cherm.
<i>C. laxa</i> Cherm.	<i>C. laxa</i> Cherm.	<i>C. laxa</i> Cherm.
<i>C. laxa</i> var. <i>macrantha</i> Cherm.	<i>C. laxa</i> var. <i>macrantha</i> Cherm.	
<i>C. recurva</i> C.B.Clarke	<i>C. elongata</i> (Kunth) Kük.	<i>C. melicoides</i> (Poir.) C.B.Clarke
<i>C. melleri</i> (Baker) C.B.Clarke ex Cherm.	<i>C. leucocarpa</i> (Ridl.) H.Pfeiff.	<i>C. leucocarpa</i> (Ridl.) H.Pfeiff.
<i>C. baronii</i> var. <i>microcarpa</i> Cherm.	<i>C. melleri</i> (Baker) C.B.Clarke ex Cherm.	<i>C. melleri</i> (Baker) C.B.Clarke ex Cherm.
	<i>C. microcarpa</i> (Cherm.) Kük.	<i>C. microcarpa</i> (Cherm.) Kük.
	<i>C. natalensis</i> C.B.Clarke	<i>C. natalensis</i> C.B.Clarke
<i>C. pantopoda</i> (Baker) C.B.Clarke ex Cherm.	<i>C. pantopoda</i> (Baker) C.B.Clarke ex Cherm.	<i>C. pantopoda</i> (Baker) C.B.Clarke ex Cherm.
	<i>C. pantopoda</i> var. <i>gracilescens</i> Kük.	<i>C. pantopoda</i> var. <i>gracilescens</i> Kük.
<i>C. baronii</i> C.B.Clarke	<i>C. pantopoda</i> var. <i>baroni</i> (C.B.Clarke) Kük.	<i>C. pantopoda</i> var. <i>baroni</i> (C.B.Clarke) Kük.
<i>C. baronii</i> var. <i>robusta</i> Cherm.	<i>C. pantopoda</i> var. <i>robusta</i> (Cherm.) Kük.	<i>C. pantopoda</i> var. <i>robusta</i> (Cherm.) Kük.
<i>C. purpurea</i> Cherm.	<i>C. purpurea</i> Cherm.	<i>C. purpurea</i> Cherm.
		<i>C. xipholepis</i> (Baker) Henriette & Senterre

Figure 1(on next page)

50% majority consensus multiple-locus BI tree with the associated PP values and the bootstrap values of the multiple-locus ML tree.

Only bootstrap values above 70% and posterior probabilities above 0.7 are shown.




Figure 2

Distribution map of *Costularia andringitrensis*, *C. brevifolia*, *C. humbertii* and *C. melleri* in Madagascar.

The distribution of the species was mapped using SimpleMappr.




Figure 3(on next page)

Illustration of *Costularia andringitrensis* (Larridon et al. 2010-0140 GENT).

(A) habit; (B) inflorescence; (C) spikelet; (D) bisexual flower and glume; (E) male flower and glume. Scale bars: A-B = 3 cm; C-E = 3 mm. Illustration drawn by Juliet Beentje.



Figure 4

Habitat and morphology of *Costularia andringitrensis*.

(A) plant *in situ*; (B) imaged plant. Photos taken by Wim Huygh in Adringitra National Park, Madagascar on 18 April 2010.



Figure 5

Distribution map of *Costularia itremoensis*, *C. microcarpa* and *C. pantopoda* in Madagascar.

The distribution of the species was mapped using SimpleMappr.




Figure 6

Habitat and morphology of *Costularia baronii*.

(A) Plant *in situ*; (D) Inflorescence detail. Photos taken by Wim Huygh in Adringitra National Park, Madagascar on 18 April 2010.



Figure 7 (on next page)

Illustration of *Costularia brevifolia* (Razakamalala 4866 K).

(A) habit; (B) leaf tip detail; (C) lower leaf detail; (D) detail of inflorescence; (E) male flower and glume. Scale bars: A = 3 cm, B-D = 1 cm, E = 5 mm. Illustration drawn by Juliet Beentje.





Figure 8(on next page)

Illustration of *Costularia cadetii*.

(A) habit (*Luceño & Guzmán 4ML09 UPOS*); (B) inflorescence (*Luceño & Guzmán 4ML09 UPOS*); (C) detail of inflorescence (*Márquez-Corro et al. 04JMC17 UPOS*); (D) spikelet (*Márquez-Corro et al. 04JMC17 UPOS*); (E) bisexual flower (*Márquez-Corro et al. 04JMC17 UPOS*); (F) anther (*Luceño & Guzmán 4ML09 UPOS*); (G) nutlet (*Márquez-Corro et al. 04JMC17 UPOS*). Scale bars: A-B = 3 cm, C-E = 3 mm, F = 1 mm, G = 3 mm. Illustration drawn by Juliet Beentje.



Figure 9

Habitat and morphology of *Costularia cadetii*.

(A) habitat; (B) habit; (C) inflorescence; (D) base of plant. Photos taken by Jeremy Bruhl (A, C, D) in La Réunion at Nez Coupé de Sainte-Rose on 4 January 2011 and by Modesto Luceño (B) in La Réunion at Piton de la Fournaise-Pas de Bellocombe on 1 January 2009.



Figure 10

Distribution map of *Costularia cadetii* and *C. melicoides* in La Réunion and Mauritius (Mascarene Islands).

The distribution of the species was mapped using SimpleMappr.




Figure 11(on next page)

Illustration of *Costularia humbertii* (Miller & Lowry II 4175 GENT).

(A) habit; (B) detail of inflorescence; (C) spikelet; (D) male flower; (E) anther; (F) bisexual flower and glume. Scale bars: A = 3 cm, B-C = 1 cm, D-F = 3 mm. Illustration drawn by Juliet Beentje.



Figure 12(on next page)

Illustration of *Costularia itremoensis*.

(A) habit (*Humbert 30060 P*); (B) spikelet (*Humbert & Swingle 4995 P*); (C) bisexual flower and glume (*Humbert & Swingle 4995 P*); (D) male flower and glume (*Humbert & Swingle 4995 P*); (E) anther and filament, immature (*Humbert & Swingle 4995 P*). Scale bars: A = 3 cm, B-D = 5 mm, E = 3 mm. Illustration drawn by Juliet Beentje.



Figure 13(on next page)

Illustration of *Costularia leucocarpa* (Larridon et al. 2010-0237 GENT).

(A) habit; (B) detail of inflorescence; (C) flowering spikelet (some glumes already fallen off); (D) bisexual flower; (E) male flower; (F) nutlet. Scale bars: A = 3 cm, B = 5 mm, C-F = 3 mm.

Illustration drawn by Juliet Beentje.



Figure 14

Distribution map of *Costularia leucocarpa* and *C. purpurea* in Madagascar.

The distribution of the species was mapped using SimpleMappr.




Figure 15(on next page)

Illustration of *Costularia natalensis* (Hilliard & Burt 14504 NU).

(A) habit; (B) spikelet; (C) terminal fertile glumes bearing a bisexual and a male flower, note six feathery bristles, three filaments, anthers already shed. Scale bars: A = 4 cm, B-C = 2 mm. Illustration drawn by Jane Browning.



Figure 16

Distribution map of *Costularia natalensis* in southeastern Africa.

The distribution of the species was mapped using SimpleMappr.




Figure 17 (on next page)

Illustration of *Costularia pantopoda* var. *pantopoda* (Larridon et al. 2010-0144 GENT).

(A) habit; (B) inflorescence matching the habit; (C) spikelet; (D) lowest glumes of spikelets; (E) rest of glumes lower to upper, abaxial view; (F) bisexual flower; (G) male flower; (H) nutlet. Scale bars: A-B = 3 cm, C-H = 3 mm. Illustration drawn by Juliet Beentje.



Figure 18

Habitat and morphology of *Costularia pantopoda* var. *pantopoda*.

(A) Plant *in situ*; (B) Inflorescence detail. Photos taken by Muthama Muasya in Adringitra National Park, Madagascar on 18 April 2010.



Figure 19(on next page)

Illustration of *Costularia cf. pantopoda* (Humbert 30061 P).

(A) habit; (B) inflorescence matching the habit; (C) detail of inflorescence; (D) spikelet; (E) bisexual flower and glume; (F) male flower and glume. Scale bars: A-B = 3 cm, C = 1 cm, D-F = 3 mm. Illustration drawn by Juliet Beentje.



Figure 20

Distribution map of *Costularia xipholepis* in the Seychelles (Mahé island).

The distribution of the species was mapped using SimpleMapper.

